



**ADAMS COUNTY**  
COLORADO

# PRELIMINARY PLAT

(MAJOR SUBDIVISION)

**Community & Economic Development Department**  
**Planning & Development**

4430 S. Adams County Pkwy., 1st Floor, Suite W2000B

Brighton, CO 80601-8218

Phone: 720.523.6800

Website: [adcogov.org](http://adcogov.org)

A major subdivision shall only be used to divide parcels of twenty (20) or more acres or create five (5) or more lots. The first approval required is the preliminary plat. The preliminary plat provides an in-depth analysis of the proposed subdivision, including design of geologic hazards, environmentally sensitive areas, required services, vehicular/pedestrian circulation, and the relationship to surrounding land uses.

Please include this page with your submittal. More information about checklist items can be found on page 2-3. Submittal instructions are at the top of page 2.

## Required Checklist Items

- ☒ Development Application Form
- ☒ Written Explanation
- ☒ Preliminary Plat
- ☒ Legal Description
- ☒ Conceptual Site Plan
- ☒ Proof of Ownership
- ☒ Proof of Water and Sewer Services
- ☒ Proof of Utilities
- ☒ Certificate of Taxes Paid
- ☒ Storm Drainage Study
- ☒ Trip Generation Analysis
- ☐ Receipt of Payment from the Colorado Geological Survey

## Supplementary Checklist Items

- ☐ School Impact Analysis
- ☐ Neighborhood Meeting Summary

## **Fees Due When Application is Deemed Complete**

|                                    |         |
|------------------------------------|---------|
| Major Subdivision Preliminary Plat | \$1,400 |
|------------------------------------|---------|

## **Guide to Development Application Submittal**

All applications shall be submitted electronically to [epermitcenter@adcogov.org](mailto:epermitcenter@adcogov.org). If the submittal is too large to email as an attachment, the application may be sent as an unlocked MS OneDrive link. Alternatively, the application may be delivered on a flash drive to the Community & Economic Development Department. Once a complete application has been received, fees will be invoiced and payable online at [www.permits.adcogov.org](http://www.permits.adcogov.org).

---

### **Written Explanation of the Project:**

- A clear and concise description of the proposal. Please include the purpose of the project, and improvements that will be made to the site.
- Identify the number of tracts and number of lots being proposed.
- Please keep written explanation to three pages or less.

### **Preliminary Plat Prepared by Registered Land Surveyor**

- A map or maps together with supporting documentation of certain described land providing permanent and accurate record of the legal description, dedications, exact size, shape, and location of lots, blocks, streets, easements, and parcels.

### **Legal Description:**

- Please provide the text of the legal description on a separate page from the plat document itself. We will need to be able to copy and paste this text to process public notifications. Your surveyor can easily provide this for you.

### **Conceptual Site Plan Showing Proposed Development:**

- A detailed drawing of existing and proposed improvements
- Including:
  - Streets, roads, and intersections
  - Driveways, access points, and parking areas
  - Existing and proposed structures, wells, and septic systems,
  - Easements, utility lines, and no build or hazardous areas
  - Scale, north arrow, and date of preparation
- An Improvement Location Certificate or Survey may be required during the official review

### **Proof of Ownership:**

- A deed may be found in the Office of the Clerk and Recorder
- A title commitment is prepared by a professional title company.

### **Proof of Water and Sewer:**

- Public utilities - A written statement from the appropriate water & sanitation district indicating that they will provide service to the property **OR** a copy of a current bill from the service provider
- Private utilities - Well permit(s) information can be obtained from the Colorado State Division of Water Resources at (303) 866-3587. A written statement from Adams County Health Department indicating the viability of obtaining Onsite Wastewater Treatment Systems

### **Proof of Utilities (Gas, Electric, etc.):**

- A written statement from the appropriate utility provider indicating that they will provide service to the property
- Copy of a current bill from the service provider

### **Certificate of Taxes Paid:**

- A Statement of Taxes Paid is not the equivalent of a Certificate of Taxes Paid. Colorado State Statutes require a Certificate of Taxes Paid to be submitted with this application.
- All taxes on the subject property must be paid in full. A certificate of taxes paid can be obtained in-person at the Adams County Treasurer's office. As of July 2023, the cost is \$10.
- You may also request a Certificate of Taxes Paid by e-mailing [treasurer@adcogov.org](mailto:treasurer@adcogov.org), and credit card payment can be processed by telephone.

**Storm Drainage Study:**

- This plan should be prepared in accordance with the “Level 1 Storm Drainage Plan” criteria as defined in Appendix item B-3 of the Adams County Development Standards and Regulations. Most importantly, it needs to clearly identify a viable storm outfall location, and floodplain/floodway boundaries.

**Trip Generation Analysis:**

- This analysis should be conducted by a traffic engineer include total vehicle trips per day and peak hour volumes generated by the proposed development.

**Receipt of Payment from Colorado Geological Survey:**

- The Colorado Geological Survey requires a fee payment for the review of any subdivision. These payments can be made at: <https://commerce.cashnet.com/MinesCGS>. A receipt of this pre-payment must be provided in this application submittal.

**Discretionary Checklist Items**

**School Impact Analysis:**

- Contact the applicable school district for the analysis. If the school district does not provide this, please include an email from them.
- Should include the increase in elementary, middle, and high school students and the existing school sites and structure of the applicable district in which the subdivision is proposed to be located.

**Neighborhood Meeting Summary**

- Please refer to Section 2-01-02 of the Adams County Development Standards and Regulations for the specific requirements regarding time, location, and notice.
- A written summary shall be prepared including the materials submittal presented at the meeting, any issues identified at the meeting, and how those issues have been addressed.

Community & Economic  
Development Department  
www.adcogov.org



4430 South Adams County Parkway  
1st Floor, Suite W2000  
Brighton, CO 80601-8204  
PHONE 720.523.6800  
FAX 720.523.6998

## DEVELOPMENT APPLICATION FORM

### Application Type:

|                                                    |                                          |                                          |
|----------------------------------------------------|------------------------------------------|------------------------------------------|
| <input type="checkbox"/> Conceptual Review         | <input type="checkbox"/> Preliminary PUD | <input type="checkbox"/> Temporary Use   |
| <input type="checkbox"/> Subdivision, Preliminary  | <input type="checkbox"/> Final PUD       | <input type="checkbox"/> Variance        |
| <input type="checkbox"/> Subdivision, Final        | <input type="checkbox"/> Rezone          | <input type="checkbox"/> Conditional Use |
| <input type="checkbox"/> Plat Correction/ Vacation | <input type="checkbox"/> Special Use     | <input type="checkbox"/> Other: _____    |

**PROJECT NAME:** Clear Creek Transit Village Final Plat, Filing No. 3

### APPLICANT

Name(s): Andy Reese, Kimley-Horn and Associates Phone #: 970-852-6858  
Address: 3325 South Timberline Road Suite 130  
City, State, Zip: Fort Collins, CO 80525  
2nd Phone #: Email: Andy.Reese@kimley-horn.com

### OWNER

Name(s): Clear Creek Investment Holdings, LLC Phone #: 303-955-5291  
Address: 900 Castleton Road, Suite 118  
City, State, Zip: Castle Rock, CO 80109  
2nd Phone #: Email:

### TECHNICAL REPRESENTATIVE (Consultant, Engineer, Surveyor, Architect, etc.)

Name: Andy Reese, Kimley-Horn and Associates Phone #: 970-852-6858  
Address: 3325 South Timberline Road Suite 130  
City, State, Zip: Fort Collins, CO 80525  
2nd Phone #: Email: Andy.Reese@kimley-horn.com

**DESCRIPTION OF SITE**

|                              |                                     |
|------------------------------|-------------------------------------|
| Address:                     | 6001 Federal Boulevard              |
| City, State, Zip:            | Denver, CO 80221                    |
| Area (acres or square feet): | +/- 68,645 SF (1.58 AC)             |
| Tax Assessor Parcel Number   | 0182508208100                       |
| Existing Zoning:             | Clear Creek Transit Village PUD/PDP |
| Existing Land Use:           | Vacant                              |
| Proposed Land Use:           | Residential and Mixed-Use           |

Have you attended a Conceptual Review? YES ☐ NO ☒ (N/A)

If Yes, please list PRE#:

I hereby certify that I am making this application as owner of the above described property or acting under the authority of the owner (attached authorization, if not owner). I am familiar with all pertinent requirements, procedures, and fees of the County. I understand that the Application Review Fee is non-refundable. All statements made on this form and additional application materials are true to the best of my knowledge and belief.

Name:  Date:

Owner's Printed Name

Name:

DocuSigned by:  
A87C0E2F07144A3...  
Owner's Signature

Community & Economic  
Development Department  
www.adcogov.org



4430 South Adams County Parkway  
1st Floor, Suite W2000  
Brighton, CO 80601-8204  
PHONE 720.523.6800  
FAX 720.523.6998

### Preliminary Plat Subdivision Checklist Requirements

1. **Subdivision Name, Subtitle:** Name of subdivision at the top of the sheet, followed by a subtitle identifying the section, township and range information along with County and State.
2. **Property Description:** An accurate and clear property (legal) description of the overall boundary of the subdivision with the acreage of the subdivision. All courses in the property (legal) description shall be shown and labeled on the plat drawing, with all bearings having the same direction as called out in the legal description. The only exception being where more than one description is required, going a different direction over the same course. The direction shall then hold for the description having more weight (i.e., the overall boundary) for purposes of the plat. If both record and "as-measured" dimensions are being used, show both and clearly label on the plat drawing. Point of commencement and/or point of beginning shall be clearly labeled on the plat drawing.
3. **Ownership Certificate:**

Know all men by these presents that (owner name(s)), being the sole owner of the following described tract of land:

Legal Description

Have (Has) by these presents laid out, platted and subdivided the same into lots, streets and easements as shown on this plat under the name and style of (subdivision name).

4. **Dedication Statements:** Statements of land to be dedicated to the County for parks or other public uses, grants of easements and dedication of public streets to the Adams County are required.
  - a. All plats with public streets shall have the following sentence in the dedication statement:

All public streets are hereby dedicated to Adams County for public use.
  - b. All plats with public easements and/or tracts must have the following sentence in the dedication statement:

Community & Economic  
Development Department  
www.adcogov.org



4430 South Adams County Parkway  
1st Floor, Suite W2000  
Brighton, CO 80601-8204  
PHONE 720.523.6800  
FAX 720.523.6998

The undersigned does hereby dedicate, grant and convey to Adams County those Public Easements (and tracts) as shown on the plat; and further restricts the use of all Public Easement to Adams County and/or its assigns, provided however, that the sole right and authority to release or quitclaim all or any such Public Easements shall remain exclusively vested in Adams County.

- c. All plats with private streets shall have the following sentence in the dedication statement:

All private streets (insert names) are privately owned and maintained by (list owner name, Owner's Association, etc.).

- d. All plats with other tracts being dedicated to the County shall have:

- (1) A sentence in the dedication statement similar to "Tract X is hereby dedicated to Adams County for public use".
- (2) A special numbered plat note defining the purpose and perpetual maintenance responsibility for the tract such as "Tract X is for public drainage, landscaping, trail and open space with maintenance of the surface being vested in the (District Name) Special Maintenance District".

5. **Surveyor's Statement:** Statement by a registered land surveyor, professionally licensed by the State of Colorado, to the effect that the layout represents a survey made by him and that the monuments thereon actually exist as located and that all dimensional and other details are correct.

**6. Access Provisions:**

- a. **Statement Restricting Access:** A statement restricting access rights across the right-of-way lines of major highways, parkways, streets or freeways, where required as a provision of approval.

**7. Easement Statement:**

Six-foot (6') wide utility easements are hereby dedicated on private property adjacent to the front lot lines of each lot in the subdivision. In addition, eight-foot (8') wide dry utility easements are hereby dedicated around the perimeter of tracts, parcels and/or open space areas. These easements are dedicated to Adams County for the benefit of the applicable utility providers for the installation, maintenance, and replacement of utilities.

Community & Economic  
Development Department  
www.adcogov.org



4430 South Adams County Parkway  
1st Floor, Suite W2000  
Brighton, CO 80601-8204  
PHONE 720.523.6800  
FAX 720.523.6998

Utility easements shall also be granted within any access easements and private streets in the subdivision. Permanent structures, improvements, objects, buildings, wells, water meters and other objects that may interfere with the utility facilities or use thereof (Interfering Objects) shall not be permitted within said utility easements and the utility providers, as grantees, may remove any Interfering Objects at no cost to such grantees, including, without limitation, vegetation.

#### 8. Storm Drainage Facilities Statement:

The policy of the County requires that maintenance access shall be provided to all storm drainage facilities to assure continuous operational capability of the system. The property owners shall be responsible for the maintenance of all drainage facilities including inlets, pipes, culverts, channels, ditches, hydraulic structures, and detention basins located on their land unless modified by the subdivision development agreement. Should the owner fail to maintain said facilities, the County shall have the right to enter said land for the sole purpose of operations and maintenance. All such maintenance cost will be assessed to the property owners.

#### 9. Layout: The exact layout including:

- a. **Boundary Lines:** The subdivision boundary will be clearly distinguishable from other map lines by use of a distinct line type and/or thickness. All lines will be labeled with a complete bearing and distance, and all curves will be labeled with a central angle (delta), radius and arc length. Radial bearings and/or chord bearings will be provided for all nontangent curves. All dimensions to be determined by accurate field survey which must balance and close within limit of one in five thousand (5,000). Show adjacent and/or intersecting plat/deed lines and label appropriately to include recording information (book and page and/or reception number).
- b. **Streets:** All street rights of way defined by the plat will be clearly distinguishable from other map lines by use of a distinct line type and/or thickness. All lines will be labeled with a complete bearing and distance, and all curves will be labeled with a central angle (delta), radius and arc length. Radial bearings and/or chord bearings will be provided for all nontangent curves. Widths shall be labeled from each right-of-way line normal to the corresponding street center line. All street center lines defined by the plat will be clearly distinguishable from other map lines by use of distinct line type and/or thickness. All lines will be labeled with a complete bearing and distance and all curves will be labeled with a central angle (delta), radius and arc length. Radial bearings and/or chord bearings will be provided for all nontangent curves. The

Community & Economic  
Development Department  
www.adcogov.org



4430 South Adams County Parkway  
1st Floor, Suite W2000  
Brighton, CO 80601-8204  
PHONE 720.523.6800  
FAX 720.523.6998

plat shall show the right-of-way lines, widths, locations and street names of all existing and proposed public or private streets:

- (1) Within the proposed subdivision, and
  - (2) Immediately abutting the proposed subdivision, and
  - (3) Any private street shall include the designation "(Private)" immediately following street name; any other private right of way that is not named shall include the designation "(Private)" in a manner that clearly conveys such a status.
- c. **Easements:** All easements as required by Adams County and other public and quasi-public agencies. Said easements shall be clearly labeled to include width, use and identification as public or private, if necessary. Tie to property lines and annotate with bearings and distances as necessary. Clearly show and label all existing easements, to include width and recording information, that cross, abut or are located within the subdivision boundary.
  - d. **Lots And Blocks:** All lines of lots, blocks and other parcels of land defined by the plat will be clearly distinguishable from other map lines by use of a distinct line type and/or thickness. All lines will be labeled with a complete bearing and distance and all curves will be labeled with a radius and arc length. Lots must close to one in five thousand (5,000).
  - e. **Readability:** All line annotation and all other text will be easily and clearly readable. No text shall overwrite other text or be overwritten by map lines.
  - f. **Leader Lines:** Use leader lines whenever a dimension is not clearly and unmistakably associated with a given line, line segment or arc.
  - g. **Multiple Sheets:** Whenever a plat drawing spans multiple sheets, clear and well labeled match lines and a key map shall be included on each sheet. Labels will be of the nature "See Sheet of ". Duplicate street names, widths, lot numbers, tract names, easement labeling or any such labeling when any feature is shown on multiple sheets.
  - h. **Identification System:** All lots and blocks in the subdivision shall be numbered, beginning with the numeral "1" and continuing consecutively throughout the tract, with no omissions or duplications. All tracts shall be likewise labeled beginning with the letter "A". Lots and tracts shall be labeled with the area of the lot or tract.

Community & Economic  
Development Department  
[www.adcogov.org](http://www.adcogov.org)



4430 South Adams County Parkway  
1st Floor, Suite W2000  
Brighton, CO 80601-8204  
PHONE 720.523.6800  
FAX 720.523.6998

- i. **Legend:** Provide a legend which designates all lines and symbols except where called out on plat drawing.
  - j. **Inundation Mark:** The plat shall clearly show the 100-year floodplain line. Reference the appropriate FEMA panel by which the location of this line has been determined.
10. **Easements:** Book and page and/or reception number for all existing and newly created easements.
11. **Adjacent Subdivision:** Names of adjacent platted areas along with the reception and/or plat book and page number shall be shown. If unplatted, so indicate. Existing street rights of way that intersect the subdivision boundary or are adjacent to said boundary lines shall be clearly labeled with the street name, right of way width and appropriate deed or plat recording information wherein the right of way is defined. Show and label all existing lots and blocks that are immediately adjacent to the subdivision boundary.
12. **Basis Of Bearing:** A clearly defined basis of bearings shall be provided, both verbally and graphically. All monumentation defining said line shall be shown and labeled on the plat drawing. When said line is not common with the subdivision boundary, it shall be accurately tied to the boundary with bearings and distances.
13. **Monuments:** All monuments used to determine and/or describe a boundary (including basis of bearings, point of beginning and point of commencement) shall be shown and clearly labeled on the plat drawing. Monuments for corners defined by the plat, or otherwise found to be missing in the field, shall be placed and set in accord with the requirements of the State of Colorado.
14. **Not A Part Of Subdivision:** All areas enclosed within the subdivision boundary which do not constitute a part of the subdivision shall be labeled "Not a part of this subdivision". All lines pertaining to such areas shall be dashed.
15. **Square Footage:** The area in square feet of all lot and tracts sought to be platted.
16. **Closure Sheets:** One copy of the computed closure sheets for the subdivision boundary.
17. **Other Information:** All other information required by State law.



September 4, 2026

**RE: *Clear Creek Transit Village  
Major Subdivision Application***

Mr. Greg Barnes:

The Clear Creek Transit Village Planning Area 5 Project is proposing a Major Subdivision Preliminary Plat within the existing Clear Creek Transit Village development (Final Plat PRC2023-00011 and Reception Number 2025000012280). The project intends to subdivide Block 5 of the approved plat into 24 lots and 3 tracts. The proposed subdivision will also dedicate easements for the proposed project.

Please note that several documents that are on the submittal checklist have been carried over from the overall development. These include a receipt of payment from the Colorado Geological Survey and a School Impact Analysis were previously submitted to the County with the overall Clear Creek Transit Village development. Additionally, a neighborhood meeting was held as part of the previous applications, so a new meeting was not conducted as part of this application.

Thank you for reviewing this request. We appreciate your attention and consideration regarding this matter.

Sincerely,

**KIMLEY-HORN AND ASSOCIATES, INC.**

A handwritten signature in black ink that reads "Andy Reese".

Andy Reese  
Project Manager

A handwritten signature in black ink that appears to read "Bryce Willaby".

Bryce Willaby, PE  
Project Engineer

**BOARD OF COUNTY COMMISSIONERS APPROVAL**

LOT 1, BLOCK 5, CLEAR CREEK TRANSIT VILLAGE FINAL PLAT, COUNTY OF ADAMS, STATE OF COLORADO.

THE UNDERSIGNED DOES HEREBY DEDICATE, GRANT AND CONVEY TO ADAMS COUNTY THOSE PUBLIC EASEMENTS AND TRACTS AS SHOWN ON THE PLAT; AND FURTHER RESTRICTS THE USE OF ALL PUBLIC EASEMENTS TO ADAMS COUNTY AND/OR ITS ASSIGNS, PROVIDED HOWEVER, THAT THE SOLE RIGHT AND AUTHORITY TO RELEASE OR QUITCLAIM ALL OR ANY SUCH PUBLIC EASEMENTS SHALL REMAIN EXCLUSIVELY VESTED IN ADAMS COUNTY.

OWNER: CLEAR CREEK INVESTMENT HOLDINGS LLC

THE FOREGOING OWNERSHIP AND DEDICATION CERTIFICATE WAS ACKNOWLEDGED BEFORE ME THIS

MY COMMISSION EXPIRES: \_\_\_\_\_ WITNESS MY HAND AND SEAL

BUILDER CIRCLE FINANCE LLC, A DELAWARE LIMITED LIABILITY COMPANY

TITLE: \_\_\_\_\_

THE FOREGOING INSTRUMENT WAS ACKNOWLEDGED BEFORE ME

THIS \_\_\_\_ DAY OF \_\_\_\_\_, 202\_\_ BY \_\_\_\_\_

MY COMMISSION EXPIRES: \_\_\_\_\_ WITNESS MY HAND AND SEAL

NOTARY PUBLIC

APPROVED BY THE ADAMS COUNTY BOARD OF COUNTY COMMISSIONERS THIS \_\_\_\_\_ DAY OF \_\_\_\_\_  
A.D. 202\_

CHAIR

APPROVED AS TO FORM

THIS PLAT IS PREPARED FOR THE PURPOSE OF CREATING AND DEDICATING THE LOTS, TRACTS, AND EASEMENTS SHOWN HEREON.

1. ACCORDING TO COLORADO LAW YOU MUST COMMENCE ANY LEGAL ACTION BASED UPON ANY DEFECT IN THIS SURVEY WITHIN THREE YEARS AFTER YOU FIRST DISCOVER SUCH DEFECT. IN NO EVENT MAY ANY ACTION BASED UPON ANY DEFECT IN THIS SURVEY BE COMMENCED MORE THAN TEN YEARS FROM THE DATE OF THE CERTIFICATION SHOWN HEREON.

2. BEARINGS ARE BASED ON THE EAST LINE OF THE NORTHWEST QUARTER OF SAID SECTION 8, ASSUMED TO BEAR NORTH 00°00'36" EAST, A DISTANCE OF 2635.75 FEET, MONUMENTED AT THE CENTER QUARTER CORNER OF SAID SECTION 8 BY A 3.25" ALUMINUM CAP, STAMPED "CHARLES H RUSSELL T3S R68W C 1/4 S8 1988 PLS 23519 ADAMS COUNTY" IN RANGE BOX AND AT THE NORTH QUARTER CORNER OF SAID SECTION 8, AS MONUMENTED BY A 3.25" ALUMINUM CAP, STAMPED "COLO DEPT OF TRANSPORTATION T3S R68W S5 1/4 COR S8 1994 PLS 26288" IN RANGE BOX.

3. THE LINEAL UNIT USED IN THE PREPARATION OF THIS SURVEY IS THE U.S. SURVEY FOOT. PURSUANT TO C.R.S. 38-52-103(2) METRIC CONVERSION IS: ONE METER EQUALS 3937/1200 FEET.

4. THIS PROPERTY IS LOCATED WITHIN ZONE X, OTHER AREAS - ZONE X (UNSHADED), DEFINED AS "AREAS DETERMINED TO BE OUTSIDE THE 0.2% ANNUAL CHANCE FLOODPLAIN" AND ZONE AE DEFINED AS "SPECIAL FLOOD HAZARD AREAS (SFHAS) SUBJECT TO INUNDATION BY THE 1% ANNUAL CHANCE FLOOD (BASE FLOOD ELEVATIONS DETERMINED)". AS SHOWN ON THE FLOOD INSURANCE RATE MAPS FOR COUNTY OF ADAMS, COMMUNITY PANEL NUMBER 80001C0592H, MAP EFFECTIVE DATE MARCH 5, 2007. THE ACCURACY OF ANY FLOOD HAZARD DATA SHOWN ON THIS SURVEY IS SUBJECT TO MAP SCALE UNCERTAINTY AND TO ANY OTHER UNCERTAINTY IN LOCATION OR ELEVATION ON THE REFERENCED FLOOD INSURANCE RATE MAPS.

5. THE POLICY OF THE COUNTY REQUIRES THAT MAINTENANCE ACCESS SHALL BE PROVIDED TO ALL STORM DRAINAGE FACILITIES TO ASSURE CONTINUOUS OPERATIONAL CAPABILITY OF THE SYSTEM. THE PROPERTY OWNERS SHALL BE RESPONSIBLE FOR THE MAINTENANCE OF ALL DRAINAGE FACILITIES INCLUDING INLETS, PIPES, CULVERTS, CHANNELS, DITCHES, HYDRAULIC STRUCTURES, AND DETENTION BASINS LOCATED ON THEIR LAND UNLESS MODIFIED BY THE SUBDIVISION DEVELOPMENT AGREEMENT. SHOULD THE OWNER FAIL TO MAINTAIN SAID FACILITIES, THE COUNTY SHALL HAVE THE RIGHT TO ENTER SAID LAND FOR THE SOLE PURPOSE OF OPERATIONS AND MAINTENANCE. ALL SUCH MAINTENANCE COST WILL BE ASSESSED TO THE PROPERTY OWNERS.

6. THIS PLAT WAS PREPARED USING THE TITLE COMMITMENT FOR TITLE INSURANCE ISSUED BY LAND TITLE GUARANTY COMPANY COMMERCIAL SERVICES, ORDER NO. ABC70862522-9, COMMITMENT DATE FEBRUARY 6, 2026 AT 5:00 P.M., WHICH PROVIDED CONFIRMATION OF OWNERSHIP AND EASEMENTS AFFECTING THE SUBJECT PROPERTY.

7. BLANKET ACCESS AND UTILITY EASEMENTS ARE HEREBY DEDICATED OVER THE ENTIRETY OF TRACTS A AND C.

8. THE SURVEY INFORMATION DEPICTED ON THIS PLAT IS BASED ON FIELD OBSERVATIONS COMPLETED ON FEBRUARY 24, 2026.

| No. | DATE | REVISION DESCRIPTION |
|-----|------|----------------------|



THIS DOCUMENT SHALL  
NOT BE RECORDED FOR  
ANY PURPOSE AND  
SHALL NOT BE USED OR  
VIEWED OR RELIED  
UPON AS A FINAL  
SURVEY DOCUMENT

I HEREBY CERTIFY I WAS IN RESPONSIBLE CHARGE OF THE SURVEY WORK USED IN THE PREPARATION OF THIS PLAT, IT IS ACCURATE TO THE BEST OF MY KNOWLEDGE, INFORMATION, AND BELIEF, IS IN ACCORDANCE WITH APPLICABLE STANDARDS OF PRACTICE, AND IS NOT A GUARANTY OR WARRANTY, EITHER EXPRESSED OR IMPLIED.

| SHEET INDEX |   |                                                   |
|-------------|---|---------------------------------------------------|
| 1           | - | LEGAL DESCRIPTION, CERTIFICATIONS, NOTES & TABLES |
| 2           | - | BOUNDARY DETAIL SHEET                             |
| 3           | - | LOT DETAIL SHEET                                  |

| LAND SUMMARY TABLE |               |               |             |
|--------------------|---------------|---------------|-------------|
| TYPE               | AREA (SF)     | AREA (AC)     | % OF TOTAL  |
| LOTS               | 54,502        | 1.2512        | 80.92%      |
| TRACTS             | 12,856        | 0.2951        | 19.08%      |
| <b>TOTAL</b>       | <b>67,358</b> | <b>1.5463</b> | <b>100%</b> |

# Kimley»»Horn

6200 SOUTH SYRACUSE WAY, # 300  
GREENWOOD VILLAGE, CO 80111

Tel. No. (303) 228-2300  
www.kimley-horn.com

|              |                 |                   |             |                    |                  |
|--------------|-----------------|-------------------|-------------|--------------------|------------------|
| <u>Scale</u> | <u>Drawn by</u> | <u>Checked by</u> | <u>Date</u> | <u>Project No.</u> | <u>Sheet No.</u> |
| N/A          | JAV             | JAF               | 2026-0831   | 196395009          | 1 OF 3           |

GRAPHIC SCALE IN FEET

80 0 40 80 160

1" = 80' @ 18X24

| LINE TABLE |             |        |
|------------|-------------|--------|
| NO.        | BEARING     | LENGTH |
| L1         | S45°00'00"E | 20.80' |
| L2         | S89°59'25"E | 16.50' |
| L3         | S00°00'03"E | 68.69' |
| L4         | S39°12'04"W | 18.50' |
| L5         | N15°00'00"W | 17.97' |
| L6         | S75°00'00"W | 81.78' |
| L7         | N72°01'27"E | 28.80' |
| L8         | S72°01'27"W | 28.80' |
| L9         | S00°00'00"E | 2.30'  |
| L10        | N22°30'00"W | 10.98' |
| L11        | N22°30'00"W | 8.58'  |

| CURVE TABLE |           |        |        |               |        |
|-------------|-----------|--------|--------|---------------|--------|
| NO.         | DELTA     | RADIUS | LENGTH | CHORD BEARING | CHORD  |
| C1          | 90°00'00" | 3.00'  | 4.71'  | N45°00'00"E   | 4.24'  |
| C2          | 17°58'33" | 15.00' | 4.71'  | N81°00'43"E   | 4.69'  |
| C3          | 17°58'33" | 35.00' | 10.98' | N81°00'43"E   | 10.94' |
| C4          | 90°00'00" | 15.00' | 23.56' | N45°00'00"E   | 21.21' |
| C5          | 34°51'02" | 35.00' | 21.29' | S72°34'29"W   | 20.96' |
| C6          | 17°58'33" | 15.00' | 4.71'  | S81°00'43"W   | 4.69'  |
| C7          | 12°26'04" | 35.00' | 7.60'  | S83°46'58"W   | 7.58'  |

| LEGEND                                                                                |                                                  |
|---------------------------------------------------------------------------------------|--------------------------------------------------|
|  | RECOVERED SECTION CORNER AS NOTED                |
|  | SET 18" LONG NO. 5 REBAR WITH 1.25" RED PLASTIC  |
|  | CAP STAMPED "PLS 38964", FLUSH WITH GRADE        |
|  | RECOVERED NO. 5 REBAR, 0.2' BELOW GRADE          |
|  | RECOVERED NO. 5 REBAR, FLUSH WITH GRADE          |
|  | RECOVERED NO. 5 REBAR WITH 1.25" YELLOW PLASTIC  |
|  | CAP STAMPED "PLS 9010 BURDICK", 0.2' BELOW GRADE |
|  | RECOVERED NO. 5 REBAR WITH 1.5" ALUMINUM         |
|  | CAP STAMPED "PLS 13664", 0.4' BELOW GRADE        |
|  | RECOVERED NO. 5 REBAR WITH 1.25" YELLOW PLASTIC  |
|  | CAP STAMPED "PLS 9010 BURDICK", FLUSH WITH GRADE |
|  | BOUNDARY LINE                                    |
|  | EASEMENT LINE AS NOTED                           |
|  | SECTION LINE                                     |
|  | LOT LINE                                         |
|  | ADJOINER LINE                                    |
|  | TIE LINE                                         |
|  | FLOOD ZONE LIMITS (APPROXIMATE)                  |
|  | BOX NUMBER                                       |



PRIOR SUBDIVISION PLAT APPEARS TO CONTAIN MULTIPLE  
PATENT AMBIGUITIES AND/OR SCRIVENER'S ERRORS. A  
SURVEYOR AFFIDAVIT OF CORRECTION DATED MAY 29,  
2026 AND RECORDED AT RECEPTION NO. 2026000031187  
ADDRESSED SOME OF THESE ISSUES. KIMLEY-HORN IS  
DEPICTING AND DIMENSIONING THE APPARENT INTENDED  
GEOMETRY AS SHOWN HEREON.

# Kimley»»Horn

|                                                               |                 |                   |                   |                                                |                     |
|---------------------------------------------------------------|-----------------|-------------------|-------------------|------------------------------------------------|---------------------|
| 6200 SOUTH SYRACUSE WAY, # 300<br>GREENWOOD VILLAGE, CO 80111 |                 |                   |                   | Tel. No. (303) 228-2300<br>www.kimley-horn.com |                     |
| Scale<br>1" = 80'                                             | Drawn by<br>JAV | Checked by<br>JAF | Date<br>2026-0831 | Project No.<br>196395009                       | Sheet No.<br>2 OF 3 |

| No. | DATE | REVISION DESCRIPTION |
|-----|------|----------------------|

CLEAR CREEK TRANSIT  
VILLAGE FINAL PLAT, FILING NO. 3  
A REPLAT OF LOT 1, BLOCK 5,  
CLEAR CREEK TRANSIT VILLAGE FINAL PLAT,  
LOCATED IN THE WEST HALF OF SECTION 8,  
TOWNSHIP 3 SOUTH, RANGE 68 WEST OF THE 6TH P.M.,  
COUNTY OF ADAMS, STATE OF COLORADO



| LINE TABLE |             |        |
|------------|-------------|--------|
| NO.        | BEARING     | LENGTH |
| L1         | S45°00'00"E | 20.80' |
| L2         | S89°59'25"E | 16.50' |
| L3         | S00°00'03"E | 68.69' |
| L4         | S39°12'04"W | 18.50' |
| L5         | N15°00'00"W | 17.97' |
| L6         | S75°00'00"W | 81.78' |
| L7         | N72°01'27"E | 28.80' |
| L8         | S72°01'27"W | 28.80' |
| L9         | S00°00'00"E | 2.30'  |
| L10        | N22°30'00"W | 10.98' |
| L11        | N22°30'00"W | 8.58'  |

| CURVE TABLE |           |        |        |               |        |
|-------------|-----------|--------|--------|---------------|--------|
| NO.         | DELTA     | RADIUS | LENGTH | CHORD BEARING | CHORD  |
| C1          | 90°00'00" | 3.00'  | 4.71'  | N45°00'00"E   | 4.24'  |
| C2          | 17°58'33" | 15.00' | 4.71'  | N81°00'43"E   | 4.69'  |
| C3          | 17°58'33" | 35.00' | 10.98' | N81°00'43"E   | 10.94' |
| C4          | 90°00'00" | 15.00' | 23.56' | N45°00'00"E   | 21.21' |
| C5          | 34°51'02" | 35.00' | 21.29' | S72°34'29"W   | 20.96' |
| C6          | 17°58'33" | 15.00' | 4.71'  | S81°00'43"W   | 4.69'  |
| C7          | 12°26'04" | 35.00' | 7.60'  | S83°46'58"W   | 7.58'  |

| LEGEND |                                 |
|--------|---------------------------------|
|        | BOUNDARY LINE                   |
|        | EASEMENT LINE AS NOTED          |
|        | SECTION LINE                    |
|        | LOT LINE                        |
|        | ADJOINER LINE                   |
|        | TIE LINE                        |
|        | FLOOD ZONE LIMITS (APPROXIMATE) |
|        | BLOCK NUMBER                    |

| No. | DATE | REVISION DESCRIPTION |
|-----|------|----------------------|
|     |      |                      |
|     |      |                      |
|     |      |                      |
|     |      |                      |
|     |      |                      |
|     |      |                      |
|     |      |                      |
|     |      |                      |
|     |      |                      |

# Kimley»Horn


6200 SOUTH SYRACUSE WAY, # 300  
GREENWOOD VILLAGE, CO 80111

Tel. No. (303) 228-2300  
www.kimley-horn.com

|                   |                 |                   |                   |                          |                     |
|-------------------|-----------------|-------------------|-------------------|--------------------------|---------------------|
| Scale<br>1" = 30' | Drawn by<br>JAV | Checked by<br>JAF | Date<br>2026-0831 | Project No.<br>196395009 | Sheet No.<br>3 OF 3 |
|-------------------|-----------------|-------------------|-------------------|--------------------------|---------------------|

LOT 1, BLOCK 5, CLEAR CREEK TRANSIT VILLAGE FINAL PLAT, COUNTY OF ADAMS, STATE OF COLORADO.

K:\NCO\_Civil\196395017\_CCTV PA3-5\PA3-CADD\PlanSheets\C-SITE\_PA5.dwg  
THIS DOCUMENT, JOSEPH NEHER WITH THE CONCEPT AND DESIGN PRESENTED HEREIN, AS AN INSTRUMENT OF SERVICE, IS INTENDED ONLY FOR THE SPECIFIC PURPOSE AND CLIENT FOR WHICH IT WAS PREPARED. REUSE OF AND IMPROPER RELIANCE ON THIS DOCUMENT WITHOUT WRITTEN AUTHORIZATION AND ADAPTATION BY KIMLEY-HORN AND ASSOCIATES, INC. SHALL BE WITHOUT LIABILITY TO KIMLEY-HORN AND ASSOCIATES, INC.



**LEGEND**

|  |                                 |
|--|---------------------------------|
|  | EXISTING ROW                    |
|  | PROPOSED LOT LINE               |
|  | EXISTING LOT LINE               |
|  | EXISTING EASEMENT               |
|  | PROPOSED EASEMENT               |
|  | PROPOSED CURB AND GUTTER        |
|  | PROPOSED INFLOW CURB AND GUTTER |
|  | PROPOSED ASPHALT PAVEMENT       |
|  | PROPOSED CONCRETE PAVEMENT      |
|  | PROPOSED CONCRETE FLATWORK      |
|  | PROPOSED ROAD SIGN              |
|  | PROPOSED LIGHT POLE             |
|  | PROPOSED TRANSFORMER            |

- NOTES:**
- ALL SIGNS AND ROADWAY MARKINGS SHALL BE IN ACCORDANCE WITH THE CURRENT EDITION OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD) AND ADAMS COUNTY DESIGN STANDARDS.
  - SIGNS SHALL BE INSTALLED 2 FEET BEHIND CURB OR SIDEWALK.
  - SEE DETAIL SHEETS FOR ADDITIONAL INFORMATION REGARDING CURBS AND PAVEMENT SECTIONS.
  - LIMITS OF STREET CUTS ARE APPROXIMATE AND ARE TO BE DETERMINED IN THE FIELD BY THE CONTRACTOR IN COORDINATION WITH THE ADAMS COUNTY ENGINEERING INSPECTOR. ALL REPAIRS SHALL CONFORM TO ADAMS COUNTY DESIGN STANDARDS.
  - ANY DAMAGED CURB, GUTTER, AND SIDEWALK EXISTING PRIOR TO CONSTRUCTION, AS WELL AS STREETS, SIDEWALKS, CURBS AND GUTTERS, DESTROYED, DAMAGED OR REMOVED DUE TO CONSTRUCTION OF THIS PROJECT, SHALL BE REPLACED OR RESTORED TO ADAMS COUNTY DESIGN STANDARDS AT THE DEVELOPER'S EXPENSE PRIOR TO THE ACCEPTANCE OF COMPLETED IMPROVEMENTS AND/OR PRIOR TO THE ISSUANCE OF THE FIRST CERTIFICATE OF OCCUPANCY.
  - REFER TO SITE AND LANDSCAPE PLANS FOR ADDITIONAL INFORMATION RELATED TO DECORATIVE PAVING, HARDSCAPES, AND OTHER SITE AMENITIES.
  - CONCRETE PANS SHALL BE DESIGNED TO BE 4' WIDE WHEN PERPENDICULAR TO DRIVE AISLES AND 2' WIDE WHEN PERPENDICULAR TO PARKING STALLS UNLESS OTHERWISE NOTED.
  - THE DRIVE AREAS WITHIN THE DEDICATED EMERGENCY ACCESS EASEMENT MUST BE CAPABLE OF SUPPORTING 80,000 POUNDS.

**PROPOSED SIGNAGE**

|                       |                         |                                       |                                |
|-----------------------|-------------------------|---------------------------------------|--------------------------------|
| <br>STOP SIGN<br>R1-1 | <br>ADA PARKING<br>R7-8 | <br>FIRE LANE<br>NO PARKING<br>R8-31A | <br>ADA EV PARKING<br>USE LAST |
|-----------------------|-------------------------|---------------------------------------|--------------------------------|

**KEYMAP**  
N.T.S.

**GRAPHIC SCALE IN FEET**  
0 10 20 40

**811**

UNPLATTED  
REC NO.  
2018000084696  
(NOT A PART)

|                                                                                                                                 |                          |
|---------------------------------------------------------------------------------------------------------------------------------|--------------------------|
| KIMLEY-HORN                                                                                                                     |                          |
| © 2026 KIMLEY-HORN AND ASSOCIATES, INC.<br>3325 SOUTH TIMBERLINE ROAD, SUITE 130<br>FORT COLLINS, COLORADO 80525 (970) 822-7911 |                          |
| DESIGNED BY: JKV<br>DRAWN BY: AVJ<br>CHECKED BY: AGR<br>DATE: 09/03/2026                                                        | PROJECT NO.<br>196395017 |
| CLEAR CREEK TRANSIT VILLAGE PA 5                                                                                                | SHEET<br>C4.0<br>5 OF 17 |
| PRELIMINARY<br>FOR REVIEW ONLY<br>NOT FOR<br>CONSTRUCTION<br>Kimley-Horn and Associates, Inc.                                   |                          |

**When Recorded, Please Return To:**

Clear Creek Investment Holdings, LLC  
900 Castleton Road, Suite 118  
Castle Rock, Colorado 80109

Doc Fee \$2,528

**SPECIAL WARRANTY DEED**

THIS DEED is made effective this October 29, 2025, from Clear Creek Development, LLC, a Delaware limited liability company ("Grantor"), to Clear Creek Investment Holdings, LLC, a Colorado limited liability company ("Grantee"), whose address is 900 Castleton Road, Suite 118, Castle Rock, Colorado 80109.

WITNESS, that Grantor, for and in consideration of the sum of Ten Dollars (\$10.00) and other good and valuable consideration, the receipt and sufficiency of which is hereby acknowledged, has granted, bargained, sold and conveyed, and by these presents does grant, bargain, sell, convey and confirm unto Grantee, its successors and assigns forever, the following real property located in Adams County, Colorado:

**SEE ATTACHED EXHIBIT A**

TOGETHER with all reversions, remainders, easements, rights-of-way, appurtenances, improvements, agreements, licenses, tenements and hereditaments appertaining to or otherwise benefiting or used in connection with such property, together with all of Grantor's right, title and interest in and to any strips of land, streets and alleys abutting or adjoining such property, water rights, mineral rights, water and sewer taps (including any water service agreements) or sanitary and storm sewer capacity appurtenant or appertaining to or otherwise benefiting or used in connection with such property; and all the estate, right, title, interest, claim and demand whatsoever of Grantor, either in law or equity, of, in and to the above-bargained premises with the hereditaments and appurtenances (collectively, "Property");

TO HAVE AND TO HOLD the Property unto Grantee, its successors and assigns forever. Grantor, for itself and its successors and assigns, does covenant and agree that it shall and will warrant and forever defend the Property in the quiet and peaceable possession of Grantee, its successors and assigns, against all and every person or persons claiming the whole or any part thereof, by, through or under Grantor, subject to those statutory exceptions, and the Permitted Exceptions identified on Exhibit "B", attached hereto and make a part hereof.



70858445

**[SIGNATURE PAGE FOLLOWS]**

IN WITNESS WHEREOF, Grantor has executed this Deed as of the date first above written.

**GRANTOR:**

Clear Creek Development, LLC,  
a Delaware limited liability company

By: Thistle Creek QOF I, L.P.,  
a Delaware limited partnership, its managing member

By: Thistle Creek QOF I GP, LLC,  
a Utah limited liability company, its general partner


By: Michael Christensen  
Name: Michael Christensen  
Title: Manager

STATE OF UTAH )  
COUNTY OF UTAH ) ss:

The foregoing instrument was acknowledged before me as of the 23 day of June 2025, by Michael Christensen as Manager of Thistle Creek QOF I GP, LLC, a Utah limited liability company, as general partner of Thistle Creek QOF I, L.P., a Delaware limited partnership, as managing member of Clear Creek Development, LLC, a Delaware limited liability company.

WITNESS my hand and official seal.

My Commission Expires: 5/9/2028 Jackson Randall Notary Public



*Signature Page to Special Warranty Deed*

**EXHIBIT A**

**LEGAL DESCRIPTION**

Lot 1, Block 1;  
Lot 1, Block 2;  
Lot 1, Block 3;  
Lot 1, Block 4;  
Lot 1, Block 5;  
Lots 1 through 64, inclusive, Block 6;  
Lots 1, through 24, inclusive, Block 7;  
Lots 1 through 43, inclusive, Block 8;  
Lots 1 through 9, inclusive, Block 9;  
Tracts A through M;

Clear Creek Transit Village, County of Adams, State of Colorado.

**EXHIBIT B**

**PERMITTED EXCEPTIONS**

1. TAXES FOR THE YEAR 2025 AND SUBSEQUENT YEARS, A LIEN NOT YET DUE AND PAYABLE.
2. (a) UNPATENTED MINING CLAIMS; (b) RESERVATION OR EXCEPTIONS IN PATENTS OR IN ACTS AUTHORIZING THE ISSUANCE THEREOF; (c) WATER RIGHTS, CLAIMS OR TITLE TO WATER.
3. EXISTING LEASES AND TENANCIES, IF ANY.
4. EASEMENTS FOR CONSTRUCTION AND MAINTENANCE OF SEWER LINES AND INCIDENTAL PURPOSES AS GRANTED TO METROPOLITAN DENVER SEWAGE DISPOSAL DISTRICT NO. 1 IN INSTRUMENT RECORDED SEPTEMBER 25, 1963 IN BOOK 1099 AT PAGE 299 AND JULY 18, 1983 IN BOOK 2768 AT PAGE 890.  
  
CORRECTED EASEMENT FOR CONSTRUCTION AND MAINTENANCE OF SEWER LINES RECORDED AUGUST 7, 1984 IN BOOK 2902 AT PAGE 735.
5. TERMS, CONDITIONS AND PROVISIONS OF AGREEMENT RECORDED APRIL 27, 1970 IN BOOK 1593 AT PAGE 320.
6. EASEMENTS, CONDITIONS, COVENANTS, RESTRICTIONS, RESERVATIONS AND NOTES ON THE PLAT OF BRANNAN'S SUBDIVISION FILING NO. 1 RECORDED OCTOBER 31, 1973 UNDER RECEPTION NO. 20815.
7. TERMS, CONDITIONS, PROVISIONS, BURDENS, OBLIGATIONS AND EASEMENTS AS SET FORTH AND GRANTED IN EASEMENT GRANT RECORDED SEPTEMBER 19, 1979 IN BOOK 2387 AT PAGE 852.
8. TERMS, CONDITIONS, PROVISIONS, BURDENS, OBLIGATIONS AND EASEMENTS AS SET FORTH AND GRANTED IN EASEMENT AGREEMENT RECORDED JULY 20, 1987 IN BOOK 3344 AT PAGE 663.
9. ANY TAX, LIEN, FEE, OR ASSESSMENT BY REASON OF INCLUSION OF SUBJECT PROPERTY IN THE HYLAND HILLS PARK AND RECREATION DISTRICT, AS EVIDENCED BY INSTRUMENT RECORDED SEPTEMBER 19, 1990, IN BOOK 3712 AT PAGE 402.
10. EFFECT OF RESOLUTION AUTHORIZING EXEMPTION FROM THE ADAMS COUNTY SUBDIVISION REGULATIONS RECORDED APRIL 6, 1992 IN BOOK 3888 AT PAGE 126.
11. TERMS, CONDITIONS, PROVISIONS, BURDENS, OBLIGATIONS AND EASEMENTS AS SET FORTH AND GRANTED IN DRAINAGE EASEMENT RECORDED APRIL 24, 1995 IN BOOK 4500 AT PAGE 531.

12. TERMS, CONDITIONS AND PROVISIONS OF A DEVELOPMENT AGREEMENT DISCLOSED BY RESOLUTION RECORDED MAY 18, 1992 IN BOOK 3905 AT PAGE 674.
13. EASEMENTS, CONDITIONS, COVENANTS, RESTRICTIONS, RESERVATIONS AND NOTES ON THE PLAT OF BRANNAN'S SUBDIVISION FILING NO. 2 RECORDED MAY 12, 1994 UNDER RECEPTION NO. 1247454.

AFFIDAVIT OF CORRECTION RECORDED JANUARY 19, 1995 IN BOOK 4455 AT PAGE 542.

14. TERMS, CONDITIONS, PROVISIONS, BURDENS AND OBLIGATIONS AS SET FORTH IN ZONING HEARING DECISION RECORDED AUGUST 03, 1995 IN BOOK 4559 AT PAGE 978.
15. TERMS, CONDITIONS, PROVISIONS, BURDENS, OBLIGATIONS AND EASEMENTS AS SET FORTH AND GRANTED IN LANDSCAPE BERM AND FENCE EASEMENT RECORDED MARCH 13, 1996 IN BOOK 4701 AT PAGE 983.
16. TERMS, CONDITIONS AND PROVISIONS OF ZONING HEARING DECISIONS RECORDED SEPTEMBER 20, 2010 UNDER RECEPTION NO. 201000062586 AND 201000062587.
17. ANY TAX, LIEN, FEE, OR ASSESSMENT BY REASON OF INCLUSION OF SUBJECT PROPERTY IN THE CLEAR CREEK TRANSIT METROPOLITAN DISTRICT NO. 1, AS EVIDENCED BY INSTRUMENT RECORDED NOVEMBER 24, 2010, UNDER RECEPTION NO. 2010000081925. ORDER FOR EXCLUSION OF REAL PROPERTY IN CONNECTION THEREWITH RECORDED MARCH 5, 2021 UNDER RECEPTION NO. 2021000027467.
18. ANY TAX, LIEN, FEE, OR ASSESSMENT BY REASON OF INCLUSION OF SUBJECT PROPERTY IN THE CLEAR CREEK TRANSIT METROPOLITAN DISTRICT NO. 2, AS EVIDENCED BY INSTRUMENT RECORDED NOVEMBER 24, 2010, UNDER RECEPTION NO. 2010000081926. ORDER FOR EXCLUSION OF REAL PROPERTY IN CONNECTION THEREWITH RECORDED MARCH 5, 2021 UNDER RECEPTION NO. 2021000027466.
19. TERMS, CONDITIONS, PROVISIONS, BURDENS AND OBLIGATIONS AS SET FORTH IN RESOLUTION ADOPTING ZONING HEARING DECISION RECORDED NOVEMBER 21, 2012 UNDER RECEPTION NO. 2012000088446.
20. ALL ITEMS SHOWN ON CLEAR CREEK TRANSIT VILLAGE PLANNED UNIT DEVELOPMENT- PRELIMINARY DEVELOPMENT PLAN, RECORDED JANUARY 22, 2013 UNDER RECEPTION NO. 2013000006476.

RESOLUTION 2015-531 APPROVING PRELIMINARY DEVELOPMENT PLAN RECORDED DECEMBER 11, 2015 UNDER RECEPTION NO. 2015000103730.

21. TERMS, CONDITIONS, PROVISIONS, BURDENS AND OBLIGATIONS AS SET FORTH IN DECLARATION OF COVENANTS IMPOSING AND IMPLEMENTING THE CLEAR CREEK PUBLIC IMPROVEMENT FEE RECORDED MARCH 16, 2021 UNDER RECEPTION NO. 2021000031185.
22. TERMS, CONDITIONS, PROVISIONS, BURDENS, OBLIGATIONS AND EASEMENTS AS SET FORTH AND GRANTED IN TEMPORARY CONSTRUCTION EASEMENT RECORDED MAY 28, 2021 UNDER RECEPTION NO. 2021000065568.
23. TERMS, CONDITIONS, PROVISIONS, BURDENS AND OBLIGATIONS AS SET FORTH IN NOTICE REGARDING AGREEMENTS FOR SALE AND PURCHASE OF REAL ESTATE RECORDED SEPTEMBER 21, 2021 UNDER RECEPTION NO. 2021000111264.
24. ALL ITEMS SHOWN ON CLEAR CREEK TRANSIT VILLAGE PLANNED UNIT DEVELOPMENT - PRELIMINARY DEVELOPMENT PLAN RECORDED JANUARY 13, 2023 UNDER RECEPTION NO. 2023000002825, AMENDMENT NO. 2 RECORDED APRIL 30, 2024 UNDER RECEPTION NO. 2024000022444.  
  
RESOLUTION 2022-608, APPROVING APPLICATION IN CASE# PRC2022-00002 CLEAR CREEK TRANSIT VILLAGE PRELIMINARY PLAT RECORDED NOVEMBER 29, 2022 UNDER RECEPTION NO. 2022000093846; RESOLUTION APPROVING APPLICATION IN CASE #PUD2023-00020 CLEAR CREEK TRANSIT VILLAGE, PRELIMINARY DEVELOPMENT PLAN, AMENDMENT 2 RECORDED FEBRUARY 8, 2024 UNDER RECEPTION NO. 2024000006547.
25. TERMS, CONDITIONS, PROVISIONS, BURDENS AND OBLIGATIONS AS SET FORTH IN BOARD OF COUNTY COMMISSIONERS FOR ADAMS COUNTY, COLORADO RESOLUTION 2024-477 APPROVING APPLICATION IN CASE #PRC2023-00011 CLEAR CREEK TRANSIT VILLAGE FINAL PLAT AND FINAL DEVELOPMENT PLAN RECORDED SEPTEMBER 20, 2024 UNDER RECEPTION NO. 2024000051817.
26. TERMS, CONDITIONS, PROVISIONS, BURDENS AND OBLIGATIONS AS SET FORTH IN BOARD OF COUNTY COMMISSIONERS FOR ADAMS COUNTY, STATE OF COLORADO RESOLUTION 2024-476 APPROVING CASE #SIA2023-00012 SUBDIVISION IMPROVEMENTS AGREEMENT FOR CLEAR CREEK TRANSIT VILLAGE RECORDED SEPTEMBER 20, 2024 UNDER RECEPTION NO. 2024000051822.
27. TERMS, CONDITIONS, PROVISIONS, BURDENS AND OBLIGATIONS AS SET FORTH IN CLEAR CREEK TRANSIT VILLAGE PLANNED UNIT DEVELOPMENT RECORDED FEBRUARY 27, 2025 UNDER RECEPTION NO. 2025000010536.
28. EASEMENTS, CONDITIONS, COVENANTS, RESTRICTIONS, RESERVATIONS AND NOTES ON THE PLAT OF CLEAR CREEK TRANSIT VILLAGE RECORDED MARCH 6, 2025 UNDER RECEPTION NO. 2025000012280 AND RE-RECORDED MARCH 20, 2025 UNDER RECEPTION NO. 2025000015037.

SURVEYOR'S AFFIDAVIT OF CORRECTION RECORDED JULY 24, 2025 UNDER  
RECEPTION NO. 2025000042632.

29. ANY FACTS, RIGHTS, INTERESTS OR CLAIMS WHICH MAY EXIST OR ARISE BY  
REASON OF THE FOLLOWING FACTS SHOWN ON A.L.T.A./N.S.P.S. LAND TITLE  
SURVEY CERTIFIED FEBRUARY 20, 2020 PREPARED BY POWER SURVEYING  
COMPANY, INC., JOB #501-19-260(B):

A. FENCE LINES ARE NOT COINCIDENT WITH PROPERTY LINES.

B. OVERHEAD UTILITY LINES CROSSING SUBJECT PROPERTY WITHOUT THE  
BENEFIT OF A RECORDED EASEMENT.



Bryan Byler  
Clear Creek Investment Holdings, LLC  
900 Castleton Road, Suite 118  
Castle Rock, CO 80109

January 5, 2026

RE: Water and Sanitary Sewer Service, 6001 Federal Blvd., Denver, CO 80221

Will-Serve Letter

Mr. Bryan Byler,

Please be advised that Crestview Water and Sanitation District (Crestview) is willing to provide treated water and sanitary sewer service to a possible development on parcel no. 0182508211004 in Adams County, Colorado that is wholly within the Crestview Water and Sanitation District boundaries.

Prior to creating a layout and filing a plat for any future development of this parcel, the petitioning owner/developer (developer) MUST have a pre-design meeting with Crestview, as the developer must allow for the installation of adequate water mains in strict accordance with Denver Water Engineering Standards and Crestview Rules and Regulations and engineering requirements. Crestview provides drinking water to its customers by means of a wholesale water purchasing contract with Denver Water. As part of the Contract, Denver Water requires Crestview and developers within Crestview's service area to adhere to Denver Water's Engineering Standards.

Sanitary sewer mains must also be designed in accordance with Crestview Rules and Regulations and engineering requirements.

For any future development of this parcel, the developer will be responsible for all costs related to the installation of required water and sewer mains and sewer monitoring manholes and is responsible for all utility modeling, engineering studies and plan development/review costs. Crestview utilizes a consulting engineer to review plans provided to Crestview by developers. Any costs invoiced to Crestview by its consulting engineer pertaining to this development will be assessed to the developer through a Funds Deposit Agreement between the developer and Crestview.

All water and sewer mains and appurtenances for the new development shall be installed at the developer's expense and deeded free and clear to Crestview prior to the issuance of any water or sewer taps.


Any required off-site improvements to Crestview's water distribution system and/or sanitary sewer collection system created by additional system demands from this proposed development will be the responsibility of the owner/developer both financially and physically and must be constructed prior to any on-site water and/or sanitary sewer improvements.

Please read and comply with Crestview's Backflow & Cross Connection Control Rules and Regulations at [CrestviewWaterColorado.gov](http://CrestviewWaterColorado.gov) under About the District, Backflow Prevention Regulations and Procedures in Appendix G relating to your project.

If your project is a residential development that is required to have 13D fire suppression in each unit, each unit is required to have a dedicated Crestview owned and read water meter and a double check valve backflow prevention assembly installed and tested prior to allowing occupation of the unit/s.


All plan sets that are required to be provided to Adams County and to Adams County Fire Protection District for review must also be provided to Crestview for review.

Crestview requires a signature of acceptance of this Will-Serve letter by the developer prior to scheduling a pre-design meeting with Crestview. Please provide a copy of this signed Will Serve letter when scheduling a pre-design meeting to Courtney Salazar, Developer/Project Coordinator, at [csalazar@CrestviewWaterColorado.gov](mailto:csalazar@CrestviewWaterColorado.gov) and to Crestview's engineer, Clarice O'Hanlon, at [cohanlon@CrestviewWaterColorado.gov](mailto:cohanlon@CrestviewWaterColorado.gov).

|                                                                                                                                                         |                     |
|---------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------|
| <div>DocuSigned by:<br/><br/><small>A87C0E2F07144A3...</small></div> | <div>2/3/2026</div> |
| Signature of developer representative                                                                                                                   | Date                |

If you have any questions or require additional information, please contact our office.

Sincerely,



Mitchell T. Terry  
District Manager  
Crestview Water & Sanitation District



## WILL SERVE LETTER

March 9, 2021

Thistle Creek QOF I, L.P.  
Michael Christensen  
14034 South 145th East, Suite 301  
Draper, UT 84020

Re: 6100 Federal Boulevard, Denver CO 80221

Dear Mr. Christensen,

This letter is to confirm that Xcel Energy is your utility provider for natural gas and electrical service. In accordance with our tariffs, on file with and approved by the Colorado Public Utilities Commission, gas and electric facilities can be made available to serve the project at 6100 Federal Boulevard, Denver CO 80221.

Your utility service(s) will be provided after the following steps are completed:

- ***Application submitted to Public Service's "Builders Call Line (BCL)"*** – once your application is accepted you will be assigned a design department representative who will be your primary point of contact
- ***Utility design is completed*** – you must provide your design representative with the site plan, the one line diagrams, and panel schedules for electric and gas loads if applicable
- ***All documents provided by design representative are signed and returned***
- ***Payment is received***
- ***Required easements are granted*** - you must sign and return applicable easement documents to your Right-of-Way agent
- ***Site is ready for utility construction***

A scheduled in-service date will be provided once these requirements have been met.

It is important to keep in mind that the terms and conditions of utility service, per our tariffs, require that you provide adequate space and an easement on your property for all gas and electric facilities required to serve your project, including but not limited to gas and electrical lines and meters, transformers, and pedestals. General guidelines for these requirements can be found at [Site Requirements. https://www.xcelenergy.com/staticfiles/xcel-responsive/Admin/Managed Documents & PDFs/Xcel-Energy-Standard-For-Electric-Installation-and-Use.pdf](https://www.xcelenergy.com/staticfiles/xcel-responsive/Admin/Managed%20Documents%20and%20PDFs/Xcel-Energy-Standard-For-Electric-Installation-and-Use.pdf) Easement requirements can be found at [Utility Design and Layout](#).

Xcel Energy looks forward to working with you on your project and if I can be of further assistance, please contact me at the phone number or email listed below.


Sincerely,

*Tawni Herren*

Tawni Herren  
Xcel Energy | Responsible By Nature  
Design Contractor for Xcel Energy  
555 Zang Street Suite 250  
Lakewood, CO 80228

Pike Engineering

Mailing address: Pike Engineering  
555 Zang, Suite 250  
Lakewood, CO 80228



Alexander L. Villagran  
Treasurer and Public Trustee  
Treasurer's Office  
4430 S. Adams County Pkwy.  
1st Floor, Suite W1000  
Brighton, CO 80601-8217  
adcogov.org

Adams County Treasurer  
Receipt of Tax Payment

~~R0103135~~ - 81,751.51  
~~R0204716~~ - 368,600.82  
~~R0103141~~ - 7,269.95

Date: 11-04-25

Account #: \_\_\_\_\_

Payor:

Land title Guarantee Company

Tax Year: 2024

Method of Payment: check Amount Paid: 457,622.28

Received By: JESUS

Thank you for your payment!  
ALL PAYMENTS ARE SUBJECT TO FINAL COLLECTION.

Treasurer Division  
PHONE 720.523.6160  
FAX 720.523.6171

Public Trustee Division  
PHONE 720.523.6250  
FAX 720.523.6458  
EMAIL [eforeclosures@adcogov.org](mailto:eforeclosures@adcogov.org)



September 2, 2026

Greg Barnes  
Adams County Engineering  
4430 S. Adams County Pkwy  
Brighton, CO 80601

**RE:     *Clear Creek Transit Village PA 5  
Drainage Compliance Letter***

Dear Greg Barnes:

The purpose of this drainage letter is to demonstrate that the proposed drainage design for Clear Creek Transit Village PA 5 (the "Project") conforms to the drainage patterns set forth by the master drainage report that was written with the overall Clear Creek Transit Village Project (the "Master Development"). The Master development "Clear Creek Transit Village Level 3 Storm Drainage Report", was prepared by Kimley-Horn in August of 2026 ("Master Drainage Report"). Excerpts from the Master Drainage Report are attached to this letter as Appendix A.

The Project is located within the West Half of Section 8, Township 3 South, Range 68 West of the Sixth Principal Meridian, County of Adams, State of Colorado. Additionally, the Project is located in Lot 1, Block 5, of the Clear Creek Transit Village Final Plat recorded March 6, 2025, Reception No. 2025000012280. The Site includes two site access points along Federal Boulevard, a private roadway network, single-family townhomes to the west and a future mixed-use development to the east. A water quality pond is located along the south side of the site. Rain gardens are located along the west and east side of the site. The proposed project consists of townhomes, multi-family residences, commercial retail, and associated infrastructure including site grading, utility service installation, parking, sidewalks, and landscaping.

#### **Existing Conditions – Master Plan Information**

The project area is within Basin F of the Master Development as shown in the Master Drainage Map, which is attached to this letter as Appendix A. Basin F has an assumed imperviousness of 90%. Per the Master Drainage Report, flows from basin F1 will sheet flow and enter the existing storm system in Grove Street or flow directly into the water quality pond. Basin F2 sheet flows to the adjacent street curb and gutter and enter the existing storm inlet at design point C1. Existing Basin F3 will sheet flow to the adjacent street curb and gutter and enter the existing storm inlet at design point I. Then all existing basins will flow through existing storm infrastructure to the water quality pond located along the south side of the site before ultimately outfalling to Clear Creek.

Additionally, according to the Master Drainage Report, additional LID infrastructure will be added within Basin F, see Appendix A for the Master Drainage Report LID exhibit.

### **Proposed Conditions**

The Project has been divided into three sub-basins: Sub-Basins C1, I1, and G1 which flow into the existing water quality pond via sheet flow, pans, swales, and existing storm infrastructure. See Appendix D for the Proposed Drainage Map.

#### Sub-Basin C1

Sub-Basin C1 consists of proposed building roof, drives, parking, sidewalks and landscaping. Flows from Sub-Basin C1 sheet flow west to adjacent street curb and gutter (design point C1) and then to an existing inlet at design point C. The existing storm inlet outfalls into the water quality pond via existing forebay A along the south side of the Site, ultimately discharging to Clear Creek.

#### Sub-Basin I1

Sub-Basin I1 consists of proposed sidewalks and landscaping. Flows from Sub-Basin I1 sheet flow east to adjacent street curb and gutter (design point I1) and then to an existing inlet at design point I. The existing storm inlet outfalls into the water quality pond via existing forebay B along the south side of the Site, ultimately discharging to Clear Creek.

#### Sub-Basin G1

Sub-Basin G1 consists of proposed building roof, sidewalks, and landscaping. Flows from Sub-Basin G1 sheet flow to the water quality pond along the south side of the Site, ultimately discharging to Clear Creek.

### **Proposed Drainage Facilities**

Site grading is designed to convey stormwater to proposed and existing inlets and storm drain lines via sheet flow, concrete pans and curb and gutter. The existing storm sewer system will convey minor and major flows to the existing water quality pond on the south side of the site. Street conveyance will be minimized wherever possible and will be designed to maintain access for emergency vehicles.

Additional LID infrastructure will be provided within Basin F via LID planters, see Appendix C for the proposed LID exhibit and planter sizing.

### **Drainage Design Criteria**

The Project was designed to conform to the requirements outlined in Adams County Storm Drainage Design and Stormwater Quality Control Regulations and the latest Mile High Flood District (MHFD) Urban Storm Drainage Criteria Manual (USDCM). As previously discussed, the Project maintains the Master Drainage Report drainage patterns with runoff from each basin directed to the water quality pond. Per the Master Drainage Plan, no detention is provided onsite, but the site will drain to Clear Creek and ultimately the South Platte River. However, additional LID infrastructure is required per the Master Drainage Report (see Appendix A). Proposed LID planters will be added within Basin F, see Appendix C for the proposed LID exhibit.

With the proposed improvements, the Site is proposing less impervious area than anticipated in the Master Drainage Report.

The Rational Method was used for all subbasins since the areas are less than 5 acres. Per Mile High Flood District and Adams County criteria, the storm frequencies used to analyze the drainage design were the 5-year and the 100-year storms. One-hour point rainfall depths used for the rational calculations were obtained from Table 9-3 in section 9-01-04-04 of the Adams County Manual. Rainfall depths for the 5-year and 100-year, are 1.42 and 2.71 inches, respectively. Rational method calculations are attached to this letter in Appendix B.

A Four Step Process was implemented for the drainage design and protection of receiving water bodies:

*Step 1 - Runoff Reduction Practices*

Runoff is routed through vegetated buffers via sheet flow wherever reasonably possible to increase time of concentration and promote infiltration. By Minimizing Directly Connected Impervious Areas (MDCIA), peak runoff volumes and pollutant loads are reduced.

*Step 2 – Implement Best Management Practices (BMPs) to treat the WQCV*

Rain gardens are proposed that will provide treatment for the WQCV with slow release and partial infiltration.

*Step 3 – Stabilizing Streams*

Stream stabilization was considered but not implemented due to open channels being minimized for site accessibility.

*Step 4 – Implementing Site Specific and Other Source Control BMPs*

Site specific controls that will be implemented include locating material storage away from storm drainage facilities and installing construction fencing around the existing regional pond to protect areas that should not be compacted or disturbed.

The trash enclosures and the dog park were located further upstream from the drainage facilities to minimize potential impacts. This additional distance allows the highly concentrated and polluted runoff an opportunity to be cleaned prior to reaching drainage conveyance systems.

Pea gravel was chosen within the dog park area promotes infiltration. Ample waste disposal stations will also be provided within the dog area to encourage dog owners to clean up after their pets and minimizing waste.

## **Conclusion**

The Master Drainage Report shows the project area as Basin F with an assumed imperviousness of 90%. The proposed project will have an impervious value of 79%, which is less than what was assumed. As such, the proposed project conforms with the original assumptions and conclusions of the Master Drainage plan.

Please contact us with any questions or concerns.

Thank You,

**KIMLEY-HORN AND ASSOCIATES, INC.**

---

Bryce Willaby, P.E.

## **Appendices**

**A – Excerpts from Master Drainage Report**

**B – Rational Method Calculations**

**C – LID**

**D – Proposed Drainage Map**

***Compliance Statement***

"I hereby attest that this report for the final drainage design for the Clear Creek Transit Village PA 5 project was prepared by me or under my direct supervision, in accordance with the provisions of the Adams County Storm Drainage Design and Stormwater Quality Control Regulations and the latest Mile High Flood District (MHFD) Urban Storm Drainage Criteria Manual (USDCM). I understand that Adams County does not and will not assume liability for drainage facilities designed by others."

---

By: Bryce Willaby, P.E.  
Registered Professional Engineer  
State of Colorado No. 63721



## **APPENDIX A – Excerpts From Master Drainage Report**



## LEVEL 3 STORM DRAINAGE REPORT

# Clear Creek Transit Village Adams County

Prepared for:

**Clear Creek Development, LLC.**  
**10808 S. River Front Parkway, Suite 378**  
**South Jordan, UT 84095**  
**(801) 809-9294**

Prepared by:

**Bryce Willaby, PE**  
**Kimley-Horn and Associates, Inc.**  
**3325 South Timberline Road, Suite 130**  
**Fort Collins, CO 80525**  
**(970) 822-7911**

Project #: 196395009

Prepared: May 15<sup>th</sup>, 2024

Revised: August 18<sup>th</sup>, 2026

**Kimley»Horn**

## **PROPOSED SUB-BASIN DESCRIPTION**

For the purposes of this Proposed Conditions Analysis, the Site was split into thirty-five (35) on-site subbasins and two (2) off-site basins as shown in the Proposed Drainage Map in Appendix A. Individual basin details such as runoff coefficient calculations, imperviousness percentages, and 5-year and 100-year peak flows are provided in Appendix C. The LID Exhibit, rain garden locations and Nyloplast sizing hydraulic calculations can be found in Appendix D.

### **Sub-Basin A1**

Sub-basin A1 is comprised of roof area and landscaping and is located in the northwest corner. Flows on the surface will overland flow to rain garden 8 and rain garden 9. Then flows will enter the proposed storm sewer (design point A1) before ultimately discharging to the proposed water quality pond located at the south side of the Site (basin G).

### **Sub-Basin A2**

Sub-basin A2 is comprised of roof area of townhomes and landscaping along the west property boundary. Stormwater will overland flow to rain gardens 1-5. Then flows will enter the proposed storm sewer (design point A2) before ultimately discharging to the proposed water quality pond located at the south side of the Site (basin G).

### **Sub-Basin A3**

Sub-basin A3 is comprised of roof area and landscaping and is located in the southwest corner of the Site. Stormwater will overland flow to rain gardens 6 and 7. Then flows will enter the proposed storm sewer (design point A3) before ultimately discharging to the proposed water quality pond located at the south side of the Site (basin G).

### **Sub-Basin B1**

Sub-basin B1 is comprised of roof area, landscaping, sidewalks, and alleys. Stormwater will discharge into adjacent landscape areas or paved alleys where it will be conveyed via a concrete pan to Grove Street. Flow then will be conveyed south, via curb and gutter, to a proposed inlet along the west side of Grove Street, design point B1. Then flows will be conveyed through proposed storm sewer before ultimately discharging to the proposed water quality pond located at the south side of the Site (basin G).

### **Sub-Basin B2**

Sub-basin B2 is comprised of roof area, landscaping, sidewalks, and alleys. Runoff will be conveyed via overland flow to Mountain Vista Lane, W 59<sup>th</sup> Place or Private Drive A. Flow along the drives will be conveyed via curb and gutter to an inlet along the west side of Grove Street, design point B2. Then flows will be conveyed through proposed storm sewer before ultimately discharging to the proposed water quality pond located at the south side of the Site (basin G).

### **Sub-Basin B3**

Sub-basin B3 is comprised of roof area, landscaping, and paved drives. Stormwater runoff will be conveyed via overland flow to curb and gutter along Mountain Vista Lane and W 59<sup>th</sup> Court. Flows will be conveyed east to a proposed inlet (design point B2) along the west side of Grove Street, design point B3. Then flows will be conveyed through proposed storm sewer before ultimately discharging to the proposed water quality pond located at the south side of the Site (basin G).

**Sub-Basin C1**

Sub-basin C1 is comprised of roof area, landscaping, sidewalks, and paved drives. Stormwater will be conveyed via overland flow to W 60<sup>th</sup> Court and travel along curb and gutter south to a proposed inlet along the east side of Grove Street, design point C1. Then flows will be conveyed through proposed storm sewer before ultimately discharging to the proposed water quality pond located at the south side of the Site (basin G). Reference Appendix D for the street capacity calculations for Grove Street.

**Sub-Basin C2**

Sub-basin C2 is comprised of roof area, landscaping, sidewalks, and paved drives. Runoff will be conveyed via overland flow to W 59<sup>th</sup> Court or a paved alley. Flow along the drives will be conveyed via curb and gutter to an inlet along the east side of Grove Street, design point C2. Then flows will be conveyed through proposed storm sewer before ultimately discharging to the proposed water quality pond located at the south side of the Site (basin G).

**Sub-Basin D1**

Sub-basin D1 is a future mixed-use development with an assumed imperviousness of 90%. It is proposed that this area will overland flow north where runoff will be channelized and enter the proposed storm sewer at design point D1. Then flows will be conveyed through the storm sewer network before ultimately discharging to the proposed water quality pond located at the south side of the Site (basin G).

**Sub-Basin D2**

Sub-basin D2 is a future mixed-use development with an assumed imperviousness of 90%. Stormwater will overland flow to design point D2. Runoff will then travel via curb and gutter south along Grove Street to a proposed inlet along the east side of Grove Street, design point C1. Then flows will be conveyed through proposed storm sewer before ultimately discharging to the proposed water quality pond located at the south side of the Site (basin G).

**Sub-Basin D3**

Sub-basin D3 is a future mixed-use development with an assumed imperviousness of 90%. Stormwater will overland flow to design point D3. Runoff will then travel via curb and gutter along adjacent drives to a proposed inlet along the north side of W 60<sup>th</sup> Avenue, design point H. Then flows will be conveyed through proposed storm sewer before ultimately discharging to the proposed water quality pond located at the south side of the Site (basin G).

**Sub-Basin E1**

Sub-basin E1 is a future park area with an assumed imperviousness of 10%. Flows will be conveyed via overland flow to curb and gutter along the adjacent streets, design point E1. Runoff will be conveyed south to a proposed inlet along the east side of Grove Street, design point C1. Then flows will be conveyed through proposed storm sewer before ultimately discharging to the proposed water quality pond located at the south side of the Site (basin G).

**Sub-Basin E2**

Sub-basin E2 is a future park area with an assumed imperviousness of 10%. Flows will be conveyed via overland flow to curb and gutter along the adjacent streets, design point E2. Runoff will be conveyed south to a proposed inlet along the south side of W 60<sup>th</sup> Avenue, design point I. Then flows

will be conveyed through proposed storm sewer before ultimately discharging to the proposed water quality pond located at the south side of the Site (basin G).

**Sub-Basin F1**

Sub-basin F1 is a future mixed-use development with an assumed imperviousness of 90%. It is proposed that future storm sewer from this Site will tie into the proposed storm sewer in Grove Street or directly into the proposed water quality pond, design point F1. Runoff from this basin will ultimately discharge to the proposed water quality pond located at the south side of the Site (basin G).

**Sub-Basin F2**

Sub-basin F2 is a future mixed-use development with an assumed imperviousness of 90%. Stormwater will overland flow to design point F2. Runoff will then travel via curb and gutter south along Grove Street to a proposed inlet along the east side of Grove Street, design point C1. Then flows will be conveyed through proposed storm sewer before ultimately discharging to the proposed water quality pond located at the south side of the Site (basin G).

**Sub-Basin F3**

Sub-basin F3 is a future mixed-use development with an assumed imperviousness of 90%. Stormwater will overland flow to design point F3. Runoff will then travel via curb and gutter along adjacent drives to a proposed inlet along the south side of W 60<sup>th</sup> Avenue, design point I. Then flows will be conveyed through proposed storm sewer before ultimately discharging to the proposed water quality pond located at the south side of the Site (basin G).

**Sub-Basin G**

Sub-basin G is comprised of landscaping and the proposed water quality pond. Runoff in this area will be conveyed via overland flow directly to the water quality pond, design point G. Within the pond, runoff will travel via a concrete pan to a proposed outlet structure and pipe, ultimately outfalling into Clear Creek.

**Sub-Basin H**

Sub-basin H is comprised of sidewalks, tree lawns and paved drives. Stormwater will overland flow to the adjacent drives where it will be conveyed via curb and gutter to a proposed inlet along the north side of W 60<sup>th</sup> Avenue, design point H. Then flows will be conveyed through proposed storm sewer before ultimately discharging to the proposed water quality pond located at the south side of the Site (basin G).

**Sub-Basin I**

Sub-basin I is comprised of sidewalks, tree lawns and paved drives. Stormwater will overland flow to the adjacent drives where it will be conveyed via curb and gutter to a proposed inlet along the south side of W 60<sup>th</sup> Avenue, design point I. Then flows will be conveyed through proposed storm sewer before ultimately discharging to the proposed water quality pond located at the south side of the Site (basin G).

**Sub-Basin J1**

Sub-basin J1 is comprised of sidewalks, tree lawns and paved drives. Runoff will be conveyed via overland flow and curb and gutter east to the Federal Boulevard right-of-way, design point J1. Runoff will be conveyed to a proposed rain garden along the west side of Federal Boulevard via a curb cut and concrete channel. Flows will ultimately outfall into the existing public storm sewer along Federal Boulevard. Reference Appendix D for concrete channel sizing calculations.

**Sub-Basin J2**

Sub-basin J2 is a future mixed-use development with an assumed imperviousness of 90%. It is proposed that the runoff for this sub-basin will outfall via overland flow in the proposed rain garden located along the east side of the Site, design point J2. Runoff will ultimately outfall into the existing public storm sewer along Federal Boulevard.

**Sub-Basin K1**

Sub-basin K1 is a future mixed-use development with an assumed imperviousness of 90%. It is proposed that this sub-basin will tie directly into the proposed storm sewer along W 60<sup>th</sup> Avenue or overland flow to future LID improvement, design point K1. Then flows will be conveyed through proposed storm sewer before ultimately discharging to the proposed water quality pond located at the south side of the Site (basin G).

**Sub-Basin K2**

Sub-basin K2 is a future mixed-use development with an assumed imperviousness of 90%. Stormwater will overland flow to design point K2 and into future LID improvement.

**Sub-Basin K3**

Sub-basin K3 is a future mixed-use development with an assumed imperviousness of 90%. Stormwater will overland flow to design point K3. Runoff will then travel via curb and gutter along adjacent drives to a proposed inlet along the north side of W 60<sup>th</sup> Avenue, design point H. Then flows will be conveyed through proposed storm sewer before ultimately discharging to the proposed water quality pond located at the south side of the Site (basin G).

**Sub-Basin K4**

Sub-basin K4 is a future mixed-use development with an assumed imperviousness of 90%. Stormwater will overland flow to design point K4. Runoff will then travel via curb and gutter along the adjacent drive to a proposed inlet along the north side of W 60<sup>th</sup> Avenue, design point L. Then flows will be conveyed through proposed storm sewer before ultimately discharging to the proposed water quality pond located at the south side of the Site (basin G).

**Sub-Basin L**

Sub-basin L is comprised of sidewalks, tree lawns and paved drives. Stormwater will overland flow to the adjacent drives where it will be conveyed via curb and gutter to a proposed inlet along the north side of W 60<sup>th</sup> Avenue, design point L. Then flows will be conveyed through proposed storm sewer before ultimately discharging to the proposed water quality pond located at the south side of the Site (basin G).

**Sub-Basin M**

Sub-basin M is comprised of sidewalks, tree lawns and paved drives. Stormwater will overland flow to the adjacent drives where it will be conveyed via curb and gutter to a proposed inlet along the south side of W 60<sup>th</sup> Avenue, design point M. Then flows will be conveyed through proposed storm sewer before ultimately discharging to the proposed water quality pond located at the south side of the Site (basin G).

**Sub-Basin N1**

Sub-basin N1 is a future mixed-use development with an assumed imperviousness of 90%. It is proposed that this sub-basin will tie directly into the proposed storm sewer along W 60<sup>th</sup> Avenue or within the private drive, design point N1. Then flows will be conveyed through proposed storm sewer

before ultimately discharging to the proposed water quality pond located at the south side of the Site (basin G).

**Sub-Basin N2**

Sub-basin N2 is a future mixed-use development with an assumed imperviousness of 90%. Stormwater will overland flow to design point N2. Runoff will then travel via curb and gutter along adjacent drives to a proposed inlet along the south side of W 60<sup>th</sup> Avenue, design point I. Then flows will be conveyed through proposed storm sewer before ultimately discharging to the proposed water quality pond located at the south side of the Site (basin G).

**Sub-Basin N3**

Sub-basin N3 is a future mixed-use development with an assumed imperviousness of 90%. Stormwater will overland flow to design point N3. Runoff will then travel via curb and gutter along the adjacent drive to a proposed inlet along the south side of W 60<sup>th</sup> Avenue, design point M. Then flows will be conveyed through proposed storm sewer before ultimately discharging to the proposed water quality pond located at the south side of the Site (basin G).

**Sub-Basin N4**

Sub-basin N4 is a future mixed-use development with an assumed imperviousness of 90%. Stormwater will overland flow to design point N4 and future LID improvement.

**Sub-Basin O**

Sub-basin O is comprised of landscaping and is located in the northeast of the site. No improvements are proposed within this sub-basin. Runoff will maintain the existing drainage pattern and be conveyed north via overland flow along the ditch along the north side of the property before entering an existing storm structure. The flows will travel north via existing storm sewer along Federal Boulevard before ultimately outfalling into the South Platte River.

**Sub-Basin OS1**

Sub-basin OS1 is comprised of landscaping and is located in the northwest portion of the of the Site. No improvements are proposed within this sub-basin. Runoff will maintain the existing drainage pattern and be conveyed north via overland flow to design point OS1, ultimately to outfall in Lake Sangraco located west of the Site.

**Sub-Basin OS2**

Sub-basin OS2 is comprised of landscaping and is located in the southwest corner of the Site. Runoff will match historic drainage patterns and will be conveyed via overland flow directly discharging into Clear Creek, design point OS2.

**Sub-Basin OS3**

Sub-basin OS3 is comprised of landscaping and is located in the southeast portion of the Site. Runoff will match historic drainage patterns and will be conveyed via overland flow directly discharging into Clear Creek, design point OS3.

**Sub-Basin OF1**

Sub-basin OF1 is located off-site and contains the west portion of Federal Boulevard. This area is comprised of concrete sidewalk, tree lawn, and paved drive. Runoff travels north via curb and gutter to a curb cut and concrete channel, design point OF1. Runoff is routed to a proposed rain garden

located in sub-basin J-2. Then flows will outfall into the existing public storm sewer along Federal Boulevard before ultimately outfalling into the South Platte River.

**Sub-Basin OF2**

Sub-basin OF2 is located off-site and is comprised of landscaping and sidewalk located in the southeast corner of the Site. Runoff will match historic drainage patterns and will be conveyed via overland flow directly discharging into Clear Creek, design point OF2.

**LOW IMPACT DEVELOPMENT**

According to section 9-01-03-14 of the Adams County Development Standards and Regulations for Storm Drainage Facilities, the use of low impact development (LID) techniques is required to control stormwater runoff from development and redevelopment sites in order to prevent flooding, erosion and stormwater pollution. The new development proposes an onsite impervious area of 611,808 SF. Proposed rain gardens will treat 80,346 SF or 13.1% of the onsite impervious area.

The proposed rain gardens will function as a LID BMP and help maintain natural drainage patterns by allowing more infiltration onsite. The proposed rain gardens function as an engineered, depressed landscape area designed to capture, filter, and infiltrate the water quality capture volume (WQCV). Runoff will infiltrate through the proposed growing media and be conveyed to the respective 12" Nyloplast dome outlet structure via a 4" slotted PVC underdrain. Reference Appendix D for respective Nyloplast inlet hydraulic sizing calculations. The proposed rain gardens located in sub-basins A-1, A-2, and A-3 are designed in series and function as a "treatment train" ultimately tributary to the proposed water quality pond located in sub-basin G.


Additionally, 108,303 SF or 17.7% of the added impervious area within the future commercial and multi-family pads will be treated by an approved LID BMP. This includes on-site tributary sub-basins D, F, K, and N. Future planned LID BMP facilities may include elevated planter beds, sand filters, rain gardens or a combination thereof. The future planned LID BMP facilities will help maintain natural drainage patterns by allowing more infiltration onsite. Future planned LID BMP facilities will directly connect to the proposed storm sewer system via planned PVC underdrains and storm sewer improvements. Per the LID exhibit included in Appendix A, proposed storm sewer outfall connections for the respective LID BMPs are noted along the proposed private storm sewer network.

In summary, LID BMPs will treat 30.8% of the total onsite impervious area. All proposed LID BMP facilities are tributary and ultimately outfall to the proposed water quality pond located along the south side of the Site. The proposed water quality pond is not included as an LID BMP with the proposed Project. All storm infrastructure improvements will be private and maintained by the property owner. Reference Appendix D for supporting BMP hydraulic calculations.

**WATER QUALITY**

Compliance with applicable water quality standards and requirements will be achieved through the implementation of a water quality pond and rain garden. Surface flows will enter the proposed water quality pond along the south perimeter of the Site via proposed inlets and private storm pipe tributary to the water quality pond. The water quality pond's 40-hour drain time for the water quality capture volume (WQCV) is recommended to remove a significant portion of total suspended solids (TSS).

**811** Know what's below.  
Call before you dig.



## LEGEND

|         |                            |
|---------|----------------------------|
| ---     | PROPERTY LINE              |
| - - - - | EASEMENT LINE              |
| ---     | PROPOSED CONTOUR           |
| ---     | PROPOSED STORM SEWER       |
| □       | PROPOSED INLET             |
| ---     | PROPOSED CURB AND GUTTER   |
| ▨       | RAIN GARDEN TREATMENT AREA |
| ▨       | PROPOSED RAIN GARDEN       |
| ▨       | LID PLANTER TREATMENT AREA |

## PROJECT LID SUMMARY

|                                                          |            |            |
|----------------------------------------------------------|------------|------------|
| TOTAL ONSITE IMPERVIOUS AREA                             |            | 611,808 SF |
| <b><u>MINIMUM AREA TO BE TREATED BY LID MEASURES</u></b> |            |            |
| TOTAL TREATED IMPERVIOUS AREAS BY RAIN GARDENS           | 80,346 SF  | 13.1%      |
| TOTAL TREATED IMPERVIOUS AREAS BY LID PLANTERS           | 108,303 SF | 17.7%      |
| TOTAL PROJECT AREA TREATED                               | 188,649 SF | 30.8%      |

TRACTS (A, I, J, K and M) INCLUDE WATER QUALITY PRESERVATION LAND USES AND ARE THEREFORE AREAS TO BE PRESERVED FOR WATER QUALITY AS GRASS BUFFERS.

## CLEAR CREEK TRANSIT VILLAGE LID BMP EXHIBIT AUGUST 18, 2026

INLET MANAGEMENT

Worksheet Protected

|                                    |                          |                          |                          |                            |                            |                            |                            |
|------------------------------------|--------------------------|--------------------------|--------------------------|----------------------------|----------------------------|----------------------------|----------------------------|
| INLET NAME                         | Inlet B1                 | Inlet B2                 | Inlet C1                 | Inlet H                    | Inlet I                    | Inlet L                    | Inlet M                    |
| Site Type (Urban or Rural)         | URBAN                    | URBAN                    | URBAN                    | URBAN                      | URBAN                      | URBAN                      | URBAN                      |
| Inlet Application (Street or Area) | STREET                   | STREET                   | STREET                   | STREET                     | STREET                     | STREET                     | STREET                     |
| Hydraulic Condition                | On Grade                 | In Sump                  | In Sump                  | In Sump                    | In Sump                    | On Grade                   | On Grade                   |
| Inlet Type                         | CDOT Type R Curb Opening | CDOT Type R Curb Opening | CDOT Type R Curb Opening | CDOT/Denver 13 Combination | CDOT/Denver 13 Combination | CDOT/Denver 13 Combination | CDOT/Denver 13 Combination |

USER-DEFINED INPUT

User-Defined Design Flows

|                        |      |      |      |     |     |     |     |
|------------------------|------|------|------|-----|-----|-----|-----|
| Minor $Q_{Down}$ (cfs) | 7.4  | 6.0  | 6.0  | 4.3 | 3.1 | 0.7 | 0.8 |
| Major $Q_{Down}$ (cfs) | 17.1 | 13.1 | 15.6 | 9.8 | 6.5 | 1.5 | 1.7 |

Bypass (Carry-Over) Flow from Upstream 

Inlets must be organized from upstream (left) to downstream (right) in order for bypass flows to be linked.

|                                         |              |              |                         |                         |                         |                         |
|-----------------------------------------|--------------|--------------|-------------------------|-------------------------|-------------------------|-------------------------|
| Receive Bypass Flow from:               | User-Defined | User-Defined | No Bypass Flow Received | No Bypass Flow Received | No Bypass Flow Received | No Bypass Flow Received |
| Minor Bypass Flow Received, $Q_b$ (cfs) | 0.0          | 0.5          | 0.0                     | 0.0                     | 0.0                     | 0.0                     |
| Major Bypass Flow Received, $Q_b$ (cfs) | 0.0          | 5.5          | 0.0                     | 0.0                     | 0.0                     | 0.0                     |

Watershed Characteristics

|                           |  |  |  |  |  |  |
|---------------------------|--|--|--|--|--|--|
| Subcatchment Area (acres) |  |  |  |  |  |  |
| Percent Impervious        |  |  |  |  |  |  |
| NRCS Soil Type            |  |  |  |  |  |  |

Watershed Profile

|                        |  |  |  |  |  |  |
|------------------------|--|--|--|--|--|--|
| Overland Slope (ft/ft) |  |  |  |  |  |  |
| Overland Length (ft)   |  |  |  |  |  |  |
| Channel Slope (ft/ft)  |  |  |  |  |  |  |
| Channel Length (ft)    |  |  |  |  |  |  |

Minor Storm Rainfall Input

|                                           |  |  |  |  |  |  |
|-------------------------------------------|--|--|--|--|--|--|
| Design Storm Return Period, $T_r$ (years) |  |  |  |  |  |  |
| One-Hour Precipitation, $P_1$ (inches)    |  |  |  |  |  |  |

Major Storm Rainfall Input

|                                           |  |  |  |  |  |  |
|-------------------------------------------|--|--|--|--|--|--|
| Design Storm Return Period, $T_r$ (years) |  |  |  |  |  |  |
| One-Hour Precipitation, $P_1$ (inches)    |  |  |  |  |  |  |

CALCULATED OUTPUT


|                                             |      |      |      |     |     |     |     |
|---------------------------------------------|------|------|------|-----|-----|-----|-----|
| Minor Total Design Peak Flow, $Q$ (cfs)     | 7.4  | 6.4  | 6.0  | 4.3 | 3.1 | 0.7 | 0.8 |
| Major Total Design Peak Flow, $Q$ (cfs)     | 17.1 | 18.6 | 15.6 | 9.8 | 6.5 | 1.5 | 1.7 |
| Minor Flow Bypassed Downstream, $Q_b$ (cfs) | 0.5  | N/A  | N/A  | N/A | N/A | 0.0 | 0.1 |
| Major Flow Bypassed Downstream, $Q_b$ (cfs) | 5.5  | N/A  | N/A  | N/A | N/A | 0.2 | 0.3 |

**ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)**

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project: Clear Creek Transit Village

Inlet ID: Inlet C1

**Gutter Geometry:**

Maximum Allowable Width for Spread Behind Curb

Side Slope Behind Curb (leave blank for no conveyance credit behind curb)

Manning's Roughness Behind Curb (typically between 0.012 and 0.020)

Height of Curb at Gutter Flow Line

Distance from Curb Face to Street Crown

Gutter Width

Street Transverse Slope

Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)

Street Longitudinal Slope - Enter 0 for sump condition

Manning's Roughness for Street Section (typically between 0.012 and 0.020)

|            |   |       |       |
|------------|---|-------|-------|
| $T_{BACK}$ | = | 17.5  | ft    |
| $S_{BACK}$ | = | 0.020 | ft/ft |
| $n_{BACK}$ | = | 0.013 |       |

|              |   |       |        |
|--------------|---|-------|--------|
| $H_{CURB}$   | = | 6.00  | inches |
| $T_{CROWN}$  | = | 13.0  | ft     |
| $W$          | = | 1.00  | ft     |
| $S_x$        | = | 0.022 | ft/ft  |
| $S_W$        | = | 0.083 | ft/ft  |
| $S_0$        | = | 0.000 | ft/ft  |
| $n_{STREET}$ | = | 0.013 |        |

Max. Allowable Spread for Minor &amp; Major Storm

Max. Allowable Depth at Gutter Flowline for Minor &amp; Major Storm

Check boxes are not applicable in SUMP conditions

|           | Minor Storm              | Major Storm              |        |
|-----------|--------------------------|--------------------------|--------|
| $T_{MAX}$ | =                        | 13.0                     | ft     |
| $d_{MAX}$ | =                        | 4.1                      | inches |
|           | <input type="checkbox"/> | <input type="checkbox"/> |        |


MINOR STORM Allowable Capacity is not applicable to Sump Condition

MAJOR STORM Allowable Capacity is not applicable to Sump Condition

|             | Minor Storm              | Major Storm              |     |
|-------------|--------------------------|--------------------------|-----|
| $Q_{allow}$ | =                        | SUMP                     | cfs |
|             | <input type="checkbox"/> | <input type="checkbox"/> |     |

# INLET IN A SUMP OR SAG LOCATION

MHFD-Inlet, Version 5.03 (August 2023)



## Design Information (Input)

Type of Inlet  
Local Depression (additional to continuous gutter depression 'a' from above)  
Number of Unit Inlets (Grate or Curb Opening)  
Water Depth at Flowline (outside of local depression)

### Grate Information

Length of a Unit Grate  
Width of a Unit Grate  
Open Area Ratio for a Grate (typical values 0.15-0.90)  
Clogging Factor for a Single Grate (typical value 0.50 - 0.70)  
Grate Weir Coefficient (typical value 2.15 - 3.60)  
Grate Orifice Coefficient (typical value 0.60 - 0.80)

### Curb Opening Information

Length of a Unit Curb Opening  
Height of Vertical Curb Opening in Inches  
Height of Curb Orifice Throat in Inches  
Angle of Throat  
Side Width for Depression Pan (typically the gutter width of 2 feet)  
Clogging Factor for a Single Curb Opening (typical value 0.10)  
Curb Opening Weir Coefficient (typical value 2.3-3.7)  
Curb Opening Orifice Coefficient (typical value 0.60 - 0.70)

### Low Head Performance Reduction (Calculated)

Depth for Grate Midwidth  
Depth for Curb Opening Weir Equation  
Grated Inlet Performance Reduction Factor for Long Inlets  
Curb Opening Performance Reduction Factor for Long Inlets  
Combination Inlet Performance Reduction Factor for Long Inlets

Total Inlet Interception Capacity (assumes clogged condition)

Inlet Capacity IS GOOD for Minor and Major Storms (>Q Peak)


|                              | MINOR                    | MAJOR |         |
|------------------------------|--------------------------|-------|---------|
| Type =                       | CDOT Type R Curb Opening |       |         |
| a <sub>local</sub> =         | 3.00                     | 3.00  | inches  |
| No =                         | 1                        | 1     |         |
| Ponding Depth =              | 4.7                      | 8.5   | inches  |
|                              | MINOR                    | MAJOR |         |
| L <sub>o</sub> (G) =         | N/A                      | N/A   | feet    |
| W <sub>o</sub> =             | N/A                      | N/A   | feet    |
| A <sub>ratio</sub> =         | N/A                      | N/A   |         |
| C <sub>r</sub> (G) =         | N/A                      | N/A   |         |
| C <sub>w</sub> (G) =         | N/A                      | N/A   |         |
| C <sub>o</sub> (G) =         | N/A                      | N/A   |         |
|                              | MINOR                    | MAJOR |         |
| L <sub>o</sub> (C) =         | 15.00                    | 15.00 | feet    |
| H <sub>vert</sub> =          | 6.00                     | 6.00  | inches  |
| H <sub>throat</sub> =        | 6.00                     | 6.00  | inches  |
| Theta =                      | 63.40                    | 63.40 | degrees |
| W <sub>p</sub> =             | 1.00                     | 1.00  | feet    |
| C <sub>r</sub> (C) =         | 0.10                     | 0.10  |         |
| C <sub>w</sub> (C) =         | 3.60                     | 3.60  |         |
| C <sub>o</sub> (C) =         | 0.67                     | 0.67  |         |
|                              | MINOR                    | MAJOR |         |
| d <sub>Grate</sub> =         | N/A                      | N/A   | ft      |
| d <sub>Curb</sub> =          | 0.31                     | 0.63  | ft      |
| RF <sub>Grate</sub> =        | N/A                      | N/A   |         |
| RF <sub>Curb</sub> =         | 0.70                     | 0.91  |         |
| RF <sub>Combination</sub> =  | N/A                      | N/A   |         |
|                              | MINOR                    | MAJOR |         |
| Q <sub>a</sub> =             | 6.9                      | 26.2  | cfs     |
| Q <sub>PEAK REQUIRED</sub> = | 6.0                      | 15.6  | cfs     |

**ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)**

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project: Clear Creek Transit Village

Inlet ID: Inlet H

**Gutter Geometry:**

Maximum Allowable Width for Spread Behind Curb

Side Slope Behind Curb (leave blank for no conveyance credit behind curb)

Manning's Roughness Behind Curb (typically between 0.012 and 0.020)

Height of Curb at Gutter Flow Line

Distance from Curb Face to Street Crown

Gutter Width

Street Transverse Slope

Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)

Street Longitudinal Slope - Enter 0 for sump condition

Manning's Roughness for Street Section (typically between 0.012 and 0.020)

|            |   |       |       |
|------------|---|-------|-------|
| $T_{BACK}$ | = | 5.0   | ft    |
| $S_{BACK}$ | = | 0.020 | ft/ft |
| $n_{BACK}$ | = | 0.013 |       |

|              |   |       |        |
|--------------|---|-------|--------|
| $H_{CURB}$   | = | 6.00  | inches |
| $T_{CROWN}$  | = | 22.0  | ft     |
| $W$          | = | 2.00  | ft     |
| $S_x$        | = | 0.022 | ft/ft  |
| $S_w$        | = | 0.083 | ft/ft  |
| $S_0$        | = | 0.000 | ft/ft  |
| $n_{STREET}$ | = | 0.013 |        |

Max. Allowable Spread for Minor &amp; Major Storm

Max. Allowable Depth at Gutter Flowline for Minor &amp; Major Storm

Check boxes are not applicable in SUMP conditions

|           | Minor Storm              | Major Storm              |        |
|-----------|--------------------------|--------------------------|--------|
| $T_{MAX}$ | =                        | 22.0                     | ft     |
| $d_{MAX}$ | =                        | 6.0                      | inches |
|           | <input type="checkbox"/> | <input type="checkbox"/> |        |

**Maximum Capacity for 1/2 Street based On Allowable Spread**Water Depth without Gutter Depression ( $T \cdot S_x \cdot 12$ )Vertical Depth between Gutter Lip and Gutter Flowline ( $W \cdot S_w \cdot 12$ )Gutter Depression ( $d_c - (W \cdot S_x \cdot 12)$ )Water Depth at Gutter Flowline ( $y + a$ )Allowable Spread for Discharge outside the Gutter Section ( $T - W$ )

Gutter Flow to Design Flow Ratio by FHWA HEC-22 method (Eq. 7-7)

Discharge outside the Gutter Section, carried in Section  $T_x$ Discharge within the Gutter Section ( $Q_T - Q_x - Q_{BACK}$ )

Discharge Behind the Curb (e.g., sidewalk, driveways, &amp; lawns)

Maximum Flow Based On Allowable Spread

Flow Velocity within the Gutter Section

 $V \cdot d$  Product: Flow Velocity times Gutter Flowline Depth

|             | Minor Storm | Major Storm |        |
|-------------|-------------|-------------|--------|
| $y$         | =           | 5.81        | inches |
| $d_c$       | =           | 2.0         | inches |
| $a$         | =           | 1.46        | inches |
| $d$         | =           | 7.27        | inches |
| $T_x$       | =           | 20.0        | ft     |
| $E_0$       | =           | 0.263       |        |
| $Q_x$       | =           | 0.0         | cfs    |
| $Q_w$       | =           | 0.0         | cfs    |
| $Q_{BACK}$  | =           | 0.0         | cfs    |
| $Q_T$       | =           | SUMP        | cfs    |
| $V$         | =           | 0.0         | fps    |
| $V \cdot d$ | =           | 0.0         |        |

**Maximum Capacity for 1/2 Street based on Allowable Depth**

Theoretical Water Spread

Theoretical Spread for Discharge outside the Gutter Section ( $T - W$ )

Gutter Flow to Design Flow Ratio by FHWA HEC-22 method (Eq. 7-7)

Theoretical Discharge outside the Gutter Section, carried in Section  $T_{XTH}$ Actual Discharge outside the Gutter Section, (limited by distance  $T_{CROWN}$ )Discharge within the Gutter Section ( $Q_d - Q_x$ )

Discharge Behind the Curb (e.g., sidewalk, driveways, &amp; lawns)

Total Discharge for Major &amp; Minor Storm (Pre-Safety Factor)

Average Flow Velocity Within the Gutter Section

 $V \cdot d$  Product: Flow Velocity Times Gutter Flowline DepthSlope-Based Safety Factor for Minor/Major Storm depth reduction,  $d \geq 6"$ 

Max Flow based on Allowable Depth (Safety Factor Applied)

Resultant Flow Depth at Gutter Flowline (Safety Factor Applied)

Resultant Flow Depth at Street Crown (Safety Factor Applied)

|             | Minor Storm | Major Storm |        |
|-------------|-------------|-------------|--------|
| $T_{TH}$    | =           | 17.2        | ft     |
| $T_{XTH}$   | =           | 15.2        | ft     |
| $E_0$       | =           | 0.339       |        |
| $Q_{XTH}$   | =           | 0.0         | cfs    |
| $Q_x$       | =           | 0.0         | cfs    |
| $Q_w$       | =           | 0.0         | cfs    |
| $Q_{BACK}$  | =           | 0.0         | cfs    |
| $Q$         | =           | SUMP        | cfs    |
| $V$         | =           | 0.0         | fps    |
| $V \cdot d$ | =           | 0.0         |        |
| $R$         | =           | SUMP        |        |
| $Q_d$       | =           | SUMP        | cfs    |
| $d$         | =           |             | inches |
| $d_{CROWN}$ | =           |             | inches |


MINOR STORM Allowable Capacity is not applicable to Sump Condition

MAJOR STORM Allowable Capacity is not applicable to Sump Condition

|             | Minor Storm | Major Storm |     |
|-------------|-------------|-------------|-----|
| $Q_{allow}$ | =           | SUMP        | cfs |

# INLET IN A SUMP OR SAG LOCATION

MHFD-Inlet, Version 5.03 (August 2023)



## Design Information (Input)

Type of Inlet  
Local Depression (additional to continuous gutter depression 'a' from above)  
Number of Unit Inlets (Grate or Curb Opening)  
Water Depth at Flowline (outside of local depression)

### Grate Information

Length of a Unit Grate  
Width of a Unit Grate  
Open Area Ratio for a Grate (typical values 0.15-0.90)  
Clogging Factor for a Single Grate (typical value 0.50 - 0.70)  
Grate Weir Coefficient (typical value 2.15 - 3.60)  
Grate Orifice Coefficient (typical value 0.60 - 0.80)

### Curb Opening Information

Length of a Unit Curb Opening  
Height of Vertical Curb Opening in Inches  
Height of Curb Orifice Throat in Inches  
Angle of Throat  
Side Width for Depression Pan (typically the gutter width of 2 feet)  
Clogging Factor for a Single Curb Opening (typical value 0.10)  
Curb Opening Weir Coefficient (typical value 2.3-3.7)  
Curb Opening Orifice Coefficient (typical value 0.60 - 0.70)

### Low Head Performance Reduction (Calculated)

Depth for Grate Midwidth  
Depth for Curb Opening Weir Equation  
Grated Inlet Performance Reduction Factor for Long Inlets  
Curb Opening Performance Reduction Factor for Long Inlets  
Combination Inlet Performance Reduction Factor for Long Inlets

Total Inlet Interception Capacity (assumes clogged condition)

Inlet Capacity IS GOOD for Minor and Major Storms (>Q Peak)


|                              | MINOR                      | MAJOR |         |
|------------------------------|----------------------------|-------|---------|
| Type =                       | CDOT/Denver 13 Combination |       |         |
| a <sub>local</sub> =         | 2.00                       | 2.00  | inches  |
| No =                         | 2                          | 2     |         |
| Ponding Depth =              | 6.0                        | 12.0  | inches  |
|                              | MINOR                      | MAJOR |         |
| L <sub>o</sub> (G) =         | 3.00                       | 3.00  | feet    |
| W <sub>o</sub> =             | 1.73                       | 1.73  | feet    |
| A <sub>ratio</sub> =         | 0.43                       | 0.43  |         |
| C <sub>r</sub> (G) =         | 0.50                       | 0.50  |         |
| C <sub>w</sub> (G) =         | 3.30                       | 3.30  |         |
| C <sub>o</sub> (G) =         | 0.60                       | 0.60  |         |
|                              | MINOR                      | MAJOR |         |
| L <sub>o</sub> (C) =         | 3.00                       | 3.00  | feet    |
| H <sub>vert</sub> =          | 6.50                       | 6.50  | inches  |
| H <sub>throat</sub> =        | 5.25                       | 5.25  | inches  |
| Theta =                      | 0.00                       | 0.00  | degrees |
| W <sub>p</sub> =             | 2.00                       | 2.00  | feet    |
| C <sub>r</sub> (C) =         | 0.10                       | 0.10  |         |
| C <sub>w</sub> (C) =         | 3.70                       | 3.70  |         |
| C <sub>o</sub> (C) =         | 0.66                       | 0.66  |         |
|                              | MINOR                      | MAJOR |         |
| d <sub>Grate</sub> =         | 0.52                       | 1.02  | ft      |
| d <sub>Curb</sub> =          | 0.33                       | 0.83  | ft      |
| RF <sub>Grate</sub> =        | 0.71                       | 1.00  |         |
| RF <sub>Curb</sub> =         | N/A                        | N/A   |         |
| RF <sub>Combination</sub> =  | 0.71                       | 1.00  |         |
|                              | MINOR                      | MAJOR |         |
| Q <sub>s</sub> =             | 6.6                        | 21.7  | cfs     |
| Q <sub>PEAK REQUIRED</sub> = | 4.3                        | 9.8   | cfs     |

**ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)**

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project: Clear Creek Transit Village

Inlet ID: Inlet I

**Gutter Geometry:**

Maximum Allowable Width for Spread Behind Curb

Side Slope Behind Curb (leave blank for no conveyance credit behind curb)

Manning's Roughness Behind Curb (typically between 0.012 and 0.020)

Height of Curb at Gutter Flow Line

Distance from Curb Face to Street Crown

Gutter Width

Street Transverse Slope

Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)

Street Longitudinal Slope - Enter 0 for sump condition

Manning's Roughness for Street Section (typically between 0.012 and 0.020)

|            |   |       |       |
|------------|---|-------|-------|
| $T_{BACK}$ | = | 5.0   | ft    |
| $S_{BACK}$ | = | 0.020 | ft/ft |
| $n_{BACK}$ | = | 0.013 |       |

|              |   |       |        |
|--------------|---|-------|--------|
| $H_{CURB}$   | = | 6.00  | inches |
| $T_{CROWN}$  | = | 22.0  | ft     |
| $W$          | = | 2.00  | ft     |
| $S_x$        | = | 0.022 | ft/ft  |
| $S_w$        | = | 0.083 | ft/ft  |
| $S_0$        | = | 0.000 | ft/ft  |
| $n_{STREET}$ | = | 0.013 |        |

Max. Allowable Spread for Minor &amp; Major Storm

Max. Allowable Depth at Gutter Flowline for Minor &amp; Major Storm

Check boxes are not applicable in SUMP conditions

|           | Minor Storm              | Major Storm              |        |
|-----------|--------------------------|--------------------------|--------|
| $T_{MAX}$ | =                        | 22.0                     | ft     |
| $d_{MAX}$ | =                        | 6.0                      | inches |
|           | <input type="checkbox"/> | <input type="checkbox"/> |        |


MINOR STORM Allowable Capacity is not applicable to Sump Condition

MAJOR STORM Allowable Capacity is not applicable to Sump Condition

|             | Minor Storm              | Major Storm              |     |
|-------------|--------------------------|--------------------------|-----|
| $Q_{allow}$ | =                        | SUMP                     | cfs |
|             | <input type="checkbox"/> | <input type="checkbox"/> |     |

# INLET IN A SUMP OR SAG LOCATION

MHFD-Inlet, Version 5.03 (August 2023)



| Design Information (Input)                                                   |                            | MINOR                        |                            | MAJOR |                 |
|------------------------------------------------------------------------------|----------------------------|------------------------------|----------------------------|-------|-----------------|
| Type of Inlet                                                                | CDOT/Denver 13 Combination | Type =                       | CDOT/Denver 13 Combination |       |                 |
| Local Depression (additional to continuous gutter depression 'a' from above) |                            | a <sub>local</sub> =         | 2.00                       | 2.00  | inches          |
| Number of Unit Inlets (Grate or Curb Opening)                                |                            | No =                         | 1                          | 1     |                 |
| Water Depth at Flowline (outside of local depression)                        |                            | Ponding Depth =              | 6.0                        | 7.3   | inches          |
| <b>Grate Information</b>                                                     |                            |                              | MINOR                      | MAJOR | Override Depths |
| Length of a Unit Grate                                                       |                            | L <sub>o</sub> (G) =         | 3.00                       | 3.00  | feet            |
| Width of a Unit Grate                                                        |                            | W <sub>o</sub> =             | 1.73                       | 1.73  | feet            |
| Open Area Ratio for a Grate (typical values 0.15-0.90)                       |                            | A <sub>ratio</sub> =         | 0.43                       | 0.43  |                 |
| Clogging Factor for a Single Grate (typical value 0.50 - 0.70)               |                            | C <sub>r</sub> (G) =         | 0.50                       | 0.50  |                 |
| Grate Weir Coefficient (typical value 2.15 - 3.60)                           |                            | C <sub>w</sub> (G) =         | 3.30                       | 3.30  |                 |
| Grate Orifice Coefficient (typical value 0.60 - 0.80)                        |                            | C <sub>o</sub> (G) =         | 0.60                       | 0.60  |                 |
| <b>Curb Opening Information</b>                                              |                            |                              | MINOR                      | MAJOR |                 |
| Length of a Unit Curb Opening                                                |                            | L <sub>o</sub> (C) =         | 3.00                       | 3.00  | feet            |
| Height of Vertical Curb Opening in Inches                                    |                            | H <sub>vert</sub> =          | 6.50                       | 6.50  | inches          |
| Height of Curb Orifice Throat in Inches                                      |                            | H <sub>throat</sub> =        | 5.25                       | 5.25  | inches          |
| Angle of Throat                                                              |                            | Theta =                      | 0.00                       | 0.00  | degrees         |
| Side Width for Depression Pan (typically the gutter width of 2 feet)         |                            | W <sub>p</sub> =             | 2.00                       | 2.00  | feet            |
| Clogging Factor for a Single Curb Opening (typical value 0.10)               |                            | C <sub>r</sub> (C) =         | 0.10                       | 0.10  |                 |
| Curb Opening Weir Coefficient (typical value 2.3-3.7)                        |                            | C <sub>w</sub> (C) =         | 3.70                       | 3.70  |                 |
| Curb Opening Orifice Coefficient (typical value 0.60 - 0.70)                 |                            | C <sub>o</sub> (C) =         | 0.66                       | 0.66  |                 |
| <b>Low Head Performance Reduction (Calculated)</b>                           |                            |                              | MINOR                      | MAJOR |                 |
| Depth for Grate Midwidth                                                     |                            | d <sub>Grate</sub> =         | 0.52                       | 0.63  | ft              |
| Depth for Curb Opening Weir Equation                                         |                            | d <sub>Curb</sub> =          | 0.33                       | 0.44  | ft              |
| Grated Inlet Performance Reduction Factor for Long Inlets                    |                            | RF <sub>Grate</sub> =        | 0.94                       | 1.00  |                 |
| Curb Opening Performance Reduction Factor for Long Inlets                    |                            | RF <sub>Curb</sub> =         | N/A                        | N/A   |                 |
| Combination Inlet Performance Reduction Factor for Long Inlets               |                            | RF <sub>Combination</sub> =  | 0.94                       | 1.00  |                 |
| <b>Total Inlet Interception Capacity (assumes clogged condition)</b>         |                            |                              | MINOR                      | MAJOR |                 |
| Inlet Capacity IS GOOD for Minor and Major Storms (>Q Peak)                  |                            | Q <sub>s</sub> =             | 5.1                        | 6.9   | cfs             |
|                                                                              |                            | Q <sub>PEAK REQUIRED</sub> = | 3.1                        | 6.5   | cfs             |

# Design Procedure Form: Rain Garden (RG)

UD-BMP (Version 3.07, March 2018)

Sheet 1 of 2

Designer: Bryce Willaby  
 Company: Kimley-Horn  
 Date: August 18, 2026  
 Project: Clear Creek Transit Village - Planter 01  
 Location: Adams County, CO

## 1. Basin Storage Volume

- A) Effective Imperviousness of Tributary Area,  $I_a$   
 (100% if all paved and roofed areas upstream of rain garden)
- B) Tributary Area's Imperviousness Ratio ( $i = I_a/100$ )
- C) Water Quality Capture Volume (WQCV) for a 12-hour Drain Time  
 (WQCV =  $0.8 * (0.91 * i^3 - 1.19 * i^2 + 0.78 * i)$ )
- D) Contributing Watershed Area (including rain garden area)
- E) Water Quality Capture Volume (WQCV) Design Volume  
 Vol = (WQCV / 12) \* Area
- F) For Watersheds Outside of the Denver Region, Depth of  
 Average Runoff Producing Storm
- G) For Watersheds Outside of the Denver Region,  
 Water Quality Capture Volume (WQCV) Design Volume
- H) User Input of Water Quality Capture Volume (WQCV) Design Volume  
 (Only if a different WQCV Design Volume is desired)

$I_a =$   %

$i =$

WQCV =  watershed inches

Area =  sq ft

$V_{WQCV} =$   cu ft

$d_e =$   in

$V_{WQCV \text{ OTHER}} =$   cu ft

$V_{WQCV \text{ USER}} =$   cu ft

## 2. Basin Geometry

- A) WQCV Depth (12-inch maximum)
- B) Rain Garden Side Slopes ( $Z = 4$  min., horiz. dist per unit vertical)  
 (Use "0" if rain garden has vertical walls)
- C) Minimum Flat Surface Area
- D) Actual Flat Surface Area
- E) Area at Design Depth (Top Surface Area)
- F) Rain Garden Total Volume  
 ( $V_T = ((A_{Top} + A_{Actual}) / 2) * \text{Depth}$ )

$D_{WQCV} =$   in

$Z =$   ft / ft

$A_{Min} =$   sq ft

$A_{Actual} =$   sq ft

$A_{Top} =$   sq ft

$V_T =$   cu ft

## 3. Growing Media

Choose One   
☐ 18" Rain Garden Growing Media  
☐ Other (Explain):  
 \_\_\_\_\_  
 \_\_\_\_\_

## 4. Underdrain System

- A) Are underdrains provided?
- B) Underdrain system orifice diameter for 12 hour drain time
- i) Distance From Lowest Elevation of the Storage  
 Volume to the Center of the Orifice
- ii) Volume to Drain in 12 Hours
- iii) Orifice Diameter, 3/8" Minimum

Choose One   
☐ YES  
☐ NO

$y =$   ft

$Vol_{12} =$   cu ft

$D_o =$   in

# Design Procedure Form: Rain Garden (RG)

UD-BMP (Version 3.07, March 2018)

Sheet 1 of 2

Designer: Bryce Willaby  
 Company: Kimley-Horn  
 Date: August 18, 2026  
 Project: Clear Creek Transit Village - Planter 03  
 Location: Adams County, CO

## 1. Basin Storage Volume

- A) Effective Imperviousness of Tributary Area,  $I_a$   
 (100% if all paved and roofed areas upstream of rain garden)
- B) Tributary Area's Imperviousness Ratio ( $i = I_a/100$ )
- C) Water Quality Capture Volume (WQCV) for a 12-hour Drain Time  
 (WQCV =  $0.8 * (0.91 * i^3 - 1.19 * i^2 + 0.78 * i)$ )
- D) Contributing Watershed Area (including rain garden area)
- E) Water Quality Capture Volume (WQCV) Design Volume  
 Vol = (WQCV / 12) \* Area
- F) For Watersheds Outside of the Denver Region, Depth of  
 Average Runoff Producing Storm
- G) For Watersheds Outside of the Denver Region,  
 Water Quality Capture Volume (WQCV) Design Volume
- H) User Input of Water Quality Capture Volume (WQCV) Design Volume  
 (Only if a different WQCV Design Volume is desired)

$I_a =$   %

$i =$

WQCV =  watershed inches

Area =  sq ft

$V_{WQCV} =$   cu ft

$d_e =$   in

$V_{WQCV \text{ OTHER}} =$   cu ft

$V_{WQCV \text{ USER}} =$   cu ft

## 2. Basin Geometry

- A) WQCV Depth (12-inch maximum)
- B) Rain Garden Side Slopes ( $Z = 4$  min., horiz. dist per unit vertical)  
 (Use "0" if rain garden has vertical walls)
- C) Minimum Flat Surface Area
- D) Actual Flat Surface Area
- E) Area at Design Depth (Top Surface Area)
- F) Rain Garden Total Volume  
 ( $V_T = ((A_{Top} + A_{Actual}) / 2) * \text{Depth}$ )

$D_{WQCV} =$   in

$Z =$   ft / ft

$A_{Min} =$   sq ft

$A_{Actual} =$   sq ft

$A_{Top} =$   sq ft

$V_T =$   cu ft

## 3. Growing Media

Choose One   
☐ 18" Rain Garden Growing Media  
☐ Other (Explain):  
 \_\_\_\_\_  
 \_\_\_\_\_

## 4. Underdrain System

- A) Are underdrains provided?
- B) Underdrain system orifice diameter for 12 hour drain time
- i) Distance From Lowest Elevation of the Storage  
 Volume to the Center of the Orifice
- ii) Volume to Drain in 12 Hours
- iii) Orifice Diameter, 3/8" Minimum

Choose One   
☐ YES  
☐ NO

$y =$   ft

$Vol_{12} =$   cu ft

$D_o =$   in



## APPENDIX B – Rational Method Calculations

# STANDARD FORM SF-1

## PROPOSED RUNOFF COEFFICIENTS - IMPERVIOUS CALCULATION

PROJECT NAME: Clear Creek Transit Village PA5

DATE: 9/1/2026

PROJECT NUMBER: 196395017

CALCULATED BY: MKL

CHECKED BY: AGR

SOIL: A

|                 | LAWNS | DRIVES & WALKS | BUILDING ROOF | PAVED | APARTMENTS & BUSINESS | PARKS |
|-----------------|-------|----------------|---------------|-------|-----------------------|-------|
| LAND USE:       | AREA  | AREA           | AREA          | AREA  | AREA                  | AREA  |
| 2-YEAR COEFF.   | 0.01  | 0.73           | 0.73          | 0.84  | 0.73                  | 0.04  |
| 5-YEAR COEFF.   | 0.01  | 0.75           | 0.75          | 0.86  | 0.75                  | 0.05  |
| 10-YEAR COEFF.  | 0.01  | 0.77           | 0.77          | 0.87  | 0.77                  | 0.05  |
| 100-YEAR COEFF. | 0.13  | 0.81           | 0.81          | 0.89  | 0.81                  | 0.19  |
| IMPERVIOUS %    | 2%    | 90%            | 90%           | 100%  | 90%                   | 10%   |

| DESIGN BASIN                         | DESIGN POINT | LAWNS AREA (AC) | DRIVES & WALKS AREA (AC) | BUILDING ROOF AREA (AC) | PAVED AREA (AC) | APARTMENTS & BUSINESS AREA (AC) | PARKS AREA (AC) | TOTAL AREA (AC) | C(2) | C(5) | C(10) | C(100) | Imp % |
|--------------------------------------|--------------|-----------------|--------------------------|-------------------------|-----------------|---------------------------------|-----------------|-----------------|------|------|-------|--------|-------|
| On-Site Basins - Connects to OA CCTV |              |                 |                          |                         |                 |                                 |                 |                 |      |      |       |        |       |
| C1                                   | C1           | 0.16            | 0.30                     | 0.37                    | 0.34            | 0.00                            | 0.00            | 1.17            | 0.66 | 0.68 | 0.69  | 0.74   | 81%   |
| I1                                   | I1           | 0.02            | 0.09                     | 0.16                    | 0.01            | 0.00                            | 0.00            | 0.29            | 0.68 | 0.70 | 0.71  | 0.76   | 84%   |
| G1                                   | G            | 0.08            | 0.03                     | 0.22                    | 0.00            | 0.00                            | 0.00            | 0.33            | 0.56 | 0.58 | 0.59  | 0.65   | 70%   |
| BASIN SUBTOTAL                       |              | 0.26            | 0.42                     | 0.75                    | 0.35            | 0.00                            | 0.00            | 1.78            | 0.65 | 0.67 | 0.68  | 0.73   | 79%   |
|                                      |              | 14%             | 24%                      | 42%                     | 20%             | 0%                              | 0%              | 100%            |      |      |       |        |       |

Notes:

1. Imperviousness (I), values per UDFCD Criteria Manual Volume 1, Table 6-3
2. Runoff Coefficients (C), values per UDFCD Criteria Manual Volume 1, Table 6-4
3. Rainfall Intensities (i), values per Adams County Stormwater Drainage Design and Stormwater Quality Control Regulations, Chapter 9, Table 9-3



STANDARD FORM SF-2  
Proposed Time of Concentration

PROJECT NAME: Clear Creek Transit Village PA5  
PROJECT NUMBER: 196395017  
CALCULATED BY: MKL  
CHECKED BY: AGR

DATE: 9/1/2026

| SUB-BASIN DATA                                                                                                                                                                                                                                                                                |             |        | INITIAL TIME (T <sub>i</sub> ) |             |                         | TRAVEL TIME (T <sub>i</sub> ) |             |                    |              |                          | T <sub>c</sub> CHECK (URBANIZED BASINS) |                   |                  |                 |                          | FINAL T <sub>c</sub> |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------|--------|--------------------------------|-------------|-------------------------|-------------------------------|-------------|--------------------|--------------|--------------------------|-----------------------------------------|-------------------|------------------|-----------------|--------------------------|----------------------|
| DESIGN BASIN (1)                                                                                                                                                                                                                                                                              | AREA Ac (2) | C5 (3) | LENGTH Ft (4)                  | SLOPE % (5) | T <sub>i</sub> Min. (6) | LENGTH Ft. (7)                | SLOPE % (8) | C <sub>v</sub> (9) | VEL fps (11) | T <sub>i</sub> Min. (12) | COMP. tc (13)                           | TOTAL LENGTH (14) | TOTAL SLOPE (15) | TOTAL IMP. (16) | T <sub>c</sub> Min. (17) | Min.                 |
| On-Site Basins                                                                                                                                                                                                                                                                                |             |        |                                |             |                         |                               |             |                    |              |                          |                                         |                   |                  |                 |                          |                      |
| C1                                                                                                                                                                                                                                                                                            | 1.17        | 0.68   | 120                            | 2.0%        | 6.7                     | 250                           | 0.5%        | 20.0               | 1.4          | 2.9                      | 9.6                                     | 370               | 1.0%             | 81%             | 15.3                     | 9.6                  |
| I1                                                                                                                                                                                                                                                                                            | 0.29        | 0.70   | 115                            | 2.0%        | 6.2                     | 95                            | 0.5%        | 20.0               | 1.4          | 1.1                      | 7.3                                     | 210               | 1.3%             | 84%             | 13.2                     | 7.3                  |
| G1                                                                                                                                                                                                                                                                                            | 0.33        | 0.58   | 55                             | 2.0%        | 5.6                     |                               |             |                    |              |                          | 5.6                                     | 55                | 2.0%             | 70%             | 14.5                     | 5.6                  |
| <div><div><math display="block">t_i = \frac{0.395(1.1 - C_s)\sqrt{L_i}}{S_o^{0.33}}</math></div><div><math display="block">t_i = \frac{L_i}{60K\sqrt{S_o}} = \frac{L_i}{60V_i}</math></div><div><math display="block">t_c = (26 - 17i) + \frac{L_i}{60(14i + 9)\sqrt{S_i}}</math></div></div> |             |        |                                |             |                         |                               |             |                    |              |                          |                                         |                   |                  |                 |                          |                      |

Kimley»Horn

STANDARD FORM SF-3

PROPOSED STORM DRAINAGE DESIGN - RATIONAL METHOD 5 YEAR EVENT

PROJECT NAME: Clear Creek Transit Village PA5

PROJECT NUMBER: 196395017

CALCULATED BY: MKL

CHECKED BY: AGR

P<sub>1</sub> (1-Hour Rainfall) =

1.42

DATE: 9/1/2026

| STORM<br>LINE  | DESIGN<br>POINT | DIRECT RUNOFF   |              |                      |                      |         |              |            | REMARKS |
|----------------|-----------------|-----------------|--------------|----------------------|----------------------|---------|--------------|------------|---------|
|                |                 | DESIGN<br>BASIN | AREA<br>(AC) | RUNOFF<br>F<br>COEFF | t <sub>c</sub> (min) | C*A(ac) | I<br>(in/hr) | Q<br>(cfs) |         |
| (1)            | (2)             | (3)             | (4)          | (5)                  | (6)                  | (7)     | (8)          | (9)        | (10)    |
| On-Site Basins |                 |                 |              |                      |                      |         |              |            |         |
|                | C1              | C1              | 1.17         | 0.68                 | 9.61                 | 0.80    | 3.90         | 3.11       |         |
|                | I1              | I1              | 0.29         | 0.70                 | 7.35                 | 0.20    | 4.30         | 0.86       |         |
|                | G               | G1              | 0.33         | 0.58                 | 5.60                 | 0.19    | 4.67         | 0.89       |         |



STANDARD FORM SF-3

PROPOSED STORM DRAINAGE DESIGN - RATIONAL METHOD 100 YEAR EVENT

PROJECT NAME: Clear Creek Transit Village PA5

PROJECT NUMBER: 196395017

CALCULATED BY: MKL

CHECKED BY: AGR

P<sub>1</sub> (1-Hour Rainfall) =

2.71

DATE: 9/1/2026

| STORM<br>LINE  | DESIGN<br>POINT | DIRECT RUNOFF   |              |                 |                      |         |              |            | REMARKS |
|----------------|-----------------|-----------------|--------------|-----------------|----------------------|---------|--------------|------------|---------|
|                |                 | DESIGN<br>BASIN | AREA<br>(AC) | RUNOFF<br>COEFF | t <sub>c</sub> (min) | C*A(ac) | I<br>(in/hr) | Q<br>(cfs) |         |
| (1)            | (2)             | (3)             | (4)          | (5)             | (6)                  | (7)     | (8)          | (9)        | (10)    |
| On-Site Basins |                 |                 |              |                 |                      |         |              |            |         |
|                | C1              | C1              | 1.17         | 0.74            | 9.61                 | 0.86    | 7.45         | 6.44       |         |
|                | I1              | I1              | 0.29         | 0.76            | 7.35                 | 0.22    | 8.20         | 1.79       |         |
|                | G               | G1              | 0.33         | 0.65            | 5.60                 | 0.21    | 8.91         | 1.91       |         |



PROJECT NAME: Clear Creek Transit Village PA5

DATE: 9/1/2026

PROJECT NUMBER: 196395017

CALCULATED BY: MKL


CHECKED BY: AGR

#### PROPOSED RATIONAL CALCULATIONS SUMMARY

| DESIGN POINT   | TRIBUTARY BASINS | TRIBUTARY AREA (AC) | IMPERVIOUSNESS % | PEAK FLOWS (CFS) |       |
|----------------|------------------|---------------------|------------------|------------------|-------|
|                |                  |                     |                  | Q5               | Q100  |
| On-Site Basins |                  |                     |                  |                  |       |
| C1             | C1               | 1.17                | 81%              | 3.11             | 6.44  |
| I1             | I1               | 0.29                | 84%              | 0.86             | 1.79  |
| G              | G1               | 0.33                | 70%              | 0.89             | 1.91  |
| TOTAL          |                  | 1.78                | 79%              | 4.86             | 10.14 |



## APPENDIX C – LID



**LEGEND:**

- PROPERTY LINE
- EASEMENT LINE
- PROPOSED CONTOUR
- PROPOSED STORM SEWER
- ===== PROPOSED CURB AND GUTTER
- //// LID PLANTER AREA
- //// LID PLANTER TREATMENT AREA

# Design Procedure Form: Rain Garden (RG)

UD-BMP (Version 3.07, March 2018)

Sheet 1 of 2

Designer: Maya Lewey  
 Company: Kimley-Horn  
 Date: August 19, 2026  
 Project: Clear Creek Transit Village PA5 Planters (4)  
 Location: Adams County, CO

## 1. Basin Storage Volume

- A) Effective Imperviousness of Tributary Area,  $I_a$   
 (100% if all paved and roofed areas upstream of rain garden)
- B) Tributary Area's Imperviousness Ratio ( $i = I_a/100$ )
- C) Water Quality Capture Volume (WQCV) for a 12-hour Drain Time  
 (WQCV =  $0.8 * (0.91 * i^3 - 1.19 * i^2 + 0.78 * i)$ )
- D) Contributing Watershed Area (including rain garden area)
- E) Water Quality Capture Volume (WQCV) Design Volume  
 Vol = (WQCV / 12) \* Area
- F) For Watersheds Outside of the Denver Region, Depth of  
 Average Runoff Producing Storm
- G) For Watersheds Outside of the Denver Region,  
 Water Quality Capture Volume (WQCV) Design Volume
- H) User Input of Water Quality Capture Volume (WQCV) Design Volume  
 (Only if a different WQCV Design Volume is desired)

$I_a =$   %

$i =$

WQCV =  watershed inches

Area =  sq ft

$V_{WQCV} =$   cu ft

$d_e =$   in

$V_{WQCV \text{ OTHER}} =$   cu ft

$V_{WQCV \text{ USER}} =$   cu ft

## 2. Basin Geometry

- A) WQCV Depth (12-inch maximum)
- B) Rain Garden Side Slopes ( $Z = 4$  min., horiz. dist per unit vertical)  
 (Use "0" if rain garden has vertical walls)
- C) Minimum Flat Surface Area
- D) Actual Flat Surface Area
- E) Area at Design Depth (Top Surface Area)
- F) Rain Garden Total Volume  
 ( $V_T = ((A_{Top} + A_{Actual}) / 2) * \text{Depth}$ )

$D_{WQCV} =$   in

$Z =$   ft / ft

$A_{Min} =$   sq ft

$A_{Actual} =$   sq ft

$A_{Top} =$   sq ft

$V_T =$   cu ft

## 3. Growing Media

Choose One   
☐ 18" Rain Garden Growing Media  
☐ Other (Explain):  
 \_\_\_\_\_  
 \_\_\_\_\_

## 4. Underdrain System

- A) Are underdrains provided?
- B) Underdrain system orifice diameter for 12 hour drain time
- i) Distance From Lowest Elevation of the Storage  
 Volume to the Center of the Orifice
- ii) Volume to Drain in 12 Hours
- iii) Orifice Diameter, 3/8" Minimum

Choose One   
☐ YES  
☐ NO

$y =$   ft


$Vol_{12} =$   cu ft

$D_o =$   in



## APPENDIX D – Proposed Drainage Map


K:\NCO\_Civil\196395017\_CCTV PA3-5\PA5\CADD\PlanSheets\C-DRAN\_PA5.dwg  
THIS DOCUMENT, JOSEPH HORN AND ASSOCIATES, INC. SHALL BE WITHOUT LIABILITY TO KIMLEY-HORN AND ASSOCIATES, INC. INTENDED ONLY FOR THE SPECIFIC PURPOSE AND CLIENT FOR WHICH IT WAS PREPARED. REUSE OF AND IMPROPER RELIANCE ON THIS DOCUMENT WITHOUT WRITTEN AUTHORIZATION AND ADAPTATION BY KIMLEY-HORN AND ASSOCIATES, INC. SHALL BE WITHOUT LIABILITY TO KIMLEY-HORN AND ASSOCIATES, INC.



**LEGEND**

- PROPERTY LINE
- EASEMENT LINE
- CLEAR CREEK 100-YR FLOODPLAIN LIMIT
- EXISTING MAJOR CONTOUR
- EXISTING MINOR CONTOUR
- PROPOSED MAJOR CONTOUR
- PROPOSED MINOR CONTOUR
- PROPOSED STORM SEWER PIPE
- EXISTING STORM SEWER PIPE
- PROPOSED STORM SEWER INLET
- PROPOSED STORM SEWER MANHOLE
- A - DRAINAGE BASIN  
B - BASIN ACREAGE  
C - 5-YEAR RUNOFF COEFFICIENT  
D - 100-YEAR RUNOFF COEFFICIENT
- PROPOSED DRAINAGE PATTERN
- PROPOSED SUB BASIN BOUNDARY
- DESIGN POINT
- PROPOSED LANDSCAPING
- PROPOSED SIDEWALK
- PROPOSED ASPHALT

| PROPOSED RATIONAL CALCULATIONS SUMMARY |                  |                     |                  |                  |       |
|----------------------------------------|------------------|---------------------|------------------|------------------|-------|
| DESIGN POINT                           | TRIBUTARY BASINS | TRIBUTARY AREA (AC) | IMPERVIOUSNESS % | PEAK FLOWS (CFS) |       |
|                                        |                  |                     |                  | Q5               | Q100  |
| On-Site Basins                         |                  |                     |                  |                  |       |
| C1                                     | C1               | 1.17                | 81%              | 3.11             | 6.44  |
| I1                                     | I1               | 0.29                | 84%              | 0.86             | 1.79  |
| G                                      | G1               | 0.33                | 70%              | 0.89             | 1.91  |
| TO TAL                                 |                  | 1.78                | 79%              | 4.86             | 10.14 |



UNPLATTED  
REC NO.  
2018000084696  
(NOT A PART)

CLEAR CREEK TRANSIT VILLAGE PA 5

**Kimley»Horn**

DESIGNED BY: JKV  
DRAWN BY: AVJ  
CHECKED BY: AGR  
DATE: 09/03/2026

**PROPOSED DRAINAGE PLAN**

**PRELIMINARY**  
FOR REVIEW ONLY  
NOT FOR  
CONSTRUCTION

PROJECT NO.  
196395017  
SHEET  
**C11.0**  
17 OF 17



August 19, 2026

Mr. Bryan Byler  
Pacific North Enterprises  
900 Castleton Road, Suite 118  
Castle Rock, CO 80109

Re: Clear Creek Transit Village  
Traffic Compliance Letter  
Adams County, Colorado

Dear Mr. Byler,

This letter has been prepared to provide a trip generation comparison for the proposed mixed-use development within Planning Area-3 (PA-3), PA-4, and PA-5 of the overall Clear Creek Transit Village, located at the northwest corner of the 60<sup>th</sup> Avenue and Federal Boulevard intersection in Adams County, Colorado. Anticipated traffic impacts associated with the overall Clear Creek Transit Village were evaluated in the *Clear Creek Transit Village Traffic Impact Study (TIS)*, dated October 2025. Applicable documents from this traffic study are included as attachments.

### **SITE INFORMATION**

As described in the 2025 TIS, the proposed mixed-use, transit-oriented project, Clear Creek Transit Village features residential and commercial land uses on a 21-acre parcel of land located at the northwest corner of the 60<sup>th</sup> Avenue and Federal Boulevard intersection in Adams County, Colorado. The site is located within walking distance of the existing Regional Transportation District (RTD) G-Line commuter rail station, which is located on the east side of Federal Boulevard at 60<sup>th</sup> Avenue, just to the south of the project. The G-line is an 11-mile commuter rail line that provides service between Denver, Arvada, and Wheat Ridge.

Since the 2025 TIS, the planned layouts of PA-1 through PA-5 have been revised. PA-3 through PA-5 are currently proposed for development as described below. A conceptual site plan for the current proposal is included as an attachment.

- PA-3 – 20 townhomes, 64 mid-rise apartments, and 6,100 square feet of retail space
- PA-4 – a neighborhood park featuring 2,600 square feet of retail space
- PA-5 – 33 townhomes, 78 mid-rise apartments, and 6,100 square feet of retail space

While not part of the currently proposed development project, the planned layouts of PA-1 and PA-2 have also been revised. Therefore, the revised layouts for PA-1 and PA-2 were considered as part of this trip generation comparison. PA-1 and PA-2 are currently planned for development as follows:

- PA-1 – 41 townhomes, 120 mid-rise apartments, and 6,100 square feet of retail space
- PA-2 – 22 townhomes, 78 mid-rise apartments, and 6,100 square feet of retail space

Regional access to the Clear Creek Transit Village will be provided by Interstate 76 (I-76), and Federal Boulevard, also designated as United States Highway 287 (US-287), as well as the RTD Clear Creek/Federal Station for immediate regional commuter rail access. Direct access to the proposed development will be provided by a full movement, signalized access along Federal Boulevard located along the site's northern property line and aligned with the existing median cut on Federal Boulevard, as well as a right-in/right-out access along Federal Boulevard, located approximately 450 feet south of the north property line (at roughly an existing curb cut).

### TRIP GENERATION COMPARISON

Site-generated traffic estimates are determined through a process known as trip generation. The most common practice for the trip generation process is to utilize rates and equations that are based on the proposed land use to estimate traffic generated by the development during a specific time interval. The acknowledged source for trip generation rates and equations is the *Trip Generation Manual*<sup>1</sup> published by the Institute of Transportation Engineers (ITE). ITE has developed these trip rates and equations based on nationwide studies.

The previously prepared *Clear Creek Transit Village TIS*, assumed PA-1 would feature 269 mid-rise apartments (ITE 221), a coffee/donut shop without drive through (ITE 936), a fast casual restaurant (ITE 930), a variety store (ITE 814), and a small office building (ITE 712). PA-2 was assumed to feature 174 mid-rise apartments (ITE 221), a fast casual restaurant (ITE 930), and a variety store (ITE 814). PA-3 and PA-5 were assumed to feature 98 and 255 mid-rise apartments (ITE 221), respectively. PA-4 was assumed to feature a neighborhood park, with no trip generation estimates associated with the planning area. As such, the previous traffic study anticipated that PA-1 through PA-5 would generate approximately 5,694 weekday daily trips, with 400 of these trips occurring during the morning peak hour and 451 of these trips occurring during the afternoon peak hour. The estimated trip generation for the applicable development area anticipated in the previous study is summarized in the table on the following page.

To calculate the anticipated traffic associated with the proposed residential and commercial land uses within PA-3, PA-4, and PA-5, as well as the anticipated future residential and commercial land uses within PA-1 and PA-2, Kimley-Horn utilized the ITE Trip Generation Manual average rates and equations that apply to Single-Family Attached Housing (ITE 215), Multifamily Housing, Low Rise (ITE 220), and Strip Retail Plaza (<40k) (ITE 822). Based on the ITE Trip Generation calculations, PA-1 through PA-5 of the proposed mixed-use development are expected to generate approximately 3,748 weekday daily trips, with 272 of these trips occurring during the morning peak hour and 444 of these trips occurring during the afternoon peak hour. The estimated trip generation for the traffic associated with the proposed development is summarized in the table on the following page. The trip generation calculations are included as attachment.

<sup>1</sup> Institute of Transportation Engineers, *Trip Generation Manual*, Twelfth Edition, Washington DC, 2025.

### Traffic Generation Comparison

| Planning Area                                                                | Use and Size                                                  | Weekday Vehicle Trips |              |     |       |              |     |       |
|------------------------------------------------------------------------------|---------------------------------------------------------------|-----------------------|--------------|-----|-------|--------------|-----|-------|
|                                                                              |                                                               | Daily                 | AM Peak Hour |     |       | PM Peak Hour |     |       |
|                                                                              |                                                               | Total                 | In           | Out | Total | In           | Out | Total |
| Original Traffic Study (Clear Creek Transit Village TIS) - PA-1 through PA-5 |                                                               |                       |              |     |       |              |     |       |
| PA-1                                                                         | Multifamily Housing, Mid-Rise (ITE 221)<br>269 Dwelling Units | 1,278                 | 31           | 55  | 86    | 51           | 27  | 78    |
|                                                                              | Coffee/Donut Shop w/o Drive Through (ITE 936)<br>1,000 Sq Ft  | 286                   | 43           | 41  | 84    | 15           | 14  | 29    |
|                                                                              | Fast Casual Restaurant (ITE 930)<br>6,000 Sq Ft               | 525                   | 7            | 4   | 11    | 37           | 31  | 68    |
|                                                                              | Variety Store (ITE 814)<br>9,000 Sq Ft                        | 516                   | 14           | 11  | 25    | 28           | 26  | 54    |
|                                                                              | Small Office Building (ITE 712)<br>3,027 Sq Ft                | 39                    | 4            | 1   | 5     | 2            | 4   | 6     |
| PA-2                                                                         | Multifamily Housing, Mid-Rise (ITE 221)<br>174 Dwelling Units | 827                   | 20           | 36  | 56    | 33           | 17  | 50    |
|                                                                              | Fast Casual Restaurant (ITE 930)<br>3,000 Sq Ft               | 262                   | 4            | 2   | 6     | 19           | 15  | 34    |
|                                                                              | Variety Store (ITE 814)<br>4,951 Sq Ft                        | 284                   | 8            | 6   | 14    | 15           | 15  | 30    |
| PA-3                                                                         | Multifamily Housing, Mid-Rise (ITE 221)<br>98 Dwelling Units  | 466                   | 11           | 20  | 31    | 18           | 10  | 28    |
| PA-5                                                                         | Multifamily Housing, Mid-Rise (ITE 221)<br>255 Dwelling Units | 1,211                 | 30           | 52  | 82    | 48           | 26  | 74    |
| Original Total Site Generated Trips                                          |                                                               | 5,694                 | 172          | 228 | 400   | 266          | 185 | 451   |
| Current Proposal - PA-3 through PA-5 (with assumed PA-1 & PA-2)              |                                                               |                       |              |     |       |              |     |       |
| PA-1                                                                         | Single-Family Attached Housing (ITE 215)<br>41 Dwelling Units | 269                   | 5            | 14  | 19    | 12           | 9   | 21    |
|                                                                              | Multifamily Housing, Mid-Rise (ITE 221)<br>120 Dwelling Units | 570                   | 15           | 23  | 38    | 23           | 12  | 35    |
|                                                                              | Strip Retail Plaza (<40k) (ITE 822)<br>6,100 Sq Ft            | 332                   | 13           | 11  | 24    | 28           | 27  | 55    |
| PA-2                                                                         | Single-Family Attached Housing (ITE 215)<br>22 Dwelling Units | 145                   | 3            | 7   | 10    | 6            | 5   | 11    |
|                                                                              | Multifamily Housing, Mid-Rise (ITE 221)<br>78 Dwelling Units  | 371                   | 10           | 15  | 25    | 15           | 8   | 23    |
|                                                                              | Strip Retail Plaza (<40k) (ITE 822)<br>6,100 Sq Ft            | 332                   | 13           | 11  | 24    | 28           | 27  | 55    |
| PA-3                                                                         | Single-Family Attached Housing (ITE 215)<br>20 Dwelling Units | 131                   | 2            | 7   | 9     | 6            | 4   | 10    |
|                                                                              | Multifamily Housing, Mid-Rise (ITE 221)<br>64 Dwelling Units  | 304                   | 8            | 13  | 21    | 12           | 7   | 19    |
|                                                                              | Strip Retail Plaza (<40k) (ITE 822)<br>6,100 Sq Ft            | 332                   | 13           | 11  | 24    | 28           | 27  | 55    |
| PA-4                                                                         | Strip Retail Plaza (<40k) (ITE 822)<br>2,600 Sq Ft            | 142                   | 6            | 4   | 10    | 16           | 15  | 31    |
| PA-5                                                                         | Single-Family Attached Housing (ITE 215)<br>33 Dwelling Units | 217                   | 4            | 12  | 16    | 10           | 7   | 17    |
|                                                                              | Multifamily Housing, Mid-Rise (ITE 221)<br>78 Dwelling Units  | 371                   | 10           | 15  | 25    | 15           | 8   | 23    |
|                                                                              | Strip Retail Plaza (<40k) (ITE 822)<br>6,100 Sq Ft            | 332                   | 13           | 11  | 24    | 28           | 27  | 55    |
| Current Proposal Total Site Generated Trips                                  |                                                               | 3,848                 | 115          | 154 | 269   | 227          | 183 | 410   |
| Net Difference in Trips                                                      |                                                               | 1,846                 | 57           | 74  | 131   | 39           | 2   | 41    |

As shown in the table on the previous page, the proposed residential and commercial land uses within PA-3, PA-4, and PA-5, in combination with the anticipated future residential and commercial land uses within PA-1 and PA-2 of Clear Creek Transit Village are expected to generate 1,846 fewer weekday daily trips, with 131 fewer morning peak-hour trips and 41 fewer afternoon peak-hour trips when compared against the applicable development area from the previous study. Based on the anticipated reduction in weekday daily trips, as well as morning and afternoon peak hour trips, it is believed that the proposed mixed-use development of PA-3, PA-4, and PA-5 is in traffic compliance with the previously conducted *Clear Creek Transit Villa TIS*, dated October 2025.

### CONCLUSIONS AND RECOMMENDATIONS

Based on the results of the trip generation comparison presented in this letter, Kimley-Horn and Associates, Inc. believes that the proposed mixed-use development of PA-3, PA-4 and PA-5 is in compliance with the *Clear Creek Transit Village TIS*. It is believed that all potential traffic impacts associated with the proposed project have been previously addressed within the original traffic impact study. As such, no additional traffic analysis is anticipated to be required.

It should be noted that the majority of the transportation infrastructure necessary to support the proposed Clear Creek Transit Village has not yet been constructed. Considering the conclusion noted above, it is recommended that this transportation infrastructure be constructed as recommended in the *Clear Creek Transit Village TIS*.

It is also recommended that when the proposed development and finalized design of PA-1 and PA-2 is prepared, the trip generation assumptions be reconfirmed for the overall PA-1 through PA-5 to ensure that PA-1 and PA-2 are still in compliance with the *Clear Creek Transit Village TIS*.

If you have any questions or need further assistance, please don't hesitate to contact me at (970) 880-1176.

Sincerely,

KIMLEY-HORN AND ASSOCIATES, INC.



Erick W. Berry, P.E., PTOE, RSP<sub>1</sub>  
Project Traffic Engineer



## Original Traffic Study Documents

# **CLEAR CREEK TRANSIT VILLAGE**

## **Traffic Impact Study**

Adams County, Colorado



**Pacific North**

Date: October 10, 2025

**Submitted To:**

**Submitted By:**

Fox Tuttle Transportation Group, LLC  
1580 Logan Street, Suite 600  
Denver, CO 80202

**FOX TUTTLE**

---

**TABLE OF CONTENTS**

|            |                                                                     |           |
|------------|---------------------------------------------------------------------|-----------|
| <b>1.0</b> | <b>Introduction .....</b>                                           | <b>4</b>  |
| <b>2.0</b> | <b>Project Description .....</b>                                    | <b>4</b>  |
| <b>3.0</b> | <b>Study Considerations .....</b>                                   | <b>5</b>  |
| 3.1        | Data Collection .....                                               | 5         |
| 3.2        | Level-of-Service Criteria .....                                     | 6         |
| <b>4.0</b> | <b>Existing Conditions .....</b>                                    | <b>6</b>  |
| 4.1        | Roadways.....                                                       | 6         |
| 4.2        | Intersections .....                                                 | 7         |
| 4.3        | Pedestrian and Bicycle Access.....                                  | 8         |
| 4.4        | Transit Access .....                                                | 8         |
| 4.5        | Existing Intersection Capacity Analysis.....                        | 9         |
| <b>5.0</b> | <b>Future Background Traffic Conditions .....</b>                   | <b>10</b> |
| 5.1        | Future Transportation Improvements to the Study Area .....          | 10        |
| 5.2        | Annual Growth Factor and Future Volume Methodology .....            | 11        |
| 5.3        | Year 2030 Background Intersection Capacity Analysis.....            | 12        |
| 5.4        | Year 2045 Background Intersection Capacity Analysis.....            | 12        |
| <b>6.0</b> | <b>Future Traffic Conditions with Site Development .....</b>        | <b>13</b> |
| 6.1        | Trip Generation .....                                               | 13        |
| 6.2        | Trip Distribution and Assignment.....                               | 15        |
| 6.3        | Year 2030 Background + Project Intersection Capacity Analysis ..... | 16        |
| 6.4        | Year 2045 Background + Project Intersection Capacity Analysis ..... | 17        |
| 6.5        | Auxiliary Lanes.....                                                | 18        |
| 6.6        | Traffic Signal Warrants .....                                       | 19        |
| 6.7        | Corridor Signal Progression .....                                   | 20        |
| <b>7.0</b> | <b>Conclusions .....</b>                                            | <b>22</b> |



### LIST OF TABLES



|                                                                           |    |
|---------------------------------------------------------------------------|----|
| Table 1 – Peak Hour Intersection Level-of-Service and Queue Summary ..... | 24 |
| Table 2 – Peak Hour Queue Summary .....                                   | 25 |
| Table 3a – Trip Generation Estimate .....                                 | 26 |
| Table 3b – Trip Type Breakdown .....                                      | 27 |

### LIST OF FIGURES

|                                                                       |    |
|-----------------------------------------------------------------------|----|
| Figure 1 – Vicinity Map .....                                         | 28 |
| Figure 2 – Conceptual Site Plan .....                                 | 29 |
| Figure 3 –Existing Traffic Volumes .....                              | 30 |
| Figure 4 – Year 2030 Background Traffic Volumes .....                 | 31 |
| Figure 5 – Year 2040 Background Traffic Volumes .....                 | 32 |
| Figure 6 – Site Trip Distribution .....                               | 33 |
| Figure 7 – Site-Generated Traffic Volumes .....                       | 34 |
| Figure 8 – Year 2030 Background + Site-Generated Traffic Volumes..... | 35 |
| Figure 9 – Year 2040 Background + Site-Generated Traffic Volumes..... | 36 |

### APPENDIX

Level of Service Definitions  
 Intersection Capacity Worksheets  
 Signal Progression Time-Space Diagrams  
 Traffic Count Data Sheets  
 Signal Warrant Analysis



---

## CLEAR CREEK TRANSIT VILLAGE TRAFFIC IMPACT STUDY

### 1.0 INTRODUCTION

The Fox Tuttle Transportation Group has prepared this traffic impact study for the proposed Clear Creek Transit Village project located on the west side of Federal Boulevard (US 287) approximately 1/3 mile north of the I-76 interchange in Adams County. The purpose of this study is to identify any potential traffic impacts and to recommend traffic mitigation measures that may be needed with development of the site as proposed. This study addresses short-term (Year 2030) and long-term (Year 2045) traffic conditions with and without the proposed site development. Weekday AM and PM peak hour periods were considered for site specific impacts.

### 2.0 PROJECT DESCRIPTION

The project site is located along the west side of US 287 approximately 1/3-mile north of I-76 and 1/3-mile south of W. 64<sup>th</sup> Avenue. The site vicinity map is shown on **Figure 1**. The mixed-use, transit-oriented project is proposing to develop residential and commercial land uses on a 21-acre parcel of land that is currently unused. The site is located within walking distance to the existing Regional Transportation District (RTD) G-Line commuter rail station, which is located on the east side of Federal Blvd. at W. 60<sup>th</sup> Avenue just to the south of the project. The G-Line is a 11-mile commuter rail line that provides service between Denver, Arvada, and Wheat Ridge.

The preliminary site and access plan is shown on **Figure 2**. Access to the site is proposed, as follows:

- Full-movement, signalized access along Federal Boulevard located along the north site property line and aligned with the existing median cut on Federal Boulevard.
- Right-in/right-out access along Federal Boulevard approximately 450 feet south of the north property line (at roughly an existing curb cut)

Three existing curb cuts along Federal Blvd. currently serving the property will be removed.

---

**All of the study intersections are expected to operate overall at acceptable levels-of-service (LOS D or better).** The movements identified to operate at LOS E during the peak hours under Year 2030 Background conditions, are anticipated to continue to operate at LOS E under Year 2045 Background conditions. The following additional movements are also anticipated to operate at LOS E or F:

**Federal Boulevard at 64<sup>th</sup> Avenue**

- During the PM peak hour, the eastbound and northbound left-turn movements are expected to operate at LOS E.

## **6.0 FUTURE TRAFFIC CONDITIONS WITH SITE DEVELOPMENT**

This section discusses impacts associated with the proposed development in the short-term and long-term conditions. In addition to the study intersections, the proposed site accesses were also evaluated during the AM and PM peak hours.

### **6.1 Trip Generation**

The Clear Creek Transit Village project is proposing to develop roughly 1.1 million square feet of mixed-use, transit-oriented development. The project will include high-density residential land uses and mixed-use neighborhood retail/commercial. As a transit-oriented development, the project will be designed to promote alternative-mode use including transit ridership, walking, and bicycling.

Based on the most current development scenario, the project proposes the following land uses and square feet (SF) per use at full build out (note that proposed units and SF may change as plans are refined):

- Approx. 937 residential dwelling units (both townhomes and rental units)
- Approx. 27,000 square feet of retail/restaurant and commercial uses

The project is anticipated to be fully built out within the first five years. To determine the traffic impacts associated with the development of the site, the amount of traffic generated by the proposed land uses

---

were estimated. Trip generation estimates for the site uses were obtained from the Institute of Transportation Engineers (ITE) trip generation manual<sup>3</sup> for the following land use categories:

- Multifamily Housing Low-Rise (ITE# 220)
- Multifamily Housing Mid-Rise (ITE# 221)
- Variety Store (General Retail) (ITE# 814)
- Fast-Casual Restaurant (ITE# 930)
- Coffee/Donut Shop without Drive-Through (ITE# 936)
- Small Office Building (ITE# 712)

Since the project is proposing a high-density, mixed-use transit-oriented development, it is anticipated that the site will generate significantly less traffic than the ITE rates predict. The ITE rates are based primarily on studies that were performed in suburban centers where there is a lack of transit and alternative mode options. Since the project proposes a mix of uses within a high-density development, we anticipate that many trips will involve non-auto uses and that multi-use trips (trips between two or more site land uses) will occur. In order to account for these trips, reduction factors for non-auto (transit, pedestrian, bicycle) and internal (multi-use trips) were applied to the ITE rates. Recent studies<sup>4</sup> have found that transit-oriented developments can generate upwards of 40% less trips than traditional ITE rates. Given that the area around the Clear Creek Transit Village site may not redevelop as quickly with high-density uses, we have assumed more modest reductions in this analysis to provide a more conservative basis for evaluation of site traffic impacts. Based on our experience with similar projects, we have assumed the following minimum reduction factors for this study, with actual reductions at area buildout likely to be much higher):

- Multi-Modal Reduction: Given the proximity of the planned Gold Line station just east of the site, a reduction of 10% was assumed for all uses to account for increased transit and non-auto use compared to the ITE rates.
- Internal Trip Reduction: These internal trips occur from one land use or building to another within the site boundaries and surrounding, connected land uses. For example, a person living in one of the proposed apartment complexes may visit the new retail or a restaurant customer may visit

---

<sup>3</sup> Trip Generation, Institute of Transportation Engineers, 11<sup>th</sup> Edition, 2021.

<sup>4</sup> "New Transit Cooperative Research Program Research Confirms Transit-Oriented Developments Produce Fewer Auto Trips". G.B. Arrington, Kimi Iboshi Sloop. ITE Journal. June 2009.

---

several retail stores during one visit. Multi-use or multi-purpose trips typically do not affect the exterior site access points, nor add any additional traffic volumes to the adjacent street network. Due to the walkability and relatively small size of the site, it is not anticipated that the site would experience many internal (starting and ending within the site) automobile trips and thus no internal trip reduction was assumed, to provide a conservative basis.

The proposed land use square footages were applied to the ITE trip rates to estimate the new site traffic as shown in **Table 3a**. Based on ITE methodology and the trip reduction assumptions discussed in this section, the project is anticipated to generate approximately 6,359 weekday daily driveway trips with 453 trips occurring in the AM peak hour and 537 trips occurring during the PM peak hour.

Due to the nature of the retail and restaurant uses proposed for the project, a percentage of the automobile traffic entering and exiting the site will be “pass-by” traffic from the adjacent roadway traffic flows. This traffic currently exists on the adjacent street network and will therefore not be considered “new” traffic to the overall region. However, these trips will add to the site access volumes and are accounted for in the site-generated traffic estimates. Thus, pass-by trips are *not* a reduction. An example would be someone driving on Federal Blvd. to work in Denver in the morning that stops at the coffee shop on site, then continues on their route to work. This is a new trip at the site driveway but is not a new trip to the surrounding roadway system. Given the size of the project and adjacent roadway traffic volumes, it was assumed that site retail, restaurants and coffee shop may experience 30% to 70% pass-by trips based on ITE average rates for each use.

Applying these pass-by assumptions, the trip type breakdown is provided on **Table 3b**. As shown, the new site uses are anticipated to generate the following primary and pass-by trips:

- Primary Trips: 5,502 daily, 363 AM peak hour, 438 PM peak hour
- Pass-by Trips: 864 daily, 90 AM peak hour, 99 PM peak hour

## 6.2 Trip Distribution and Assignment

The estimated site trips presented in **Table 3b** were distributed onto the adjacent street network based on existing and future land use and traffic patterns in the area. Assumed site distribution percentages for the primary site trips are shown on **Figure 6**. Pass-by traffic distribution at the site accesses was assumed based on existing and future traffic volumes and directional distribution along Federal Boulevard adjacent to the site.

---

## CONCLUSIONS

The project site is located along the west side of US 287 approximately 1/3-mile north of I-76 and 1/3-mile south of W. 64<sup>th</sup> Avenue. The project will include high-density residential and ground-floor neighborhood retail, restaurant, and commercial space. As a transit-oriented development, the project will be designed to promote alternative-mode use including transit ridership, walking, and bicycling.

Based on the most current development scenario, the project proposes the following land uses and square feet (SF) per use at full build out:

- Approx. 937 residential dwelling units (both townhomes and rental units)
- Approx. 27,000 square feet of retail/restaurant and commercial uses

Exact uses and tenants for the retail/commercial space is unknown but conservative assumptions have been used, including a coffee shop and restaurant spaces (which relatively typically high trip generators). Based on the trip generation analysis, the project is anticipated to generate 6,359 weekday daily driveway trips with 453 trips occurring in the AM peak hour and 537 trips occurring during the PM peak hour. Due to the nature of the retail and restaurant uses proposed for the project, a percentage of the automobile traffic entering and exiting the site will be “pass-by” traffic from the adjacent roadway traffic flows. Approximately 864 daily, 90 AM peak hour, 99 PM peak hour trips generated by the project site are expected to be pass-by trips that would otherwise already exist on Federal Blvd., but will be new trips at the site driveways.

Two access locations to the site are proposed. A full-movement, signalized access along Federal Boulevard located along the north site property line and aligned with the existing median cut on Federal Boulevard. A second right-in/right-out access along Federal Boulevard approximately 450 feet south of the north property line is also proposed.

Results of the short-term (Year 2030) and long-term (Year 2045) traffic operations analysis indicate that all of the study intersections are expected to operate overall at acceptable levels-of-service (LOS D or better) with the site generated traffic. Further, all of the study intersections are expected to operate at the same LOS as Year 2030 and Year 2045 Background condition.

In addition to the proposed access design along the project Federal Blvd. frontage, the project should implement the following improvements and modifications:

1. A signal is recommended at the existing full-movement access along Federal Boulevard when traffic volumes warrant. Per this study, MUTCD Four-Hour warrants will be met with buildout of

---

the site. This intersection will be shared with properties north of the site on the west side of Federal Boulevard as well as properties on the east side of Federal Boulevard (a median break and northbound and southbound left-turn lanes have already been constructed along Federal Boulevard at this location). This signal should include a crosswalk on the south leg of the intersection and curb ramps to facilitate crossing of Federal Blvd. to/from sites uses and adjacent/nearby mixed use and transit services (both the existing bus and commuter rail services and future BRT corridor services).

2. Extend the existing northbound left-turn storage at the north access (new signal). The existing raised median design on Federal Blvd. provides for approximately 280' of storage plus a 175' taper. This available storage length is anticipated to be exceeded in the Year 2045 PM peak hour (projected 95<sup>th</sup>—percentile queue of 300') with the proposed lane repurposing of the Federal BRT project. It is recommended that the existing median planter be removed and the storage length extended to the south to become a shared back-to-back taper with the existing southbound left-turn lane approaching 60<sup>th</sup> Avenue. This would effectively increase the storage length by +140' and would maintain a 175' taper, providing a maximum storage length of 420', plus taper.

**Table 3a. Trip Generation Estimate**

| Land Use                                                    | Size  | Unit           | Non-Auto<br>Reduction | Average<br>Weekday Trips |       | Weekday AM<br>Peak Hour Trips |       |     |     | Weekday PM<br>Peak Hour Trips |       |     |     |
|-------------------------------------------------------------|-------|----------------|-----------------------|--------------------------|-------|-------------------------------|-------|-----|-----|-------------------------------|-------|-----|-----|
|                                                             |       |                |                       | Rate                     | Total | Rate                          | Total | In  | Out | Rate                          | Total | In  | Out |
|                                                             |       |                |                       |                          |       |                               |       |     |     |                               |       |     |     |
| PA - 1                                                      |       |                |                       |                          |       |                               |       |     |     |                               |       |     |     |
| #221 Multifamily Housing (Mid-Rise) (close to rail transit) | 269   | Dwelling Units | 0%                    | 4.75                     | 1278  | 0.32                          | 86    | 31  | 55  | 0.29                          | 78    | 51  | 27  |
| #936 Coffee/Donut Shop without Drive-Through*               | 1.000 | 1,000 SF       | 10%                   | 317.47                   | 286   | 93.08                         | 84    | 43  | 41  | 32.29                         | 29    | 15  | 14  |
| #930 Fast Casual Restaurant                                 | 6.000 | 1,000 SF       | 10%                   | 97.14                    | 525   | 2.07                          | 11    | 7   | 4   | 12.55                         | 68    | 37  | 31  |
| #814 Variety Store (General Retail)                         | 9.000 | 1,000 SF       | 10%                   | 63.66                    | 516   | 3.04                          | 25    | 14  | 11  | 6.70                          | 54    | 28  | 26  |
| #712 Small Office Building                                  | 3.027 | 1,000 SF       | 10%                   | 14.39                    | 39    | 1.67                          | 5     | 4   | 1   | 2.16                          | 6     | 2   | 4   |
| PA - 2                                                      |       |                |                       |                          |       |                               |       |     |     |                               |       |     |     |
| #221 Multifamily Housing (Mid-Rise) (close to rail transit) | 174   | Dwelling Units | 0%                    | 4.75                     | 827   | 0.32                          | 56    | 20  | 36  | 0.29                          | 50    | 33  | 17  |
| #930 Fast Casual Restaurant                                 | 3.000 | 1,000 SF       | 10%                   | 97.14                    | 262   | 2.07                          | 6     | 4   | 2   | 12.55                         | 34    | 19  | 15  |
| #814 Variety Store (General Retail)                         | 4.951 | 1,000 SF       | 10%                   | 63.66                    | 284   | 3.04                          | 14    | 8   | 6   | 6.70                          | 30    | 15  | 15  |
| PA - 3                                                      |       |                |                       |                          |       |                               |       |     |     |                               |       |     |     |
| #221 Multifamily Housing (Mid-Rise) (close to rail transit) | 98    | Dwelling Units | 0%                    | 4.75                     | 466   | 0.32                          | 31    | 11  | 20  | 0.29                          | 28    | 18  | 10  |
| PA - 5                                                      |       |                |                       |                          |       |                               |       |     |     |                               |       |     |     |
| #221 Multifamily Housing (Mid-Rise) (close to rail transit) | 255   | Dwelling Units | 0%                    | 4.75                     | 1211  | 0.32                          | 82    | 30  | 52  | 0.29                          | 74    | 48  | 26  |
| PA - 6                                                      |       |                |                       |                          |       |                               |       |     |     |                               |       |     |     |
| #220 Multifamily Housing (Low-Rise) (close to rail transit) | 34    | Dwelling Units | 0%                    | 4.72                     | 160   | 0.38                          | 13    | 4   | 9   | 0.61                          | 21    | 13  | 8   |
| PA - 7                                                      |       |                |                       |                          |       |                               |       |     |     |                               |       |     |     |
| #220 Multifamily Housing (Low-Rise) (close to rail transit) | 56    | Dwelling Units | 0%                    | 4.72                     | 264   | 0.38                          | 21    | 6   | 15  | 0.61                          | 34    | 20  | 14  |
| PA - 8                                                      |       |                |                       |                          |       |                               |       |     |     |                               |       |     |     |
| #220 Multifamily Housing (Low-Rise) (close to rail transit) | 43    | Dwelling Units | 0%                    | 4.72                     | 203   | 0.38                          | 16    | 5   | 11  | 0.61                          | 26    | 16  | 10  |
| PA - 9                                                      |       |                |                       |                          |       |                               |       |     |     |                               |       |     |     |
| #220 Multifamily Housing (Low-Rise) (close to rail transit) | 8     | Dwelling Units | 0%                    | 4.72                     | 38    | 0.38                          | 3     | 1   | 2   | 0.61                          | 5     | 3   | 2   |
| Total                                                       |       |                |                       |                          | 6359  |                               | 453   | 188 | 265 |                               | 537   | 318 | 219 |

\* Since no ITE data is available for #936 daily rates, #933 (Fast Food without Drive-Through) was utilized for daily rate

**Table 3b. Trip Type Breakdown**

|                                                             | Trip Type % <sup>(1)</sup> |         | PRIMARY Trips |             |            |            |            |            | PASS-BY Trips |            |           |           |           |           |
|-------------------------------------------------------------|----------------------------|---------|---------------|-------------|------------|------------|------------|------------|---------------|------------|-----------|-----------|-----------|-----------|
| Land Use                                                    | Primary                    | Pass-By | Daily In      | Daily Out   | AM In      | AM Out     | PM In      | PM Out     | Daily In      | Daily Out  | AM In     | AM Out    | PM In     | PM Out    |
| <b>PA - 1</b>                                               |                            |         |               |             |            |            |            |            |               |            |           |           |           |           |
| #221 Multifamily Housing (Mid-Rise) (close to rail transit) | 100%                       | 0%      | 639           | 639         | 31         | 55         | 51         | 27         | 0             | 0          | 0         | 0         | 0         | 0         |
| #936 Coffee/Donut Shop without Drive-Through*               | 18%                        | 82%     | 26            | 26          | 8          | 7          | 3          | 3          | 117           | 117        | 35        | 34        | 12        | 11        |
| #930 Fast Casual Restaurant                                 | 57%                        | 43%     | 150           | 150         | 4          | 2          | 21         | 18         | 113           | 113        | 3         | 2         | 16        | 13        |
| #814 Variety Store (General Retail)                         | 66%                        | 34%     | 170           | 170         | 9          | 7          | 18         | 17         | 88            | 88         | 5         | 4         | 10        | 9         |
| #712 Small Office Building                                  | 100%                       | 0%      | 20            | 20          | 4          | 1          | 2          | 4          | 0             | 0          | 0         | 0         | 0         | 0         |
| <b>PA - 2</b>                                               |                            |         |               |             |            |            |            |            |               |            |           |           |           |           |
| #221 Multifamily Housing (Mid-Rise) (close to rail transit) | 100%                       | 0%      | 414           | 414         | 20         | 36         | 33         | 17         | 0             | 0          | 0         | 0         | 0         | 0         |
| #930 Fast Casual Restaurant                                 | 50%                        | 50%     | 66            | 66          | 2          | 1          | 10         | 8          | 66            | 66         | 2         | 1         | 10        | 8         |
| #814 Variety Store (General Retail)                         | 66%                        | 34%     | 94            | 94          | 5          | 4          | 10         | 10         | 48            | 48         | 3         | 2         | 5         | 5         |
| <b>PA - 3</b>                                               |                            |         |               |             |            |            |            |            |               |            |           |           |           |           |
| #221 Multifamily Housing (Mid-Rise) (close to rail transit) | 100%                       | 0%      | 233           | 233         | 11         | 20         | 18         | 10         | 0             | 0          | 0         | 0         | 0         | 0         |
| <b>PA - 5</b>                                               |                            |         |               |             |            |            |            |            |               |            |           |           |           |           |
| #221 Multifamily Housing (Mid-Rise) (close to rail transit) | 100%                       | 0%      | 606           | 606         | 30         | 52         | 48         | 26         | 0             | 0          | 0         | 0         | 0         | 0         |
| <b>PA - 6</b>                                               |                            |         |               |             |            |            |            |            |               |            |           |           |           |           |
| #220 Multifamily Housing (Low-Rise) (close to rail transit) | 100%                       | 0%      | 80            | 80          | 4          | 9          | 13         | 8          | 0             | 0          | 0         | 0         | 0         | 0         |
| <b>PA - 7</b>                                               |                            |         |               |             |            |            |            |            |               |            |           |           |           |           |
| #220 Multifamily Housing (Low-Rise) (close to rail transit) | 100%                       | 0%      | 132           | 132         | 6          | 15         | 20         | 14         | 0             | 0          | 0         | 0         | 0         | 0         |
| <b>PA - 8</b>                                               |                            |         |               |             |            |            |            |            |               |            |           |           |           |           |
| #220 Multifamily Housing (Low-Rise) (close to rail transit) | 100%                       | 0%      | 102           | 102         | 5          | 11         | 16         | 10         | 0             | 0          | 0         | 0         | 0         | 0         |
| <b>PA - 9</b>                                               |                            |         |               |             |            |            |            |            |               |            |           |           |           |           |
| #220 Multifamily Housing (Low-Rise) (close to rail transit) | 100%                       | 0%      | 19            | 19          | 1          | 2          | 3          | 2          | 0             | 0          | 0         | 0         | 0         | 0         |
| <b>TOTAL</b>                                                |                            |         | <b>2751</b>   | <b>2751</b> | <b>140</b> | <b>223</b> | <b>266</b> | <b>173</b> | <b>432</b>    | <b>432</b> | <b>48</b> | <b>42</b> | <b>52</b> | <b>46</b> |

Source: ITE Trip Generation Handbook.

<sup>(1)</sup> Supported by ITE average data for each land use or comparable land use. For Land Use #936, daily pass-by data for #937 Coffee/Donut Shop with Drive-Through Window was used. For Land Use #930, PM peak data for #932 High-Turnover (Sit-Down) Restaurant was used.











# KEY

→ LANE CONFIGURATION

XXXX DAILY TRAFFIC VOLUME

XX (XX) AM (PM) PEAK HOUR TRIP VOLUME



**FOX TUTTLE**

## CLEAR CREEK TRANSIT VILLAGE TRAFFIC ANALYSIS SITE GENERATED TRAFFIC VOLUMES

|           |       |                |     |      |          |          |     |          |   |
|-----------|-------|----------------|-----|------|----------|----------|-----|----------|---|
| Project # | 19036 | Original Scale | NTS | Date | 10/10/25 | Drawn by | EJG | Figure # | 7 |
|-----------|-------|----------------|-----|------|----------|----------|-----|----------|---|



## Conceptual Site Plan

# CLEAR CREEK TRANSIT VILLAGE

60TH AND FEDERAL  
DENVER, CO 80221


PROJ. NO. 25-01  
DRAWN: Author  
CHECKED: Checker  
APPROVED: Approver  
DATE: 03/18/26  
REVISIONS

ISSUED  
FOR: NOT FOR  
CONSTRUCTION  
© NEO STUDIO

SCALE: 1/32" = 1'-0"

SHEET TITLE:  
SITE PLAN SD

A0.00S



| PA | LAND USE              | UNIT COUNT | UNIT S.F. | TOTAL S.F. | BEDROOM COUNT | STREET PARKING | TOTAL PARKING | MIN. PARKING 1 SPACE/UNIT 2 SPACE/1000 RETAIL |
|----|-----------------------|------------|-----------|------------|---------------|----------------|---------------|-----------------------------------------------|
|    | 1 RETAIL              | 2          | 3029      | 6058       |               | 21             | 352           | 12.116                                        |
|    | APARTMENT-STUDIO      | 12         | 575       |            | 6900          | 12             |               | 12                                            |
|    | APARTMENT-ONE BD      | 68         | 698       |            | 47464         | 68             |               | 68                                            |
|    | APARTMENT-TWO BD      | 40         | 950       |            | 38000         | 80             |               | 40                                            |
|    | APARTMENT-TWO BD/FLAT | 0          | 983       |            | 0             | 0              |               | 0                                             |
|    | 1 TOWNHOME 2          | 8          | 950       |            | 7600          | 16             |               | 8                                             |
|    | 1 TOWNHOME 2.3        | 4          | 896       |            | 3584          | 8              |               | 4                                             |
|    | TOWNHOME 1            | 29         | 2100      |            | 60900         | 87             |               | 29                                            |
|    |                       | 161        |           | 6058       | 164448        | 271            | 21            | 352 173.116                                   |

|                       |     |      |      |       |     |    |    |         |
|-----------------------|-----|------|------|-------|-----|----|----|---------|
| 2 RETAIL              | 2   | 3029 | 6058 |       |     | 33 | 0  | 12.116  |
| APARTMENT-STUDIO      | 12  | 350  |      | 4200  | 12  |    |    | 12      |
| APARTMENT-ONE BD      | 48  | 698  |      | 33504 | 48  |    |    | 48      |
| APARTMENT-TWO BD      | 18  | 950  |      | 17100 | 36  |    |    | 18      |
| APARTMENT-TWO BD/FLAT | 0   | 983  |      | 0     | 0   |    |    | 0       |
| 1 TOWNHOME 2          | 10  | 950  |      | 9500  | 20  |    |    | 10      |
| TOWNHOME 2.3          | 0   | 690  |      | 0     | 0   |    |    | 0       |
| TOWNHOME 3            | 12  | 1739 |      | 20868 | 36  |    | 24 | 12      |
|                       | 100 |      | 6058 | 85172 | 152 | 33 | 24 | 112.116 |

|                  |    |      |      |       |     |    |    |        |
|------------------|----|------|------|-------|-----|----|----|--------|
| 3 RETAIL         | 2  | 3029 | 6058 |       |     | 37 | 0  | 12.116 |
| APARTMENT-STUDIO | 0  | 350  |      | 0     | 0   |    |    | 0      |
| APARTMENT-ONE BD | 48 | 698  |      | 33504 | 48  |    |    | 48     |
| APARTMENT-TWO BD | 16 | 950  |      | 15200 | 32  |    |    | 16     |
| 1 TOWNHOME 2     | 8  | 950  |      | 7600  | 16  |    | 0  | 8      |
| TOWNHOME 2.1     | 12 | 1835 |      | 22020 | 36  |    | 24 | 12     |
|                  | 84 |      | 6058 | 78324 | 132 | 37 | 24 | 96.116 |

|                       |     |      |      |        |     |    |    |         |
|-----------------------|-----|------|------|--------|-----|----|----|---------|
| 5 RETAIL              | 2   | 3029 | 6058 |        |     | 40 | 0  | 12.116  |
| APARTMENT-STUDIO      | 12  | 350  |      | 4200   | 12  |    |    | 12      |
| APARTMENT-ONE BD      | 48  | 698  |      | 33504  | 48  |    |    | 48      |
| APARTMENT-TWO BD/FLAT | 0   | 983  |      | 0      | 0   |    |    | 0       |
| APARTMENT-TWO BD      | 18  | 950  |      | 17100  | 36  |    |    | 18      |
| 1 TOWNHOME 2          | 10  | 950  |      | 9500   | 20  |    |    | 10      |
| TOWNHOME 3            | 23  | 1789 |      | 41147  | 69  |    | 46 | 23      |
|                       | 111 |      | 6058 | 105451 | 185 | 40 | 46 | 123.116 |

|        |     |             |                  |          |         |     |         |                  |
|--------|-----|-------------|------------------|----------|---------|-----|---------|------------------|
|        | 456 | 24232       | 433395           | 740      | 131     | 446 | 504.464 | PARKING REQUIRED |
| #UNITS |     | RETAIL S.F. | RESIDENTIAL S.F. | BEDROOMS | PARKING | 577 | 1.27    | SPACES PER UNIT  |



## Trip Generation Calculations

### PA-1 - PA-5 Daily Trip Generation Calculations

| TRIP GENERATION CHARACTERISTICS         |             |       |          |                | DIRECTIONAL DISTRIBUTION |           | BASELINE TRIPS |       |       | VEHICLE TRIPS |             |               | INTERNAL CAPTURE      |          | EXTERNAL VEHICLE TRIPS |              |                |
|-----------------------------------------|-------------|-------|----------|----------------|--------------------------|-----------|----------------|-------|-------|---------------|-------------|---------------|-----------------------|----------|------------------------|--------------|----------------|
| Land Use + Code                         | Source      | Scale | ITE Unit | Equation/Rate  | Entering %               | Exiting % | In             | Out   | Total | Vehicle In    | Vehicle Out | Vehicle Total | Internal Capture Rate | IC Trips | External In            | External Out | External Total |
| 1 (215) Single-Family Attached Housing  | ITE 12th Ed | 41    | DU       | $T = 6.57(X)$  | 50%                      | 50%       | 135            | 134   | 269   | 135           | 134         | 269           | 10.3%                 | 28       | 118                    | 123          | 241            |
| 2 (221) Multifamily Housing (Mid-Rise)  | ITE 12th Ed | 120   | DU       | $T = 4.75(X)$  | 50%                      | 50%       | 285            | 285   | 570   | 285           | 285         | 570           | 10.3%                 | 59       | 250                    | 261          | 511            |
| 3 (822) Strip Retail Plaza (<40k)       | ITE 12th Ed | 6.1   | LKSF     | $T = 54.45(X)$ | 50%                      | 50%       | 166            | 166   | 332   | 166           | 166         | 332           | 16.7%                 | 57       | 143                    | 132          | 275            |
| 4 (215) Single-Family Attached Housing  | ITE 12th Ed | 22    | DU       | $T = 6.57(X)$  | 50%                      | 50%       | 73             | 72    | 145   | 73            | 72          | 145           | 10.3%                 | 15       | 64                     | 66           | 130            |
| 5 (221) Multifamily Housing (Mid-Rise)  | ITE 12th Ed | 78    | DU       | $T = 4.75(X)$  | 50%                      | 50%       | 186            | 185   | 371   | 186           | 185         | 371           | 10.3%                 | 39       | 163                    | 169          | 332            |
| 6 (822) Strip Retail Plaza (<40k)       | ITE 12th Ed | 6.1   | LKSF     | $T = 54.45(X)$ | 50%                      | 50%       | 166            | 166   | 332   | 166           | 166         | 332           | 16.7%                 | 57       | 143                    | 132          | 275            |
| 7 (215) Single-Family Attached Housing  | ITE 12th Ed | 20    | DU       | $T = 6.57(X)$  | 50%                      | 50%       | 66             | 65    | 131   | 66            | 65          | 131           | 10.3%                 | 13       | 58                     | 60           | 118            |
| 8 (221) Multifamily Housing (Mid-Rise)  | ITE 12th Ed | 64    | DU       | $T = 4.75(X)$  | 50%                      | 50%       | 152            | 152   | 304   | 152           | 152         | 304           | 10.3%                 | 32       | 133                    | 139          | 272            |
| 9 (822) Strip Retail Plaza (<40k)       | ITE 12th Ed | 6.1   | LKSF     | $T = 54.45(X)$ | 50%                      | 50%       | 166            | 166   | 332   | 166           | 166         | 332           | 16.7%                 | 57       | 143                    | 132          | 275            |
| 10 (822) Strip Retail Plaza (<40k)      | ITE 12th Ed | 2.6   | LKSF     | $T = 54.45(X)$ | 50%                      | 50%       | 71             | 71    | 142   | 71            | 71          | 142           | 16.7%                 | 24       | 61                     | 57           | 118            |
| 11 (215) Single-Family Attached Housing | ITE 12th Ed | 33    | DU       | $T = 6.57(X)$  | 50%                      | 50%       | 109            | 108   | 217   | 109           | 108         | 217           | 10.3%                 | 22       | 96                     | 99           | 195            |
| 12 (221) Multifamily Housing (Mid-Rise) | ITE 12th Ed | 78    | DU       | $T = 4.75(X)$  | 50%                      | 50%       | 186            | 185   | 371   | 186           | 185         | 371           | 10.3%                 | 39       | 163                    | 169          | 332            |
| 13 (822) Strip Retail Plaza (<40k)      | ITE 12th Ed | 6.1   | LKSF     | $T = 54.45(X)$ | 50%                      | 50%       | 166            | 166   | 332   | 166           | 166         | 332           | 16.7%                 | 57       | 143                    | 132          | 275            |
| <b>Total:</b>                           |             |       |          |                |                          |           | 1,927          | 1,921 | 3,848 | 1,927         | 1,921       | 3,848         | 12.8%                 | 499      | 1,678                  | 1,671        | 3,349          |

### PA-1 - PA-5 AM Peak Hour Trip Generation Calculations

| TRIP GENERATION CHARACTERISTICS         |             |       |          |                      | DIRECTIONAL DISTRIBUTION |           | BASELINE TRIPS |     |       | VEHICLE TRIPS |             |               | INTERNAL CAPTURE      |          | EXTERNAL VEHICLE TRIPS |              |                |
|-----------------------------------------|-------------|-------|----------|----------------------|--------------------------|-----------|----------------|-----|-------|---------------|-------------|---------------|-----------------------|----------|------------------------|--------------|----------------|
| Land Use + Code                         | Source      | Scale | ITE Unit | Equation/Rate        | Entering %               | Exiting % | In             | Out | Total | Vehicle In    | Vehicle Out | Vehicle Total | Internal Capture Rate | IC Trips | External In            | External Out | External Total |
| 1 (215) Single-Family Attached Housing  | ITE 12th Ed | 41    | DU       | $T = 0.47(X)$        | 25%                      | 75%       | 5              | 14  | 19    | 5             | 14          | 19            | 1.2%                  | 0        | 5                      | 14           | 19             |
| 2 (221) Multifamily Housing (Mid-Rise)  | ITE 12th Ed | 120   | DU       | $T = 0.31(X) + 1.06$ | 39%                      | 61%       | 15             | 23  | 38    | 15            | 23          | 38            | 1.2%                  | 2        | 14                     | 22           | 36             |
| 3 (822) Strip Retail Plaza (<40k)       | ITE 12th Ed | 6.1   | LKSF     | $T = 3.93(X)$        | 55%                      | 45%       | 13             | 11  | 24    | 13            | 11          | 24            | 1.9%                  | 2        | 12                     | 10           | 22             |
| 4 (215) Single-Family Attached Housing  | ITE 12th Ed | 22    | DU       | $T = 0.47(X)$        | 25%                      | 75%       | 3              | 7   | 10    | 3             | 7           | 10            | 1.2%                  | 0        | 3                      | 7            | 10             |
| 5 (221) Multifamily Housing (Mid-Rise)  | ITE 12th Ed | 78    | DU       | $T = 0.31(X) + 1.06$ | 39%                      | 61%       | 10             | 15  | 25    | 10            | 15          | 25            | 1.2%                  | 0        | 10                     | 15           | 25             |
| 6 (822) Strip Retail Plaza (<40k)       | ITE 12th Ed | 6.1   | LKSF     | $T = 3.93(X)$        | 55%                      | 45%       | 13             | 11  | 24    | 13            | 11          | 24            | 1.9%                  | 2        | 12                     | 10           | 22             |
| 7 (215) Single-Family Attached Housing  | ITE 12th Ed | 20    | DU       | $T = 0.47(X)$        | 25%                      | 75%       | 2              | 7   | 9     | 2             | 7           | 9             | 1.2%                  | 0        | 2                      | 7            | 9              |
| 8 (221) Multifamily Housing (Mid-Rise)  | ITE 12th Ed | 64    | DU       | $T = 0.31(X) + 1.06$ | 39%                      | 61%       | 8              | 13  | 21    | 8             | 13          | 21            | 1.2%                  | 0        | 8                      | 13           | 21             |
| 9 (822) Strip Retail Plaza (<40k)       | ITE 12th Ed | 6.1   | LKSF     | $T = 3.93(X)$        | 55%                      | 45%       | 13             | 11  | 24    | 13            | 11          | 24            | 1.9%                  | 2        | 12                     | 10           | 22             |
| 10 (822) Strip Retail Plaza (<40k)      | ITE 12th Ed | 2.6   | LKSF     | $T = 3.93(X)$        | 55%                      | 45%       | 6              | 4   | 10    | 6             | 4           | 10            | 1.9%                  | 0        | 6                      | 4            | 10             |
| 11 (215) Single-Family Attached Housing | ITE 12th Ed | 33    | DU       | $T = 0.47(X)$        | 25%                      | 75%       | 4              | 12  | 16    | 4             | 12          | 16            | 1.2%                  | 0        | 4                      | 12           | 16             |
| 12 (221) Multifamily Housing (Mid-Rise) | ITE 12th Ed | 78    | DU       | $T = 0.31(X) + 1.06$ | 39%                      | 61%       | 10             | 15  | 25    | 10            | 15          | 25            | 1.2%                  | 0        | 10                     | 15           | 25             |
| 13 (822) Strip Retail Plaza (<40k)      | ITE 12th Ed | 6.1   | LKSF     | $T = 3.93(X)$        | 55%                      | 45%       | 13             | 11  | 24    | 13            | 11          | 24            | 1.9%                  | 2        | 12                     | 10           | 22             |
| <b>Total:</b>                           |             |       |          |                      |                          |           | 115            | 154 | 269   | 115           | 154         | 269           | 1.5%                  | 10       | 110                    | 149          | 259            |

### PA-1 - PA-5 PM Peak Hour Trip Generation Calculations

| TRIP GENERATION CHARACTERISTICS         |             |       |          |                               | DIRECTIONAL DISTRIBUTION |           | BASELINE TRIPS |     |       | VEHICLE TRIPS |             |               | INTERNAL CAPTURE      |          | EXTERNAL VEHICLE TRIPS |              |                |
|-----------------------------------------|-------------|-------|----------|-------------------------------|--------------------------|-----------|----------------|-----|-------|---------------|-------------|---------------|-----------------------|----------|------------------------|--------------|----------------|
| Land Use + Code                         | Source      | Scale | ITE Unit | Equation/Rate                 | Entering %               | Exiting % | In             | Out | Total | Vehicle In    | Vehicle Out | Vehicle Total | Internal Capture Rate | IC Trips | External In            | External Out | External Total |
| 1 (215) Single-Family Attached Housing  | ITE 12th Ed | 41    | DU       | $T = 0.51(X)$                 | 57%                      | 43%       | 12             | 9   | 21    | 12            | 9           | 21            | 28.3%                 | 6        | 8                      | 7            | 15             |
| 2 (221) Multifamily Housing (Mid-Rise)  | ITE 12th Ed | 120   | DU       | $T = 0.29(X)$                 | 65%                      | 35%       | 23             | 12  | 35    | 23            | 12          | 35            | 28.3%                 | 10       | 16                     | 9            | 25             |
| 3 (822) Strip Retail Plaza (<40k)       | ITE 12th Ed | 6.1   | LKSF     | $\ln(T) = 0.68 \ln(X) + 2.77$ | 50%                      | 50%       | 28             | 27  | 55    | 28            | 27          | 55            | 17.9%                 | 10       | 25                     | 20           | 45             |
| 4 (215) Single-Family Attached Housing  | ITE 12th Ed | 22    | DU       | $T = 0.51(X)$                 | 57%                      | 43%       | 6              | 5   | 11    | 6             | 5           | 11            | 28.3%                 | 3        | 4                      | 4            | 8              |
| 5 (221) Multifamily Housing (Mid-Rise)  | ITE 12th Ed | 78    | DU       | $T = 0.29(X)$                 | 65%                      | 35%       | 15             | 8   | 23    | 15            | 8           | 23            | 28.3%                 | 7        | 10                     | 6            | 16             |
| 6 (822) Strip Retail Plaza (<40k)       | ITE 12th Ed | 6.1   | LKSF     | $\ln(T) = 0.68 \ln(X) + 2.77$ | 50%                      | 50%       | 28             | 27  | 55    | 28            | 27          | 55            | 17.9%                 | 10       | 25                     | 20           | 45             |
| 7 (215) Single-Family Attached Housing  | ITE 12th Ed | 20    | DU       | $T = 0.51(X)$                 | 57%                      | 43%       | 6              | 4   | 10    | 6             | 4           | 10            | 28.3%                 | 3        | 4                      | 3            | 7              |
| 8 (221) Multifamily Housing (Mid-Rise)  | ITE 12th Ed | 64    | DU       | $T = 0.29(X)$                 | 65%                      | 35%       | 12             | 7   | 19    | 12            | 7           | 19            | 28.3%                 | 6        | 8                      | 5            | 13             |
| 9 (822) Strip Retail Plaza (<40k)       | ITE 12th Ed | 6.1   | LKSF     | $\ln(T) = 0.68 \ln(X) + 2.77$ | 50%                      | 50%       | 28             | 27  | 55    | 28            | 27          | 55            | 17.9%                 | 10       | 25                     | 20           | 45             |
| 10 (822) Strip Retail Plaza (<40k)      | ITE 12th Ed | 2.6   | LKSF     | $\ln(T) = 0.68 \ln(X) + 2.77$ | 50%                      | 50%       | 16             | 15  | 31    | 16            | 15          | 31            | 17.9%                 | 5        | 15                     | 11           | 26             |
| 11 (215) Single-Family Attached Housing | ITE 12th Ed | 33    | DU       | $T = 0.51(X)$                 | 57%                      | 43%       | 10             | 7   | 17    | 10            | 7           | 17            | 28.3%                 | 5        | 7                      | 5            | 12             |
| 12 (221) Multifamily Housing (Mid-Rise) | ITE 12th Ed | 78    | DU       | $T = 0.29(X)$                 | 65%                      | 35%       | 15             | 8   | 23    | 15            | 8           | 23            | 28.3%                 | 7        | 10                     | 6            | 16             |
| 13 (822) Strip Retail Plaza (<40k)      | ITE 12th Ed | 6.1   | LKSF     | $\ln(T) = 0.68 \ln(X) + 2.77$ | 50%                      | 50%       | 28             | 27  | 55    | 28            | 27          | 55            | 17.9%                 | 10       | 25                     | 20           | 45             |
| <b>Total:</b>                           |             |       |          |                               |                          |           | 227            | 183 | 410   | 227           | 183         | 410           | 22.0%                 | 92       | 182                    | 136          | 318            |

# Parcel Map Check Report

**Client:**

Client

Client Company

Address 1

Date: 8/31/2026 4:03:09 PM

**Prepared by:**

Preparer

Your Company Name

123 Main Street

Parcel Name: BNDY - BLOCK 2

**Description:**

Process segment order counterclockwise: False

Enable mapcheck across chord: False

North: 465,272.1556'

East: 633,981.3838'

**Segment# 1: Line**

Course: S75°00'00"W

Length: 81.09'

North: 465,251.1679'

East: 633,903.0569'

**Segment# 2: Line**

Course: N15°00'00"W

Length: 17.97'

North: 465,268.5256'

East: 633,898.4059'

**Segment# 3: Line**

Course: S75°00'00"W

Length: 81.78'

North: 465,247.3594'

East: 633,819.4125'

**Segment# 4: Line**

Course: S90°00'00"W

Length: 94.84'

North: 465,247.3594'

East: 633,724.5725'

**Segment# 5: Line**

Course: N0°00'00"E

Length: 267.15'

North: 465,514.5094'

East: 633,724.5725'

**Segment# 6: Curve**

Length: 4.71'

Radius: 3.00'

Delta: 90°00'00"

Tangent: 3.00'

Chord: 4.24'

Course: N45°00'00"E

Course In: N90°00'00"E

Course Out: N0°00'00"E

RP North: 465,514.5094'

East: 633,727.5725'

End North: 465,517.5094'

East: 633,727.5725'

**Segment# 7: Line**

Course: N90°00'00"E

Length: 234.30'

North: 465,517.5094'

East: 633,961.8725'

Segment# 8: Line

Course: S45°00'00"E

Length: 20.80'

North: 465,502.8016'

East: 633,976.5803'

Segment# 9: Line

Course: S0°00'00"E

Length: 147.60'

North: 465,355.2016'

East: 633,976.5803'

Segment# 10: Line

Course: S89°59'25"E

Length: 16.50'

North: 465,355.1988'

East: 633,993.0803'

Segment# 11: Line

Course: S0°00'03"E

Length: 68.69'

North: 465,286.5088'

East: 633,993.0813'

Segment# 12: Line

Course: S39°12'04"W

Length: 18.50'

North: 465,272.1725'

East: 633,981.3885'

Perimeter: 1,053.93'

Area: 67,357.94755Sq.Ft.

Error Closure: 0.0176

Course: N15°25'53"E

Error North : 0.01696

East: 0.00468

Precision 1: 59,882.39

---

Parcel Name: LOTS F3 - LOT 201

Description:

Process segment order counterclockwise: False

Enable mapcheck across chord: False

North:465,326.5578'

East:633,749.5758'

Segment# 1: Line

Course: N90°00'00"W

Length: 25.00'

North: 465,326.5578'

East: 633,724.5758'

Segment# 2: Line

Course: N0°00'00"E

Length: 65.38'

North: 465,391.9378'

East: 633,724.5758'

Segment# 3: Line

Course: N90°00'00"E

Length: 25.00'

North: 465,391.9378'

East: 633,749.5758'

Segment# 4: Line

Course: S0°00'00"E

Length: 65.38'

North: 465,326.5578'

East: 633,749.5758'

Perimeter: 180.76'

Area: 1,634.49050Sq.Ft.

Error Closure: 0.0000

Course: N0°00'00"E

Error North : 0.00000

East: 0.00000

Precision 1: 180,760,000.00

---

Parcel Name: LOTS F3 - LOT 202

Description:

Process segment order counterclockwise: False

Enable mapcheck across chord: False

North:465,326.5578'

East:633,769.0758'

Segment# 1: Line

Course: N90°00'00"W

Length: 19.50'

North: 465,326.5578'

East: 633,749.5758'

Segment# 2: Line

Course: N0°00'00"E

Length: 65.38'

North: 465,391.9378'

East: 633,749.5758'

Segment# 3: Line

Course: N90°00'00"E

Length: 19.50'

North: 465,391.9378'

East: 633,769.0758'

Segment# 4: Line

Course: S0°00'00"E

Length: 65.38'

North: 465,326.5578'

East: 633,769.0758'

Perimeter: 169.76'

Area: 1,274.90259Sq.Ft.

Error Closure: 0.0000

Course: N0°00'00"E

Error North : 0.00000

East: 0.00000

Precision 1: 169,760,000.00

---

Parcel Name: LOTS F3 - LOT 203

Description:

Process segment order counterclockwise: False

Enable mapcheck across chord: False

North:465,326.5578'

East:633,788.5758'

## Segment# 1: Line

Course: N90°00'00"W

Length: 19.50'

North: 465,326.5578'

East: 633,769.0758'

## Segment# 2: Line

Course: N0°00'00"E

Length: 65.38'

North: 465,391.9378'

East: 633,769.0758'

## Segment# 3: Line

Course: N90°00'00"E

Length: 19.50'

North: 465,391.9378'

East: 633,788.5758'

## Segment# 4: Line

Course: S0°00'00"E

Length: 65.38'

North: 465,326.5578'

East: 633,788.5758'

Perimeter: 169.76'

Area: 1,274.90259Sq.Ft.

Error Closure: 0.0000

Course: N0°00'00"E

Error North : 0.00000

East: 0.00000

Precision 1: 169,760,000.00

---

Parcel Name: LOTS F3 - LOT 204

## Description:

Process segment order counterclockwise: False

Enable mapcheck across chord: False

North:465,391.9374'

East:633,808.0758'

## Segment# 1: Line

Course: S0°00'00"E

Length: 65.38'

North: 465,326.5574'

East: 633,808.0758'

## Segment# 2: Line

Course: N90°00'00"W

Length: 19.50'

North: 465,326.5574'

East: 633,788.5758'

## Segment# 3: Line

Course: N0°00'00"E

Length: 65.38'

North: 465,391.9374'

East: 633,788.5758'

## Segment# 4: Line

Course: N90°00'00"E

Length: 19.50'

North: 465,391.9374'

East: 633,808.0758'

Perimeter: 169.76'

Area: 1,274.90259Sq.Ft.

Error Closure: 0.0000

Course: N0°00'00"E

Error North : 0.00000

East: 0.00000

Precision 1: 169,760,000.00

---

Parcel Name: LOTS F3 - LOT 205

Description:

Process segment order counterclockwise: False

Enable mapcheck across chord: False

North:465,327.2900'

East:633,827.6688'

Segment# 1: Curve

Length: 4.71'

Radius: 15.00'

Delta: 17°58'33"

Tangent: 2.37'

Chord: 4.69'

Course: S81°00'43"W

Course In: N17°58'33"W

Course Out: S0°00'00"E

RP North: 465,341.5578'

East: 633,823.0395'

End North: 465,326.5578'

East: 633,823.0395'

Segment# 2: Line

Course: N90°00'00"W

Length: 14.96'

North: 465,326.5578'

East: 633,808.0795'

Segment# 3: Line

Course: N0°00'00"E

Length: 65.38'

North: 465,391.9378'

East: 633,808.0795'

Segment# 4: Line

Course: N90°00'00"E

Length: 21.50'

North: 465,391.9378'

East: 633,829.5795'

Segment# 5: Line

Course: S0°00'00"E

Length: 52.53'

North: 465,339.4078'

East: 633,829.5795'

Segment# 6: Line

Course: S22°30'00"E

Length: 10.98'

North: 465,329.2636'

East: 633,833.7814'

Segment# 7: Line

Course: S72°01'27"W

Length: 6.42'

North: 465,327.2823'

East: 633,827.6748'

Perimeter: 176.47'

Area: 1,426.81862Sq.Ft.

Error Closure: 0.0098

Course: S37°55'43"E

Error North : -0.00771

East: 0.00601

Precision 1: 18,008.16

---

Parcel Name: LOTS F3 - LOT 206

Description:

Process segment order counterclockwise: False

Enable mapcheck across chord: False

North:465,391.9374'

East:633,870.0788'

Segment# 1: Line

Course: S0°00'00"E

Length: 54.05'

North: 465,337.8874'

East: 633,870.0788'

Segment# 2: Line

Course: N90°00'00"W

Length: 4.22'

North: 465,337.8874'

East: 633,865.8588'

Segment# 3: Curve

Length: 10.98'

Radius: 35.00'

Delta: 17°58'33"

Tangent: 5.54'

Chord: 10.94'

Course: S81°00'43"W

Course In: S0°00'00"E

Course Out: N17°58'33"W

RP North: 465,302.8874'

East: 633,865.8588'

End North: 465,336.1789'

East: 633,855.0573'

Segment# 4: Line

Course: S72°01'27"W

Length: 2.31'

North: 465,335.4660'

East: 633,852.8600'

Segment# 5: Line

Course: N22°30'00"W

Length: 8.58'

North: 465,343.3929'

East: 633,849.5766'

Segment# 6: Line

Course: N0°00'00"E

Length: 48.55'

North: 465,391.9429'

East: 633,849.5766'

Segment# 7: Line

Course: N90°00'00"E

Length: 20.50'

North: 465,391.9429'

East: 633,870.0766'

Perimeter: 149.19'

Area: 1,113.70252Sq.Ft.

Error Closure: 0.0060

Course: N21°53'51"W

Error North : 0.00552

East: -0.00222

Precision 1: 24,865.00

---

Parcel Name: LOTS F3 - LOT 207

Description:

Process segment order counterclockwise: False

Enable mapcheck across chord: False

North:465,337.8862'

East:633,870.0788'

Segment# 1: Line

Course: N0°00'00"E

Length: 54.05'

North: 465,391.9362'

East: 633,870.0788'

Segment# 2: Line

Course: N90°00'00"E

Length: 19.50'

North: 465,391.9362'

East: 633,889.5788'

Segment# 3: Line

Course: S0°00'00"E

Length: 54.05'

North: 465,337.8862'

East: 633,889.5788'

Segment# 4: Line

Course: N90°00'00"W

Length: 19.50'

North: 465,337.8862'

East: 633,870.0788'

Perimeter: 147.10'

Area: 1,053.99806Sq.Ft.

Error Closure: 0.0000

Course: N0°00'00"E

Error North : 0.00000

East: 0.00000

Precision 1: 147,100,000.00

---

Parcel Name: LOTS F3 - LOT 208

Description:

Process segment order counterclockwise: False

Enable mapcheck across chord: False

North:465,337.8862'

East:633,889.5788'

Segment# 1: Line

Course: N0°00'00"E

Length: 54.05'

North: 465,391.9362'

East: 633,889.5788'

## Segment# 2: Line

Course: N90°00'00"E

Length: 19.50'

North: 465,391.9362'

East: 633,909.0788'

## Segment# 3: Line

Course: S0°00'00"E

Length: 54.05'

North: 465,337.8862'

East: 633,909.0788'

## Segment# 4: Line

Course: N90°00'00"W

Length: 19.50'

North: 465,337.8862'

East: 633,889.5788'

Perimeter: 147.10'

Area: 1,053.99806Sq.Ft.

Error Closure: 0.0000

Course: N0°00'00"E

Error North : 0.00000

East: 0.00000

Precision 1: 147,100,000.00

---

Parcel Name: LOTS F3 - LOT 209

Description:

Process segment order counterclockwise: False

Enable mapcheck across chord: False

North:465,337.8862'

East:633,909.0788'

## Segment# 1: Line

Course: N0°00'00"E

Length: 54.05'

North: 465,391.9362'

East: 633,909.0788'

## Segment# 2: Line

Course: N90°00'00"E

Length: 19.50'

North: 465,391.9362'

East: 633,928.5788'

## Segment# 3: Line

Course: S0°00'00"E

Length: 54.05'

North: 465,337.8862'

East: 633,928.5788'

## Segment# 4: Line

Course: N90°00'00"W

Length: 19.50'

North: 465,337.8862'

East: 633,909.0788'

Perimeter: 147.10'

Area: 1,053.99806Sq.Ft.

Error Closure: 0.0000

Course: N0°00'00"E

Error North : 0.00000

East: 0.00000

Precision 1: 147,100,000.00

---

Parcel Name: LOTS F3 - LOT 210

Description:

Process segment order counterclockwise: False

Enable mapcheck across chord: False

North:465,337.8862'

East:633,928.5788'

Segment# 1: Line

Course: N0°00'00"E

Length: 54.05'

North: 465,391.9362'

East: 633,928.5788'

Segment# 2: Line

Course: N90°00'00"E

Length: 19.50'

North: 465,391.9362'

East: 633,948.0788'

Segment# 3: Line

Course: S0°00'00"E

Length: 54.05'

North: 465,337.8862'

East: 633,948.0788'

Segment# 4: Line

Course: N90°00'00"W

Length: 19.50'

North: 465,337.8862'

East: 633,928.5788'

Perimeter: 147.10'

Area: 1,053.99806Sq.Ft.

Error Closure: 0.0000

Course: N0°00'00"E

Error North : 0.00000

East: 0.00000

Precision 1: 147,100,000.00

---

Parcel Name: LOTS F3 - LOT 211

Description:

Process segment order counterclockwise: False

Enable mapcheck across chord: False

North:465,337.8862'

East:633,948.0788'

Segment# 1: Line

Course: N0°00'00"E

Length: 54.05'

North: 465,391.9362'

East: 633,948.0788'

Segment# 2: Line

Course: N90°00'00"E

Length: 28.50'

North: 465,391.9362'

East: 633,976.5788'

## Segment# 3: Line

Course: S0°00'00"E

Length: 36.75'

North: 465,355.1862'

East: 633,976.5788'

## Segment# 4: Line

Course: S89°59'25"E

Length: 5.50'

North: 465,355.1853'

East: 633,982.0788'

## Segment# 5: Line

Course: S0°00'00"E

Length: 2.30'

North: 465,352.8853'

East: 633,982.0788'

## Segment# 6: Curve

Length: 23.56'

Radius: 15.00'

Delta: 90°00'00"

Tangent: 15.00'

Chord: 21.21'

Course: S45°00'00"W

Course In: N90°00'00"W

Course Out: S0°00'00"E

RP North: 465,352.8853'

East: 633,967.0788'

End North: 465,337.8853'

East: 633,967.0788'

## Segment# 7: Line

Course: N90°00'00"W

Length: 19.00'

North: 465,337.8853'

East: 633,948.0788'

Perimeter: 169.66'

Area: 1,587.26555Sq.Ft.

Error Closure: 0.0009

Course: S0°00'17"W

Error North : -0.00093

East: -0.00000

Precision 1: 188,511.11

---

Parcel Name: LOTS F3 - LOT 212

Description:

Process segment order counterclockwise: False

Enable mapcheck across chord: False

North: 465,502.7945'

East: 633,976.5774'

## Segment# 1: Line

Course: S0°00'00"E

Length: 86.86'

North: 465,415.9345'

East: 633,976.5774'

## Segment# 2: Line

Course: N90°00'00"W

Length: 252.00'

North: 465,415.9345'

East: 633,724.5774'

## Segment# 3: Line

Course: N0°00'00"E

Length: 98.56'

North: 465,514.4945'

East: 633,724.5774'

## Segment# 4: Curve

Length: 4.71'

Radius: 3.00'

Delta: 90°00'00"

Tangent: 3.00'

Chord: 4.24'

Course: N45°00'00"E

Course In: N90°00'00"E

Course Out: N0°00'00"E

RP North: 465,514.4945'

East: 633,727.5774'

End North: 465,517.4945'

East: 633,727.5774'

## Segment# 5: Line

Course: N90°00'00"E

Length: 234.30'

North: 465,517.4945'

East: 633,961.8774'

## Segment# 6: Line

Course: S45°00'00"E

Length: 20.80'

North: 465,502.7866'

East: 633,976.5852'

Perimeter: 697.23'

Area: 25,484.10781Sq.Ft.

Error Closure: 0.0111

Course: S45°00'00"E

Error North : -0.00782

East: 0.00782

Precision 1: 62,813.51

---

Parcel Name: LOTS F3 - LOT 213

Description:

Process segment order counterclockwise: False

Enable mapcheck across chord: False

North:465,306.5578'

East:633,752.5758'

## Segment# 1: Line

Course: S0°00'00"E

Length: 59.20'

North: 465,247.3578'

East: 633,752.5758'

## Segment# 2: Line

Course: S90°00'00"W

Length: 28.00'

North: 465,247.3578'

East: 633,724.5758'

## Segment# 3: Line

Course: N0°00'00"E

Length: 59.20'

North: 465,306.5578'

East: 633,724.5758'

Segment# 4: Line

Course: N90°00'00"E

Length: 28.00'

North: 465,306.5578'

East: 633,752.5758'

Perimeter: 174.41'

Area: 1,657.67876Sq.Ft.

Error Closure: 0.0000

Course: N0°00'00"E

Error North : 0.00000

East: 0.00000

Precision 1: 174,400,000.00

---

Parcel Name: LOTS F3 - LOT 214

Description:

Process segment order counterclockwise: False

Enable mapcheck across chord: False

North:465,247.3550'

East:633,752.5758'

Segment# 1: Line

Course: N0°00'00"E

Length: 59.20'

North: 465,306.5550'

East: 633,752.5758'

Segment# 2: Line

Course: N90°00'00"E

Length: 19.50'

North: 465,306.5550'

East: 633,772.0758'

Segment# 3: Line

Course: S0°00'00"E

Length: 59.20'

North: 465,247.3550'

East: 633,772.0758'

Segment# 4: Line

Course: S90°00'00"W

Length: 19.50'

North: 465,247.3550'

East: 633,752.5758'

Perimeter: 157.41'

Area: 1,154.45485Sq.Ft.

Error Closure: 0.0000

Course: N0°00'00"E

Error North : 0.00000

East: 0.00000

Precision 1: 157,400,000.00

---

Parcel Name: LOTS F3 - LOT 215

Description:

Process segment order counterclockwise: False

Enable mapcheck across chord: False

North:465,306.5578'

East:633,772.0758'

## Segment# 1: Line

Course: N90°00'00"E

Length: 19.50'

North: 465,306.5578'

East: 633,791.5758'

## Segment# 2: Line

Course: S0°00'00"E

Length: 59.20'

North: 465,247.3578'

East: 633,791.5758'

## Segment# 3: Line

Course: S90°00'00"W

Length: 19.50'

North: 465,247.3578'

East: 633,772.0758'

## Segment# 4: Line

Course: N0°00'00"E

Length: 59.20'

North: 465,306.5578'

East: 633,772.0758'

Perimeter: 157.41'

Area: 1,154.45485Sq.Ft.

Error Closure: 0.0000

Course: N0°00'00"E

Error North : 0.00000

East: 0.00000

Precision 1: 157,400,000.00

---

Parcel Name: LOTS F3 - LOT 216

## Description:

Process segment order counterclockwise: False

Enable mapcheck across chord: False

North:465,306.5578'

East:633,791.5758'

## Segment# 1: Line

Course: N90°00'00"E

Length: 19.50'

North: 465,306.5578'

East: 633,811.0758'

## Segment# 2: Line

Course: S0°00'00"E

Length: 59.20'

North: 465,247.3578'

East: 633,811.0758'

## Segment# 3: Line

Course: S90°00'00"W

Length: 19.50'

North: 465,247.3578'

East: 633,791.5758'

## Segment# 4: Line

Course: N0°00'00"E

Length: 59.20'

North: 465,306.5578'

East: 633,791.5758'

Perimeter: 157.41'

Area: 1,154.45485Sq.Ft.

Error Closure: 0.0000

Course: N0°00'00"E

Error North : 0.00000

East: 0.00000

Precision 1: 157,400,000.00

---

Parcel Name: LOTS F3 - LOT 217

Description:

Process segment order counterclockwise: False

Enable mapcheck across chord: False

North:465,250.3464'

East:633,830.5758'

Segment# 1: Line

Course: S75°00'00"W

Length: 11.56'

North: 465,247.3545'

East: 633,819.4097'

Segment# 2: Line

Course: S90°00'00"W

Length: 8.34'

North: 465,247.3545'

East: 633,811.0697'

Segment# 3: Line

Course: N0°00'00"E

Length: 59.20'

North: 465,306.5545'

East: 633,811.0697'

Segment# 4: Line

Course: N90°00'00"E

Length: 11.96'

North: 465,306.5545'

East: 633,823.0297'

Segment# 5: Curve

Length: 7.60'

Radius: 35.00'

Delta: 12°26'04"

Tangent: 3.81'

Chord: 7.58'

Course: N83°46'58"E

Course In: N0°00'00"E

Course Out: S12°26'04"E

RP North: 465,341.5545'

East: 633,823.0297'

End North: 465,307.3755'

East: 633,830.5660'

Segment# 6: Line

Course: S0°00'00"E

Length: 57.03'

North: 465,250.3455'

East: 633,830.5660'

Perimeter: 155.69'

Area: 1,139.80838Sq.Ft.

Error Closure: 0.0099

Course: S84°27'09"W

Error North : -0.00095

East: -0.00982

Precision 1: 15,726.26

---

Parcel Name: LOTS F3 - LOT 218

Description:

Process segment order counterclockwise: False

Enable mapcheck across chord: False

North: 465,257.1791'

East: 633,856.0758'

Segment# 1: Line

Course: S75°00'00"W

Length: 26.40'

North: 465,250.3463'

East: 633,830.5753'

Segment# 2: Line

Course: N0°00'00"E

Length: 57.03'

North: 465,307.3763'

East: 633,830.5753'

Segment# 3: Curve

Length: 3.39'

Radius: 35.00'

Delta: 5°32'29"

Tangent: 1.69'

Chord: 3.38'

Course: N74°47'41"E

Course In: N12°26'04"W

Course Out: S17°58'33"E

RP North: 465,341.5553'

East: 633,823.0391'

End North: 465,308.2638'

East: 633,833.8406'

Segment# 4: Line

Course: N72°01'27"E

Length: 23.38'

North: 465,315.4792'

East: 633,856.0794'

Segment# 5: Line

Course: S0°00'00"E

Length: 58.30'

North: 465,257.1792'

East: 633,856.0794'

Perimeter: 168.49'

Area: 1,468.49852Sq.Ft.

Error Closure: 0.0036

Course: N88°39'42"E

Error North : 0.00008

East: 0.00357

Precision 1: 46,805.56

---

Parcel Name: LOTS F3 - LOT 219

Description:

Process segment order counterclockwise: False

Enable mapcheck across chord: False

North:465,264.0129'

East:633,881.5798'

## Segment# 1: Line

Course: S75°00'00"W

Length: 26.40'

North: 465,257.1801'

East: 633,856.0793'

## Segment# 2: Line

Course: N0°00'00"E

Length: 58.30'

North: 465,315.4801'

East: 633,856.0793'

## Segment# 3: Line

Course: N72°01'27"E

Length: 5.42'

North: 465,317.1528'

East: 633,861.2348'

## Segment# 4: Curve

Length: 4.71'

Radius: 15.00'

Delta: 17°58'33"

Tangent: 2.37'

Chord: 4.69'

Course: N81°00'43"E

Course In: S17°58'33"E

Course Out: N0°00'00"E

RP North: 465,302.8850'

East: 633,865.8640'

End North: 465,317.8850'

East: 633,865.8640'

## Segment# 5: Line

Course: N90°00'00"E

Length: 15.72'

North: 465,317.8850'

East: 633,881.5840'

## Segment# 6: Line

Course: S0°00'00"E

Length: 53.87'

North: 465,264.0150'

East: 633,881.5840'

Perimeter: 164.42'

Area: 1,451.91496Sq.Ft.

Error Closure: 0.0047

Course: N63°52'33"E

Error North : 0.00207

East: 0.00423

Precision 1: 34,982.98

---

Parcel Name: LOTS F3 - LOT 220

Description:

Process segment order counterclockwise: False

Enable mapcheck across chord: False

North:465,268.5207'

East:633,898.4031'

## Segment# 1: Line

Course: S75°00'00"W

Length: 17.42'

North: 465,264.0121'

East: 633,881.5767'

## Segment# 2: Line

Course: N0°00'00"E

Length: 53.87'

North: 465,317.8821'

East: 633,881.5767'

## Segment# 3: Line

Course: N90°00'00"E

Length: 19.50'

North: 465,317.8821'

East: 633,901.0767'

## Segment# 4: Line

Course: S0°00'00"E

Length: 59.35'

North: 465,258.5321'

East: 633,901.0767'

## Segment# 5: Line

Course: N15°00'00"W

Length: 10.34'

North: 465,268.5198'

East: 633,898.4005'

Perimeter: 160.49'

Area: 1,013.91422Sq.Ft.

Error Closure: 0.0028

Course: S69°57'22"W

Error North : -0.00095

East: -0.00262

Precision 1: 57,314.29

---

Parcel Name: LOTS F3 - LOT 221

Description:

Process segment order counterclockwise: False

Enable mapcheck across chord: False

North:465,251.1669'

East:633,903.0530'

## Segment# 1: Line

Course: N15°00'00"W

Length: 7.62'

North: 465,258.5272'

East: 633,901.0808'

## Segment# 2: Line

Course: N0°00'00"E

Length: 59.35'

North: 465,317.8772'

East: 633,901.0808'

## Segment# 3: Line

Course: N90°00'00"E

Length: 19.50'

North: 465,317.8772'

East: 633,920.5808'

## Segment# 4: Line

Course: S0°00'00"E

Length: 62.02'

North: 465,255.8572'

East: 633,920.5808'

Segment# 5: Line

Course: S75°00'00"W

Length: 18.14'

North: 465,251.1623'

East: 633,903.0590'

Perimeter: 166.65'

Area: 1,252.60538Sq.Ft.

Error Closure: 0.0075

Course: S51°56'30"E

Error North : -0.00462

East: 0.00590

Precision 1: 22,217.33

---

Parcel Name: LOTS F3 - LOT 222

Description:

Process segment order counterclockwise: False

Enable mapcheck across chord: False

North:465,255.8632'

East:633,920.5798'

Segment# 1: Line

Course: N0°00'00"E

Length: 62.02'

North: 465,317.8832'

East: 633,920.5798'

Segment# 2: Line

Course: N90°00'00"E

Length: 19.50'

North: 465,317.8832'

East: 633,940.0798'

Segment# 3: Line

Course: S0°00'00"E

Length: 56.80'

North: 465,261.0832'

East: 633,940.0798'

Segment# 4: Line

Course: S75°00'00"W

Length: 20.19'

North: 465,255.8576'

East: 633,920.5777'

Perimeter: 158.51'

Area: 1,158.50539Sq.Ft.

Error Closure: 0.0059

Course: S20°10'56"W

Error North : -0.00556

East: -0.00204

Precision 1: 26,866.10

---

Parcel Name: LOTS F3 - LOT 223

Description:

Process segment order counterclockwise: False

Enable mapcheck across chord: False

North:465,261.0882'

East:633,940.0798'

## Segment# 1: Line

Course: N0°00'00"E

Length: 56.80'

North: 465,317.8882'

East: 633,940.0798'

## Segment# 2: Line

Course: N90°00'00"E

Length: 19.50'

North: 465,317.8882'

East: 633,959.5798'

## Segment# 3: Line

Course: S0°00'00"E

Length: 51.57'

North: 465,266.3182'

East: 633,959.5798'

## Segment# 4: Line

Course: S75°00'00"W

Length: 20.19'

North: 465,261.0926'

East: 633,940.0777'

Perimeter: 148.06'

Area: 1,056.61771Sq.Ft.

Error Closure: 0.0049

Course: N24°41'09"W

Error North : 0.00444

East: -0.00204

Precision 1: 30,216.33

---

Parcel Name: LOTS F3 - LOT 224

## Description:

Process segment order counterclockwise: False

Enable mapcheck across chord: False

North:465,272.1556'

East:633,981.3838'

## Segment# 1: Line

Course: S75°00'00"W

Length: 22.57'

North: 465,266.3140'

East: 633,959.5829'

## Segment# 2: Line

Course: N0°00'00"E

Length: 51.57'

North: 465,317.8840'

East: 633,959.5829'

## Segment# 3: Line

Course: N90°00'00"E

Length: 13.50'

North: 465,317.8840'

East: 633,973.0829'

## Segment# 4: Curve

Length: 21.29'

Radius: 35.00'

Delta: 34°51'02"  
Chord: 20.96'  
Course In: N0°00'00"E  
RP North: 465,352.8840'  
End North: 465,324.1614'

Tangent: 10.99'  
Course: N72°34'29"E  
Course Out: S34°51'02"E  
East: 633,973.0829'  
East: 633,993.0832'

## Segment# 5: Line

Course: S0°00'03"E  
North: 465,286.4914'

Length: 37.67'  
East: 633,993.0838'

## Segment# 6: Line

Course: S39°12'04"W  
North: 465,272.1552'

Length: 18.50'  
East: 633,981.3909'

Perimeter: 165.11'  
Error Closure: 0.0071  
Error North : -0.00038

Area: 1,551.97765Sq.Ft.  
Course: S86°57'18"E  
East: 0.00711

Precision 1: 23,253.52

---

Parcel Name: LOTS F3 - TRACT A

Description:

Process segment order counterclockwise: False

Enable mapcheck across chord: False

North:465,415.9374' East:633,976.5774'

## Segment# 1: Line

Course: S0°00'00"E  
North: 465,391.9374'

Length: 24.00'  
East: 633,976.5774'

## Segment# 2: Line

Course: N90°00'00"W  
North: 465,391.9374'

Length: 28.50'  
East: 633,948.0774'

## Segment# 3: Line

Course: N90°00'00"W  
North: 465,391.9374'

Length: 19.50'  
East: 633,928.5774'

## Segment# 4: Line

Course: N90°00'00"W  
North: 465,391.9374'

Length: 19.50'  
East: 633,909.0774'

## Segment# 5: Line

Course: N90°00'00"W

Length: 19.50'

North: 465,391.9374'

East: 633,889.5774'

## Segment# 6: Line

Course: N90°00'00"W

Length: 19.50'

North: 465,391.9374'

East: 633,870.0774'

## Segment# 7: Line

Course: N90°00'00"W

Length: 20.50'

North: 465,391.9374'

East: 633,849.5774'

## Segment# 8: Line

Course: N90°00'00"W

Length: 20.00'

North: 465,391.9374'

East: 633,829.5774'

## Segment# 9: Line

Course: N90°00'00"W

Length: 21.50'

North: 465,391.9374'

East: 633,808.0774'

## Segment# 10: Line

Course: N90°00'00"W

Length: 19.50'

North: 465,391.9374'

East: 633,788.5774'

## Segment# 11: Line

Course: N90°00'00"W

Length: 19.50'

North: 465,391.9374'

East: 633,769.0774'

## Segment# 12: Line

Course: N90°00'00"W

Length: 19.50'

North: 465,391.9374'

East: 633,749.5774'

## Segment# 13: Line

Course: N90°00'00"W

Length: 25.00'

North: 465,391.9374'

East: 633,724.5774'

## Segment# 14: Line

Course: N0°00'00"E

Length: 24.00'

North: 465,415.9374'

East: 633,724.5774'

## Segment# 15: Line

Course: N90°00'00"E

Length: 252.00'

North: 465,415.9374'

East: 633,976.5774'

Perimeter: 552.00'

Area: 6,048.03798Sq.Ft.

Error Closure: 0.0000

Course: N0°00'00"E

Error North : 0.00000

East: 0.00000

Precision 1: 552,000,000.00

---

Parcel Name: LOTS F3 - TRACT B

Description:

Process segment order counterclockwise: False

Enable mapcheck across chord: False

North:465,339.4120'

East:633,829.5774'

Segment# 1: Line

Course: N0°00'00"E

Length: 52.53'

North: 465,391.9420'

East: 633,829.5774'

Segment# 2: Line

Course: N90°00'00"E

Length: 20.00'

North: 465,391.9420'

East: 633,849.5774'

Segment# 3: Line

Course: S0°00'00"E

Length: 48.55'

North: 465,343.3920'

East: 633,849.5774'

Segment# 4: Line

Course: S22°30'00"E

Length: 8.58'

North: 465,335.4652'

East: 633,852.8609'

Segment# 5: Line

Course: S72°01'27"W

Length: 20.06'

North: 465,329.2743'

East: 633,833.7800'

Segment# 6: Line

Course: N22°30'00"W

Length: 10.98'

North: 465,339.4185'

East: 633,829.5782'

Perimeter: 160.69'

Area: 1,206.27720Sq.Ft.

Error Closure: 0.0065

Course: N6°37'55"E

Error North : 0.00648

East: 0.00075

Precision 1: 24,723.08

---

Parcel Name: LOTS F3 - TRACT C

Description:

Process segment order counterclockwise: False

Enable mapcheck across chord: False

North:465,337.8862'

East:633,889.5788'

## Segment# 1: Line

Course: N90°00'00"E

Length: 19.50'

North: 465,337.8862'

East: 633,909.0788'

## Segment# 2: Line

Course: N90°00'00"E

Length: 19.50'

North: 465,337.8862'

East: 633,928.5788'

## Segment# 3: Line

Course: N90°00'00"E

Length: 19.50'

North: 465,337.8862'

East: 633,948.0788'

## Segment# 4: Line

Course: N90°00'00"E

Length: 19.00'

North: 465,337.8862'

East: 633,967.0788'

## Segment# 5: Curve

Length: 23.56'

Radius: 15.00'

Delta: 90°00'00"

Tangent: 15.00'

Chord: 21.21'

Course: N45°00'00"E

Course In: N0°00'00"E

Course Out: N90°00'00"E

RP North: 465,352.8862'

East: 633,967.0788'

End North: 465,352.8862'

East: 633,982.0788'

## Segment# 6: Line

Course: N0°00'00"E

Length: 2.30'

North: 465,355.1862'

East: 633,982.0788'

## Segment# 7: Line

Course: S89°59'25"E

Length: 11.00'

North: 465,355.1843'

East: 633,993.0788'

## Segment# 8: Line

Course: S0°00'03"E

Length: 31.02'

North: 465,324.1643'

East: 633,993.0793'

## Segment# 9: Curve

Length: 21.29'

Radius: 35.00'

Delta: 34°51'02"

Tangent: 10.99'

Chord: 20.96'

Course: S72°34'29"W

Course In: N34°51'02"W

Course Out: S0°00'00"E

RP North: 465,352.8869'

East: 633,973.0790'

End North: 465,317.8869'

East: 633,973.0790'

## Segment# 10: Line

Course: N90°00'00"W

Length: 13.50'

North: 465,317.8869'

East: 633,959.5790'

## Segment# 11: Line

Course: N90°00'00"W

Length: 19.50'

North: 465,317.8869'

East: 633,940.0790'

## Segment# 12: Line

Course: N90°00'00"W

Length: 19.50'

North: 465,317.8869'

East: 633,920.5790'

## Segment# 13: Line

Course: N90°00'00"W

Length: 19.50'

North: 465,317.8869'

East: 633,901.0790'

## Segment# 14: Line

Course: N90°00'00"W

Length: 19.50'

North: 465,317.8869'

East: 633,881.5790'

## Segment# 15: Line

Course: N90°00'00"W

Length: 15.72'

North: 465,317.8869'

East: 633,865.8590'

## Segment# 16: Curve

Length: 4.71'

Radius: 15.00'

Delta: 17°58'33"

Tangent: 2.37'

Chord: 4.69'

Course: S81°00'43"W

Course In: S0°00'00"E

Course Out: N17°58'33"W

RP North: 465,302.8869'

East: 633,865.8590'

End North: 465,317.1547'

East: 633,861.2297'

## Segment# 17: Line

Course: S72°01'27"W

Length: 5.42'

North: 465,315.4820'

East: 633,856.0743'

## Segment# 18: Line

Course: S72°01'27"W

Length: 23.38'

North: 465,308.2666'

East: 633,833.8355'

## Segment# 19: Curve

Length: 3.39'

Radius: 35.00'

Delta: 5°32'29"  
Chord: 3.38'  
Course In: N17°58'33"W  
RP North: 465,341.5581'  
End North: 465,307.3791'

Tangent: 1.69'  
Course: S74°47'41"W  
Course Out: S12°26'04"E  
East: 633,823.0340'  
East: 633,830.5703'

Segment# 20: Curve

Length: 7.60'  
Delta: 12°26'04"  
Chord: 7.58'  
Course In: N12°26'04"W  
RP North: 465,341.5581'  
End North: 465,306.5581'

Radius: 35.00'  
Tangent: 3.81'  
Course: S83°46'58"W  
Course Out: S0°00'00"E  
East: 633,823.0340'  
East: 633,823.0340'

Segment# 21: Line

Course: N90°00'00"W  
North: 465,306.5581'

Length: 11.96'  
East: 633,811.0740'

Segment# 22: Line

Course: N90°00'00"W  
North: 465,306.5581'

Length: 19.50'  
East: 633,791.5740'

Segment# 23: Line

Course: N90°00'00"W  
North: 465,306.5581'

Length: 19.50'  
East: 633,772.0740'

Segment# 24: Line

Course: N90°00'00"W  
North: 465,306.5581'

Length: 19.50'  
East: 633,752.5740'

Segment# 25: Line

Course: N90°00'00"W  
North: 465,306.5581'

Length: 28.00'  
East: 633,724.5740'

Segment# 26: Line

Course: N0°00'00"E  
North: 465,326.5581'

Length: 20.00'  
East: 633,724.5740'

Segment# 27: Line

Course: N90°00'00"E  
North: 465,326.5581'

Length: 25.00'  
East: 633,749.5740'

Segment# 28: Line

Course: N90°00'00"E

Length: 19.50'

North: 465,326.5581'

East: 633,769.0740'

## Segment# 29: Line

Course: N90°00'00"E

Length: 19.50'

North: 465,326.5581'

East: 633,788.5740'

## Segment# 30: Line

Course: N90°00'00"E

Length: 19.50'

North: 465,326.5581'

East: 633,808.0740'

## Segment# 31: Line

Course: N90°00'00"E

Length: 14.96'

North: 465,326.5581'

East: 633,823.0340'

## Segment# 32: Curve

Length: 4.71'

Radius: 15.00'

Delta: 17°58'33"

Tangent: 2.37'

Chord: 4.69'

Course: N81°00'43"E

Course In: N0°00'00"E

Course Out: S17°58'33"E

RP North: 465,341.5581'

East: 633,823.0340'

End North: 465,327.2903'

East: 633,827.6632'

## Segment# 33: Line

Course: N72°01'27"E

Length: 6.42'

North: 465,329.2716'

East: 633,833.7698'

## Segment# 34: Line

Course: N72°01'27"E

Length: 20.06'

North: 465,335.4625'

East: 633,852.8506'

## Segment# 35: Line

Course: N72°01'27"E

Length: 2.31'

North: 465,336.1754'

East: 633,855.0479'

## Segment# 36: Curve

Length: 10.98'

Radius: 35.00'

Delta: 17°58'33"

Tangent: 5.54'

Chord: 10.94'

Course: N81°00'43"E

Course In: S17°58'33"E

Course Out: N0°00'00"E

RP North: 465,302.8838'

East: 633,865.8494'

End North: 465,337.8838'

East: 633,865.8494'

## Segment# 37: Line

Course: N90°00'00"E

Length: 4.22'

North: 465,337.8838'

East: 633,870.0694'

Segment# 38: Line

Course: N90°00'00"E

Length: 19.50'

North: 465,337.8838'

East: 633,889.5694'

Perimeter: 603.51'

Area: 5,601.66180Sq.Ft.

Error Closure: 0.0097

Course: S75°50'58"W

Error North : -0.00237

East: -0.00939

Precision 1: 62,217.53